

EVALUATION OF BOND-CONTROLLED,
EPOXY-COATED PRESTRESSING STRAND
on
HUBBARD CREEK BRIDGE
Bridge No. 3339A

Experimental Features Project OR 84-06

Final Report

by

Allison Petrak
and
Eric W. Brooks

Research Specialists

in collaboration with

Richard L. Groff, P.E.
Structural Design Engineer
and
Jan Six, P.E.
Research Coordinator

OREGON STATE HIGHWAY DIVISION
Materials and Research Section
Salem, Oregon 97310

prepared for

FEDERAL HIGHWAY ADMINISTRATION
Washington D.C. 20590

October 1990

TABLE OF CONTENTS

INTRODUCTION 1

BRIDGE DESCRIPTION 1

EVALUATION PROCEDURE 2

 Preconstruction 3

 Postconstruction 4

 Long Term Performance 4

COST COMPARISON 4

CONCLUSIONS 5

APPENDICES

 A. Finished Deck Grades A-1

 B. Long Term Finished Deck Grades B-1

 C. Inspection Vaults: Strand Measurements C-1

 D. Visual Inspections D-1

 E. Bridge Design Drawings E-1

 Plan and Elevation (Figure 1)

 Inspection Vault Details (Figure 2)

 F. Photographs F-1

ACKNOWLEDGMENT

The authors wish to thank Frank Morrison, Project Manager, Region 3, for providing information on construction procedures and conducting the inspections, and George Wirrick, Morse Bros, for providing information on the castings and prestressing.

DISCLAIMER

The contents of this report reflect the views of the authors who are solely responsible for the facts and the accuracy of the material presented. The contents do not necessarily reflect the official views of the Oregon Department of Transportation. The report does not constitute a standard, specification or regulation.

The Oregon Department of Transportation does not endorse products or manufactures. Trademarks or manufactures' names appear herein only because they are considered essential to the subject of this document.

INTRODUCTION

Oregon's many coastal bridges are subject to a severely corrosive environment, being exposed to frequent rain and fog and a nearly constant misting of salt spray. Heavy rains flush ocean salts off the sides and decks of bridges, but leave the underside covered with salty ocean spray. Because of this spray, coastal bridges are more subject to corrosive attack on the underside than from chlorides applied to the deck. A significant number of coastal bridges are succumbing to the effects of this harsh environment and will be in need of replacement over the next several years.

Prestressed concrete bridges will most likely be chosen to replace these deteriorating structures. Corrosive agents can attack the steel reinforcement contained in prestressed concrete structures, causing tensile stresses which fracture the concrete. Coating the reinforcing steel with epoxy encases and protects the steel from these corrosive agents.

While epoxy coated reinforcing steel has been used successfully to combat corrosion for several years, epoxy coating for prestressing strand is a relatively new development. An NCHRP study titled "Corrosion Protection of Prestressing Systems in Concrete Bridges" (Project 4-15, FY 1982) was conducted to test the mechanical behavior and corrosion resistance of epoxy coated 7-wire strand used in prestensioning applications. The final report for this study (NCHRP Report 313) concluded that epoxy coated prestressed strand was superior to bare strand wire in both corrosion resistance and bond strength. However, a full scale evaluation of girders in service in the appropriate environment, as opposed to laboratory tests and simulations, was considered essential.

BRIDGE DESCRIPTION

Hubbard Creek Bridge, located on the Oregon Coast Highway (US101) one mile south of Port Orford, was chosen as the experimental project bridge. The new bridge is a 138 foot long, single span structure replacing the existing 40 year old bridge. Due to it's proximity to the ocean and its corrosion history, this bridge site was ideal for testing the effectiveness of the epoxy coated prestressing strand.

Seven prestressed bulb-T beams, six feet high and 139 feet long, were used in the construction of the bridge. Each web contained 26 harped strands, with 26 more strands in the bulb section. The low

relaxation, 1/2" diameter, 7-wire strand was specified to have a minimum epoxy coating of 30 mils, with proprietary grit impregnation to increase bonding capacity.

Incorporated into the design of the replacement structure were several features intended to combat the corrosive effects of the marine environment. These features included:

1. The use of 3" minimum concrete cover over the reinforcement wherever practical (everywhere except the precast, prestressed bulb-T girders);
2. The use of a waterproof coating on all exposed concrete surfaces except the roadway;
3. The use of epoxy coated reinforcing bars throughout; and
4. The use of low relaxation, bond-controlled, epoxy coated prestressing strand in the bulb-T girders.

EVALUATION PROCEDURE

The preconstruction evaluation included investigating the condition of the epoxy coated prestressing strand in the yard, and its performance after stressing but before casting of the girders. The constructed girders were also evaluated during placement and periodically for the first five years of service. At each post construction inspection, the web and bottom flange surfaces of the girders were observed for cracking, and the midspan deflection was recorded relative to a fixed frame of reference. Additionally, the creep and the deflection of the girders was monitored. These last two measurements were considered necessary to verify the proper bonding of the strands to the concrete.

Eight strands were left extended in beam number seven (four strands at each end), and the ends of these strands were measured relative to a fixed reference point. Inspection vaults were constructed at both end bents to monitor slippage of the prestressing strands (four at each end). See figure 2 in Appendix E for details on the method of strand measurement.

The five year evaluation period was probably insufficient to evaluate the coating's effectiveness in preventing corrosion, but it was long enough to determine any structural performance problems with girders constructed with epoxy-coated prestressed strands.

PRECONSTRUCTION EVALUATION

On April 10, 1985, inspections were made of the epoxy coated strand as it emerged from the guide ring of its original shipping coil in the plant of the precaster. Most of the strand appeared to be coated uniformly, with a fairly consistent grit impregnation and a surprising range of blue and blue-green colors.

In some areas on one coil, the coating had loose flakes underlaid by a tighter coating layer, with less grit density and less apparent coating thickness between individual wires of the strand. With the removal of the loose material and verification of the underlying coating thickness and integrity, the strands were accepted for use in the middle of the section's bulb.

Due to the abrasive surface of the coated strand, installing the strand after stirrups were in place would damage the epoxy coating. To prevent this, the strands were raised off the stirrups with temporary wooden blocks, which were removed after the strands were in place.

After casting, the epoxy strand could not be released until the concrete surface temperature cooled to approximately 120 degrees F. This caused no delay or additional expense, as the contractor was able to schedule stripping and form work during this time.

A girder, cast the previous day, was inspected for apparent cracking, spalling, and evidence of strand slippage. The initial camber was approximately 4", as compared to the predicted 2-7/8 ". This excessive camber may have been due to excellent bonding or, because of the relatively early release time, the concrete may not have reached the anticipated elastic modulus. In either case, the large camber is indicative of adequate initial bonding.

A small number of very thin vertical cracks were observed near the "dead" end of the beam. These cracks are possibly the result of horizontal friction in the supports resisting shrinkage. Another possibility is stress differential during detensioning in the region where the strands had not developed enough to introduce significant compression into the ends of the member. These cracks were considered insignificant by the State Inspectors.

Camber was measured after the release of the girders, and varied from 3-7/6" to 3-15/16" for all beams. Again, this large camber is indicative of excellent bonding between the strand and concrete. After erection of the girders and before pouring the deck, camber measurements were reasonably consistent with the anticipated long term camber projections.

POST-CONSTRUCTION EVALUATION

Construction of the Hubbard Creek Replacement Bridge was completed September, 1985, as scheduled. As outlined in the workplan, the finished deck grades were regularly monitored. The maximum midspan deflection was 0.08' during the first 5 months immediately following construction. This difference includes deflections that occurred due to the pouring of bridge parapets. Cracking was not observed on the web or bottom flange surfaces of any girder.

Measurements taken on the extended strands showed no measureable movement or slippage had taken place.

LONG TERM MONITORING

Grade measurements on the bridge deck and strand measurements in the inspection vaults were made from 1985 to 1990 by the project manager's field crew. Visual inspections of the bridge were made by the Region 3 Bridge Inspector every two years. There have not been any significant changes measured or observed in the structure during this time period. The maximum deflection recorded over this time period has been 0.05'. No measureable movement or slippage of the epoxy-coated prestressed strands was detected. See Appendixes A-D for the detailed field measurements and inspection reports.

The inspections and monitoring of the deck and the girders have been continued through the fifth year of service. The data from these inspections have been analyzed, and are included in this report.

COST COMPARISON

The epoxy coated strand, "Flo Bond", is only available from Florida Wire and Cable Company. It is approximately \$0.45/lin. ft., compared to \$0.195/lin. ft. for the same strand uncoated. Using the epoxy coated prestressing strand on the Hubbard Creek Replacement Bridge added \$14,030 to the \$134,760 cost of the beams. This increased the total cost of the beams by 10.4% and added 4.3% to the total price of the bridge.

Special chucks and jaws were required to handle the epoxy coated strands at the yard. These tools, while expensive, can be used again on any project utilizing epoxy coated strand. The one time cost of these tools was \$3,043.

No other costs which could be attributed to the use of epoxy coated strands were reported in casting the beams or during the field installation.

CONCLUSIONS

The use of epoxy coated strands caused no significant construction or casting problems. All evidence received supports the conclusion that epoxy coating of the prestressed strand does not cause any short term bonding difficulties. Monitoring was continued for five years during which time no signs of debonding appeared.

The use of epoxy coating on prestressing strand will be considered for all future applications in marine environments. More data will be collected from this project in the future for additional long-term evaluation. Epoxy-coated prestressed strands have also been used in beams on the South Slough (Charleston) Bridge (Experimental Feature 89-06). This project will be evaluated over the next three years and will provide additional data on the use of this type of corrosion prevention technique. Based on information from this study and the NCHRP report the use of epoxy-coated prestressed strands appears to be a beneficial and viable option for use in reducing the corrosion potential of coastal highway bridges.

APPENDIX

APPENDIX B
Finished Deck Grades
1985-1990

Date	20' Lt	±	20' Rt	Party
Computed	52 ⁰⁵	51 ⁷⁵	51 ⁹⁵	
7/3/85	52 ⁰⁶	51 ⁷²	51 ⁹³	Before Parapets
12/16/85	52 ⁰⁵	51 ⁷⁵	51 ⁹¹	
1/29/86	52 ⁰²	51 ⁶⁸	51 ⁹²	
2/19/86	52 ⁰²	51 ⁶⁸	51 ⁹¹	
3/12/86	52 ⁰²	51 ⁶⁹	51 ⁹¹	
3/31/86	52 ⁰²	51 ⁶⁸	51 ⁹¹	
5/28/86	52 ⁰²	51 ⁶⁸	51 ⁹¹	
7/11/86	52 ⁰³	51 ⁷⁰	51 ⁹²	
1/7/87	52 ⁰³	51 ⁶⁹	51 ⁹²	
5/13/87	52 ⁰²	51 ⁶⁹	51 ⁹¹	
7/17/87	52 ⁰²	51 ⁶⁹	51 ⁹⁰	
10/6/87	52 ⁰²	51 ⁷⁰	51 ⁹²	
1/8/88	52 ⁰²	51 ⁶⁸	51 ⁹⁰	
4/28/88	52 ⁰¹	51 ⁶⁸	51 ⁹⁰	
10/3/88	52 ⁰³	51 ⁷⁰	51 ⁹²	
6/14/89	52 ⁰¹	51 ⁶⁸	51 ⁹⁰	
4/13/90	52 ⁰¹	51 ⁶⁹	51 ⁹⁰	Last Monitor

Const. _____ Date _____
 Line Staked _____ Party _____
 Project Hubbard Cr. Br. Monitoring
Sta 67+77.5

5-306
 WESTERN
 SURVEYING CORP.
 FARMINGTON, UTAH

APPENDIX B
Finished Deck Grades
1985-1990

Oregon State Highway Division
LEVEL SHEETS

Sta 68+50

Date	20' L	6	20' R	
Computed	50 ⁴³	49 ⁸²	49 ²¹	
7/3/85	50 ⁴⁸	49 ⁸⁷	49 ³⁵	Before Parapets
12/16/85	50 ³⁹	49 ⁸²	49 ²⁷	
1/29/86	50 ⁴¹	49 ⁸³	49 ²⁹	
2/19/86	50 ⁴⁰	49 ⁸³	49 ²⁹	
3/12/86	50 ⁴¹	49 ⁸³	49 ²⁹	
3/31/86	50 ⁴¹	49 ⁸³	49 ²⁹	
5/28/86	50 ⁴⁰	49 ⁸³	49 ²⁹	
7/11/86	50 ⁴³	49 ⁸⁶	49 ³²	
1/7/87	50 ⁴¹	49 ⁸³	49 ²⁹	
5/13/87	50 ⁴²	49 ⁸³	49 ³⁰	
7/17/87	50 ⁴¹	49 ⁸³	49 ²⁹	
10/6/87	50 ⁴¹	49 ⁸⁴	49 ³⁰	
1/8/88	50 ⁴¹	49 ⁸²	49 ²⁹	
4/28/88	50 ⁴⁰	49 ⁸²	49 ²⁹	
10/3/88	50 ⁴³	49 ⁸⁵	49 ³¹	
6/14/89	50 ⁴⁰	49 ⁸⁴	49 ²⁹	
4/13/90	50 ⁴⁰	49 ⁸⁴	49 ²⁹	Lost Monitor

APPENDIX B

Finished Deck Grades

1985-1990

Const, _____ Date _____
 Line Staked 12/16/85 - 4/13/90 Party _____
 Project Hubbard Cr. Br. Monitoring _____
 Sta. 69+15.5 _____

Date	20' L	E	20' R	
Computed	49 ⁹⁴	48 ⁵⁵	47 ⁶⁶	
7/3/85	49 ⁹⁷	48 ⁵⁸	47 ⁶⁹	Before for 90 ft
12/16/85	49 ⁹⁴	48 ⁵⁵	47 ⁶⁶	
1/29/86	49 ⁹⁴	48 ⁵⁶	47 ⁶⁹	
2/19/86	49 ⁹⁴	48 ⁵⁶	47 ⁶⁹	
3/12/86	49 ⁹⁴	48 ⁵⁵	47 ⁶⁹	
3/31/86	49 ⁹⁴	48 ⁵⁶	47 ⁶⁸	
5/28/86	49 ⁹¹	48 ⁵⁴	47 ⁶⁶	
7/11/86	49 ⁹⁶	48 ⁵⁷	47 ⁷²	
1/7/87	49 ⁹⁴	48 ⁵⁶	47 ⁶⁹	
5/13/87	49 ⁹³	48 ⁵⁵	47 ⁶⁷	
7/17/89	49 ⁹²	48 ⁵⁴	47 ⁶⁷	
10/6/87	49 ⁹³	48 ⁵⁴	47 ⁶⁵	
1/8/88	49 ⁹³	48 ⁵³	47 ⁶⁶	
4/28/88	49 ⁹²	48 ⁵³	47 ⁶⁶	
10/3/88	49 ⁹³	48 ⁵⁴	47 ⁶⁸	
6/14/89	49 ⁹¹	48 ⁵³	47 ⁶⁶	
4/13/90	49 ⁹¹	48 ⁵³	47 ⁶⁶	Last monitor

S-396

W. L. DORRANCE CORP.
 10000 W. 10th St.
 Overland Park, KS 66211

W. L. DORRANCE CORP.
 10000 W. 10th St.
 Overland Park, KS 66211

APPENDIX C
Strand Displacement
(vault layout)

Oregon State Highway Division
TRANSIT SHEET

INSPECTION VAULTS

#1 SE CORNER UPPER	#2 SE CORNER LOWER
LEFT RIGHT	LEFT RIGHT
#3 SW CORNER UPPER	#4 SW CORNER LOWER
LEFT RIGHT	LEFT RIGHT

APPENDIX C
Strand Displacement
(First quarter)

MONITOR		Date		
Line		Staked	12-14-85	
Project		HUBBARD CR. BRIDGE		Party
INSPECTION VAULTS				J. ROWE B. FERRESON S. DOCKINS G. ETHERTON
PLATE	DATE	MOVEMENT		REMARKS
		LEFT	RIGHT	
# 1	11-08-85			INT. READING
SE COR	12-16-85	0.00	0.00	
UPPER	3-31-86	0.00	0.00	
See Next Set of Notes				
# 2	11-08-85			INT. READING
SE COR	12-16-85	0.00	0.00	
LOWER	3-31-86	0.00	0.00	
		//		
# 3	11-08-85			INT. READING
SW COR	12-16-85	0.00	0.00	
UPPER	3-31-86	0.00	0.00	
		//		
# 4	11-08-85			INT. READING
SW COR	12-16-85	0.00	0.00	
LOWER	3-31-86	0.00	0.00	
		//		

APPENDIX C

Strand Displacement

(1985-1990)

LEVEL SHEETS

Oregon State Highway Division

Form 734-3084 SP70635-734

Party

Date Staked

CONST

Project HURBARD CR. BR

INSPECTION VAULT # 67+75.4

INSPECTION VAULT # 69+15.7

DATE	UPPER PLATE		LOWER PLATE		INITIAL	DATE	UPPER PLATE		LOWER PLATE		INITIAL
	UPPER STRAND	LOWER STRAND	UPPER STRAND	LOWER STRAND			UPPER STRAND	LOWER STRAND	UPPER STRAND	LOWER STRAND	
12/16/85	0	0	0	0		12/16/85	0	0	0	0	INITIAL
1/29/86	0	0	0	0		1/29/86	0	0	0	0	
3/12/86	0	0	0	0		3/12/86	0	0	0	0	
5-28-86	0	0	0	0		5-28-86	0	0	0	0	
7-11-86	0	0	0	0		7-11-86	0	0	0	0	
1-7-87	0	0	0	0		1-7-87	0.005	0	0	0	
5-13-87	0	0	0	0		5-13-87	-0.005	0	0	0	
7-13-87	0	0	0	0		7-13-87	-0.005	0	0	0	
10/6/87	0	0	0	0		10/6/87	0	0	0	0	
1-8-88	0	0	0	0		1-8-88	0	0	0	0	
4-28-88	0	0	0	0		4-28-88	0	0	0	0	
10-3-88	-0.005	0	0	0		10-3-88	-0.005	0	0	0	
4-12-90	-0.005	0	-0.02	0		4-12-90	0	0	0	0	

* NOTE: RESTORING STRAND PROCEED (R.D.T.)

APPENDIX D



BRIDGE INSPECTION REPORT OREGON STATE HIGHWAY DIVISION

BRIDGE NO. 03339A

BRIDGE TYPE 158' Prest. RCDG NAME Hubbard Creek (STATE) FAS. FAU. OS) HWY. NO. 009
 CF 162-200 (OVER, UNDER) Creek COUNTY Curry INSP. FREQ. Odd MILE POST 302.28
 DI. CT 07 YEAR BUILT 1942 A.C. (in.) DATE 11/30/85 INSPECTORS' SIGNATURES Larry A. Bowler

		Condition Rating		OBSERVATIONS		Condition Rating		(Rating Guide on back of sheet)	
		AR	OM			AR	OM		
1. END BENTS	Caps		9	1. Stringers				DECK (58)	
	Piles		9	2. Girder or Beams (Bulb-T)			9	1. Deck - Structural Condition	
	Footings		9	3. Floor beams				2. Wearing Surface (AC)	
	Footing Piles		9	4. TRUSSES				3. Deck Joints	
	Backwalls, Bulkheads		9	Chords				4. Curbs, Fallow Guards	
	Wings		9	Web Members				5. Sidewalks	
2. INTERIOR PIERS OR BENTS	Caps			Portals				6. Parapet, Concrete Barrier	
	Columns, Posts			Bracing				7. Railing, Posts	
	Footings			5. Diaphragms, Bridging			9	8. Median Barrier, Railing	
	Footing Piles			6. Bearing Devices			9	9. Paint	
	Piles			7. Paint			9	10. Drains	
	Bracing			8. Rivets or Bolts				11. Lighting Standards	
3. Debris on Seats				9. Weids				12. Utilities	
4. Paint				10. Collision Damage			N	13. Vibrations in Deck	
5. Collision Damage				11. Deflection under Load			9	INSPECTOR'S CONDITION RATING (58)	
6. Scour			N	12. Alignment of Members			9	9	
7. Settlement (Footing or Piling)			9	13. Vibrations under Load			9	APPROACH CONDITION (65)	
INSPECTOR'S CONDITION RATING (60)			9	14. Machinery (Movable Spans)				1. Pavement & Embankment	
ANNEAL & CHAN. PROTECT. (61)				INSPECTOR'S CONDITION RATING (59)			9	2. Shoulder Embankment	
1. Anneal Scour			8	CULVERTS & RETAIN. WALLS (62)				3. Relief Joints	
2. Embankment Erosion			8	1. Barrel or Wall				4. Approach Slab	
3. Drift			8	Concrete				5. Guardrail	
4. Vegetation			8	Steel				INSPECTOR'S CONDITION RATING (65)	
5. Channel Change			N	Timber				SAFETY FEATURES (36)	
6. Fender System				2. Headwall & Parapet				APPR. ALINE (72)	
7. Spur Dikes & Jetties				3. Aprons				SIGNING	
8. Riprap			8	4. Wingwalls				1. Posted Loading	
9. Adequacy of Opening			8	5. Adequacy				2. Legibility	
INSPECTOR'S CONDITION RATING (61)			8	6. Debris				3. Visibility	
				INSPECTOR'S CONDITION RATING (62)				INSPECTOR'S CONDITION RATING	

REMARKS (Key-in to item and number above)

(58-12) On the west side on each end of the bridge is a metal hatch that I would guess to be for utilities. Need a lock on the inspection vault hatch doors. (Br. Inspection Vault)

MAINTENANCE RECOMMENDATIONS

PREFIX	ITEM	COSTS		REPAIRS COMPLETE
		ESTIMATED	ACTUAL	
	Place lock on the inspection vault doors	50 ⁰⁰		