

**EVALUATION OF
GRIT-IMPREGNATED,
EPOXY COATED PRESTRESSING
STRAND ON SOUTH SLOUGH
(CHARLESTON) BRIDGE**

Bridge No. 1940G

Final Report

Experimental Features Project OR 89-06

by

H. Martin Laylor
Senior Research Specialist

OREGON DEPARTMENT OF TRANSPORTATION
Engineering Services Section
Research Unit
Salem, Oregon 97310

prepared for

FEDERAL HIGHWAY ADMINISTRATION
Washington D.C. 20590

April 1995

1. Report No.		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle Evaluation of Grit-Impregnated, Epoxy Coated Prestressing Strand on South Slough (Charleston) Bridge Final Report				5. Report Date April 1995	
				6. Performing Organization Code	
7. Author(s) H. Martin Laylor				8. Performing Organization Report No.	
9. Performing Organization Name and Address Oregon Department of Transportation Research Unit Salem, OR				10. Work Unit No. (TRAIS)	
				11. Contract or Grant No.	
12. Sponsoring Agency Name and Address				13. Type of Report and Period Covered Final Report 1989-1993	
				14. Sponsoring Agency Code	
15. Supplementary Notes					
16. Abstract <p>The use of grit-impregnated, epoxy coated prestressing strand is a relatively new design strategy being used for corrosion abatement on new concrete structures. This application was chosen for the South Slough (Charleston) structure because it is subject to a corrosive environment created by the salt in the marine air. Findings from the evaluation of revealed that:</p> <ol style="list-style-type: none"> 1.) The coated strand was abrasion resistant and that normal handling during fabrication did not damage the coating, 2.) The strands that were monitored did not display significant creep, 3.) Camber measurements appear normal, showing good bonding, and 4.) No cracking of the web or bottom flange was observed. <p>The use of epoxy coated prestressing strand for beams in aggressive chloride-rich environments is recommended as a "permitted alternative".</p>					
17. Key Words PRESTRESSING, EPOXY COATED, GRIT IMPREGNATED			18. Distribution Statement Available through the Oregon Department of Transportation Research Unit		
19. Security Classif. (of this report)		20. Security Classif. (of this page)		21. No. of Pages	22. Price

SI* (MODERN METRIC) CONVERSION FACTORS

APPROXIMATE CONVERSIONS TO SI UNITS

Symbol	When You Know	Multiply By	To Find	Symbol
<u>LENGTH</u>				
in	inches	25.4	millimeters	mm
ft	feet	0.305	meters	m
yd	yards	0.914	meters	m
mi	miles	1.61	kilometers	km
<u>AREA</u>				
in ²	square inches	645.2	millimeters squared	mm ²
ft ²	square feet	0.093	meters squared	m ²
yd ²	square yards	0.836	meters squared	m ²
ac	acres	0.405	hectares	ha
mi ²	square miles	2.59	kilometers squared	km ²
<u>VOLUME</u>				
fl oz	fluid ounces	29.57	milliliters	mL
gal	gallons	3.785	liters	L
ft ³	cubic feet	0.028	meters cubed	m ³
yd ³	cubic yards	0.765	meters cubed	m ³
NOTE: Volumes greater than 1000 L shall be shown in m ³ .				
<u>MASS</u>				
oz	ounces	28.35	grams	g
lb	pounds	0.454	kilograms	kg
T	short tons (2000 lb)	0.907	megagrams	Mg
<u>TEMPERATURE (exact)</u>				
°F	Fahrenheit temperature	5(F-32)/9	Celsius temperature	°C

APPROXIMATE CONVERSIONS FROM SI UNITS

Symbol	When You Know	Multiply By	To Find	Symbol
<u>LENGTH</u>				
mm	millimeters	0.039	inches	in
m	meters	3.28	feet	ft
m	meters	1.09	yards	yd
km	kilometers	0.621	miles	mi
<u>AREA</u>				
mm ²	millimeters squared	0.0016	square inches	in ²
m ²	meters squared	10.764	square feet	ft ²
ha	hectares	2.47	acres	ac
km ²	kilometers squared	0.386	square miles	mi ²
<u>VOLUME</u>				
mL	milliliters	0.034	fluid ounces	fl oz
L	liters	0.264	gallons	gal
m ³	meters cubed	35.315	cubic feet	ft ³
m ³	meters cubed	1.308	cubic yards	yd ³
<u>MASS</u>				
g	grams	0.035	ounces	oz
kg	kilograms	2.205	pounds	lb
Mg	megagrams	1.102	short tons (2000 lb)	T
<u>TEMPERATURE (exact)</u>				
°C	Celsius temperature	1.8 + 32	Fahrenheit	°F



* SI is the symbol for the International System of Measurement

ACKNOWLEDGEMENTS

The author wishes to thank project managers Frank Morrison, Ray Cranston, and their crew for their active role in taking strand and camber measurements. They provided quality information and kept to the time schedule outlined in the workplan. The author would also like to thank Elizabeth Hunt of the Research Unit for reviewing this report.

DISCLAIMER

This document is disseminated under the sponsorship of the Oregon Department of Transportation (ODOT) and the United States Department of Transportation (USDOT) in the interest of information exchange. The State of Oregon and the United States Government assume no liability for its contents or use thereof.

The contents of this report reflect the views of the author, who is responsible for the facts and the accuracy of the data presented herein. The contents do not necessarily reflect the official policies of the ODOT or the USDOT.

The State of Oregon and the United States Government do not endorse products or manufacturers. Trademarks or manufacturers' names appear herein only because they are considered essential to the object of this document.

This report does not constitute a standard, specification or regulation.

This page intentionally left blank.

**EVALUATION OF GRIT-IMPREGNATED, EPOXY
COATED PRESTRESSING STRAND ON SOUTH
SLOUGH (CHARLESTON) BRIDGE**

TABLE OF CONTENTS

1.0	INTRODUCTION	1
1.1	Background	1
1.2	Objectives	1
2.0	BRIDGE DESCRIPTION	3
3.0	RESULTS	5
3.1	Fabrication	5
3.2	Creep Measurements	5
	3.2.1 Group One Strand Measurements	5
	3.2.2 Group Two Strand Measurements	6
	3.2.3 Group Three Strand Measurements	6
3.3	Camber Measurements	7
	3.3.1 Camber Measurements Taken at the Casting Plant	7
	3.3.2 Camber Measurements Taken In-Place	7
3.4	Crack Inspection	7
4.0	CONCLUSIONS	9
5.0	RECOMMENDATIONS	9
6.0	REFERENCES	11

APPENDIX A: Plan Details

APPENDIX B: Field Survey Results Used in Camber Calculations

LIST OF FIGURES

Figure 2.1	Project Location	3
------------	------------------------	---

**EVALUATION OF GRIT-IMPREGNATED, EPOXY
COATED PRESTRESSING STRAND ON SOUTH
SLOUGH (CHARLESTON) BRIDGE**

LIST OF TABLES

Table 3.1	Group One Strand Measurements	5
Table 3.2	Group Two Strand Measurements	6
Table 3.3	Group Three Strand Measurements	6
Table B-1	Top Deck Elevations-In Feet	B-1
Table B-2	Beam 1-1 Elevation Readings-In Feet	B-2

1.0 INTRODUCTION

1.1 Background

Oregon's coastal bridges are subject to a corrosive environment because of the salt in the marine air. A significant number of coastal bridges are showing the effects of this harsh environment and will be in need of rehabilitation or replacement over the next several years. If the replacement option is selected, prestressed concrete bridges will most likely be used. In this case, some form of corrosion protection for the pre-stressing steel will be required.

1.2 Objectives

The objective of this study was to evaluate the differences between beams made with a grit-impregnated, epoxy coated, pre-stressing strand and uncoated strand. This was done by performing an inspection during fabrication, monitoring the pre-stressing cables for creep, visually inspecting the beams for cracks and measuring camber.

This page intentionally left blank.

2.0 BRIDGE DESCRIPTION

The South Slough Bridge (Bridge No. 1940G) is located on the Cape Arago Highway (Highway 240) in Coos County. The structure, a coastal bridge, is subject to a corrosive environment. A vicinity map showing the project location is in Figure 2.1.

The deck is approximately 1192 feet (360 m) long and has bascule spans near the center to allow ocean vessels passage into the slough. General bridge design drawings are in Appendix A.




Figure 2.1 Project Location

This page intentionally left blank.

3.0 RESULTS

3.1 Fabrication

Handling and stressing characteristics of the strand were observed during fabrication of beam 1-1. The coated strand was found to be abrasion resistant and normal handling during fabrication did not damage the coating (1).

3.2 Strand Measurements

So that strand measurements could be taken from a given reference point throughout the evaluation, reference clamps were mounted on each of two protruding strands. However, these reference points were changed three times because the reference clamps were damaged. When the beam was in place, strand measurements were taken from the beam wall to the tip of strand.

Presented for comparison are three groups of strand measurements. Although comparisons cannot be made between groups, comparisons can be made within each group over the limited time segment.

3.2.1 Group One Strand Measurements:

Group one includes the first set of strand measurements taken shortly after the beam was fabricated and periodically during the next six days. These measurements were taken from the first set of reference clamps (Table 3.1). These show that the epoxy coated strand had a good initial bond with the concrete. The change over time is within the expected tolerances.

Table 3.1: Group One Strand Measurements

STRAND MEASUREMENTS (IN.)										
DATE	2/15/90		2/16/90		2/16/90		2/19/90		2/20/90	
TIME	8:30 AM		8:00 AM		12:00 NOON		9:00 AM		9:00 AM	
TEMP.	NA		36°F		40°F		29°F		42°F	
	Top	Bottom	Top	Bottom	Top	Bottom	Top	Bottom	Top	Bottom
	.517	.569	.513	.571	.516	.568	.512	.566	.512	.567
	.518	.570	.513	.571	.515	.569	.515	.569	.513	.568
	.518	.568	.514	.575	.516	.569	.514	.569	.513	.569
	.519	.569	.513	.568	.516	.568	.511	.570	.512	.569
			.513	.571	.515	.568	.513	.569	.513	.567
AVG.	.518	.569	.513	.571	.516	.568	.513	.569	.513	.568

3.2.2 Group Two Strand Measurements:

Group two strand measurements were taken periodically while the beam was stored at the casting plant. These measurements were taken from a second set of reference clamps and are shown in Table 3.2. Group two measurements, taken over a ninety day period, do not reveal any significant slippage.

Table 3.2: Group Two Strand Measurements

STRAND MEASUREMENTS (IN.)						
DATE	3/2/90		3/6/90		5/30/90	
TIME	9:30 AM		10:00 AM		(Shipping Date)	
TEMP	50°F		50°F		NA	
	Top	Bottom	Top	Bottom	Top	Bottom
	.578	.509	.577	.513	.577	.512
	.578	.509	.577	.513		
	.576	.508	.577	.513		
	.579	.510	.578	.513		
	.579	.510	.578	.513		
AVG.	.578	.509	.577	.513		

3.2.3 Group Three Strand Measurements:

A third group of strand measurements were taken after the beam was in place. These measurements are of the whole protruding strand length rather than from a reference point and are reported in Table 3.3. These measurements do not show any slippage.

Table 3.3: Group Three Strand Measurements

STRAND MEASUREMENTS (FT.)				
DATE	7/17/91	1/31/92	10/8/92	6/15/93
TOP STRAND	.84	.83	.84	.84
BOTTOM STRAND	1.51	1.50	1.51	1.50

3.3 Camber Measurements

3.3.1 Camber Measurements Taken at the Casting Plant

Initial camber measurements were taken shortly after release. Additional camber measurements were taken 10 days later and again prior to the beam being shipped to the construction site approximately 100 days later. The results were as follows:

Beam camber at release.(2/15/90) = 1 9/16 inch

After beam was moved to storage.(2/26/90) = 1 13/16 inch

Before shipping to bridge site.(5/30/90) = 2 11/32 inch

3.3.2 Camber Measurements Taken In-Place

Camber measurements were taken from the bottom of the in-place beam, on the dates shown. Camber readings appear normal, showing good bonding. Field survey measurements used to figure camber are in Tables B-1 and B-2 of Appendix B.

<u>Date:</u>	<u>6/28/91</u>	<u>1/13/92</u>	<u>7/28/92</u>	<u>6/15/93</u>
Camber:	1 2/3 inch	1 2/3 inch	1 1/3 inch	1 1/3 inch

3.4 Crack Inspection

The beam at release did not have any visible cracks. Crack inspections were performed by the project manager's crew after construction and no cracking was reported. A final crack inspection was performed on June 15, 1993. Along with beam 1-1, the web and bottom flange of beams 1-2, 1-3, 1-4, 1-5, and 1-6 were also inspected. No cracking was observed.

This page intentionally left blank.

4.0 CONCLUSIONS

This is the second evaluation of beams made with grit-impregnated, epoxy coated prestressing strand. The first project was the Hubbard Creek Bridge (1,2). Information from both of these projects supports the conclusion that epoxy coated prestressing strand does not cause any short term problems with beam performance.

The following conclusions can be made:

1. The use of epoxy coated strands caused no significant construction or casting problems.
2. Cable movement with respect to the concrete was not detectable.
3. The camber before and after erection was very similar to what is expected for beams made with uncoated wire.
4. There was no cracking found in the beams.

5.0 RECOMMENDATIONS

The use of epoxy coated prestressing strand for beams in aggressive chloride-rich environments is recommended as a "permitted alternative".




This page intentionally left blank.

6.0 REFERENCES

1. Rusnak, James "Evaluation of Grit-Impregnated Epoxy Coated Prestressing Strand on South Slough (Charleston) Bridge, Bridge No. 1940G", December 1991.
2. Petrak, Allison and Brooks, Eric W.; "Evaluation of Bond-Controlled Epoxy-Coated Prestressing Strand on Hubbard Creek Bridge." October 1990.

This page intentionally left blank.

APPENDIX A
PLAN DETAILS



BRIDGE NO. 28 SOUTH SLOUGH (CHARLESTON) BRIDGE SEC. CAPE ARAGO HIGHWAY COOS COUNTY

GENERAL PLAN


APPROVED: *(Signature)* R.G. Elliott
DESIGNED: R.G. Elliott
CHECKED: R.G. Elliott
DATE: DEC 28, 1959
BRIDGE NO. 28-1959 CALC. BOOK 19-59 SHEET 41 OF 47

FUNCTION SPECIFICATIONS


GENERAL NOTES:

- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE BRIDGE DESIGN SPECIFICATIONS FOR STEEL BEAM BRIDGES, 1945 EDITION, AS REVISED BY THE FEDERAL BUREAU OF ROAD RESEARCH, PUBLISHED IN 1950.
- ALL DIMENSIONS SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED.
- ALL STRUCTURAL STEEL SHALL BE ASTM A36, UNLESS OTHERWISE SPECIFIED.
- ALL WELDS SHALL BE IN ACCORDANCE WITH THE BRIDGE DESIGN SPECIFICATIONS, SECTION 6.00.
- ALL FOUNDATION SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED.
- ALL EARTH RETENTION SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED.
- ALL UTILITIES SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED.
- ALL DIMENSIONS SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED.
- ALL MATERIALS SHALL BE AS SPECIFIED UNLESS OTHERWISE SPECIFIED.
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE BRIDGE DESIGN SPECIFICATIONS, 1945 EDITION, AS REVISED BY THE FEDERAL BUREAU OF ROAD RESEARCH, PUBLISHED IN 1950.
- ALL DIMENSIONS SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED.
- ALL STRUCTURAL STEEL SHALL BE ASTM A36, UNLESS OTHERWISE SPECIFIED.
- ALL WELDS SHALL BE IN ACCORDANCE WITH THE BRIDGE DESIGN SPECIFICATIONS, SECTION 6.00.
- ALL FOUNDATION SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED.
- ALL EARTH RETENTION SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED.
- ALL UTILITIES SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED.
- ALL DIMENSIONS SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED.
- ALL MATERIALS SHALL BE AS SPECIFIED UNLESS OTHERWISE SPECIFIED.
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE BRIDGE DESIGN SPECIFICATIONS, 1945 EDITION, AS REVISED BY THE FEDERAL BUREAU OF ROAD RESEARCH, PUBLISHED IN 1950.


APPROVED: *[Signature]*
 DATE 12/10/99
 CHECKED: *[Signature]*
 DATE 2/1/00
 DESIGNED: *[Signature]*
 DATE 12/10/99




END VIEW, BEAM 1-1
Scale: 1/2" = 1'-0"




SECTION A-A
Scale: 1/2" = 1'-0"



SECTION B-B
Scale: 1/2" = 1'-0"



PLAN - BENT 1
Scale: 1/2" = 1'-0"



PLAN - SECTION
Scale: 1/2" = 1'-0"

NOTE:
 For notes not shown, see "General Notes" Aug 1990

Note:
 1. Use cover plates externally for post-tensioning.

2. See Access Hole Cover Note, see drawing 29725

APPENDIX B

**FIELD SURVEYS RESULTS USED
IN CHAMBER CALCULATIONS**

**TOP DECK ELEVATIONS - IN FEET
BENCH MARK AT 15.39 FEET
STATION 0+00 IS AT WEST END OF GIRDER**

Table B-1

STATION	ELEVATION			
	6-15-91	1-13-92	7-28-92	6-15-93
0+00	15.26	15.36	15.39	15.39
0+10	15.61	15.61	15.60	15.62
0+20	15.85	15.86	15.85	15.87
0+30	16.10	16.11	16.09	16.12
0+40	16.41	16.42	16.41	16.43
0+50	16.71	16.73	16.71	16.74
0+60	17.05	17.04	17.03	17.05
0+70	17.36	17.36	17.35	17.37
0+80	17.70	17.70	17.67	17.71
0+90	18.04	18.05	18.01	18.05
0+98 <u>02</u>	18.36	18.36	18.35	18.36

**BEAM 1-1 ELEVATION READINGS - IN FEET
TAKEN FROM BOTTOM OF GIRDER
STATION 0+00 IS AT EAST END OF GIRDER**

Table B-2

STATION	ELEVATION			
	6-18-91	1-13-92	7-28-92	6-15-93
0+10	11.93	11.93	11.89	11.95
0+20	11.63	11.65	11.61	11.67
0+30	11.34	11.36	11.32	11.38
0+40	11.08	11.07	11.04	11.09
0+50	10.78	10.78	10.73	10.80
0+60	10.48	10.47	10.45	10.49
0+70	10.17	10.18	10.13	10.19
0+80	9.84	9.84	9.81	9.86
0+90	9.53	9.53	9.50	9.55
0+95	9.36	9.36	9.34	NA