

Design and Performance Verification of a Bridge Column/Footing/Pile System for Accelerated Bridge Construction (ABC)

Final Report
March 2020



IOWA STATE UNIVERSITY
Institute for Transportation

Sponsored by
Iowa Highway Research Board
(IHRB Project TR-673)
Iowa Department of Transportation
(InTrans Project 14-495)

About the Bridge Engineering Center

The mission of the Bridge Engineering Center (BEC) is to conduct research on bridge technologies to help bridge designers/owners design, build, and maintain long-lasting bridges.

About the Institute for Transportation

The mission of the Institute for Transportation (InTrans) at Iowa State University is to develop and implement innovative methods, materials, and technologies for improving transportation efficiency, safety, reliability, and sustainability while improving the learning environment of students, faculty, and staff in transportation-related fields.

Iowa State University Nondiscrimination Statement

Iowa State University does not discriminate on the basis of race, color, age, ethnicity, religion, national origin, pregnancy, sexual orientation, gender identity, genetic information, sex, marital status, disability, or status as a US veteran. Inquiries regarding nondiscrimination policies may be directed to the Office of Equal Opportunity, 3410 Beardshear Hall, 515 Morrill Road, Ames, Iowa 50011, telephone: 515-294-7612, hotline: 515-294-1222, email: eooffice@iastate.edu.

Disclaimer Notice

The contents of this report reflect the views of the authors, who are responsible for the facts and the accuracy of the information presented herein. The opinions, findings and conclusions expressed in this publication are those of the authors and not necessarily those of the sponsors.

The sponsors assume no liability for the contents or use of the information contained in this document. This report does not constitute a standard, specification, or regulation.

The sponsors do not endorse products or manufacturers. Trademarks or manufacturers' names appear in this report only because they are considered essential to the objective of the document.

Iowa DOT Statements

Federal and state laws prohibit employment and/or public accommodation discrimination on the basis of age, color, creed, disability, gender identity, national origin, pregnancy, race, religion, sex, sexual orientation or veteran's status. If you believe you have been discriminated against, please contact the Iowa Civil Rights Commission at 800-457-4416 or Iowa Department of Transportation's affirmative action officer. If you need accommodations because of a disability to access the Iowa Department of Transportation's services, contact the agency's affirmative action officer at 800-262-0003.

The preparation of this report was financed in part through funds provided by the Iowa Department of Transportation through its "Second Revised Agreement for the Management of Research Conducted by Iowa State University for the Iowa Department of Transportation" and its amendments.

The opinions, findings, and conclusions expressed in this publication are those of the authors and not necessarily those of the Iowa Department of Transportation.

Technical Report Documentation Page

1. Report No. IHRB Project TR-673	2. Government Accession No.	3. Recipient's Catalog No.	
4. Title and Subtitle Design and Performance Verification of a Bridge Column/Footing/Pile System for Accelerated Bridge Construction (ABC)		5. Report Date March 2020	
		6. Performing Organization Code	
7. Author(s) Zhao Cheng (https://orcid.org/0000-0002-8354-3988), Sri Sritharan (orcid.org/0000-0001-9941-8156), and Jeremy Ashlock (orcid.org/0000-0003-0677-9900)		8. Performing Organization Report No. InTrans Project 14-495	
9. Performing Organization Name and Address Bridge Engineering Center Iowa State University 2711 South Loop Drive, Suite 4700 Ames, IA 50010-8664		10. Work Unit No. (TRAIS)	
		11. Contract or Grant No.	
12. Sponsoring Organization Name and Address Iowa Highway Research Board Iowa Department of Transportation 800 Lincoln Way Ames, IA 50010		13. Type of Report and Period Covered Final Report	
		14. Sponsoring Agency Code IHRB Project TR-673	
15. Supplementary Notes Visit www.intrans.iastate.edu for color pdfs of this and other research reports.			
16. Abstract <p>The use of prefabricated components has been continuously gaining momentum in bridge construction because of its numerous advantages over conventional cast-in-place construction methods. However, there are few, if any, projects that have utilized prefabricated components to construct the entire bridge column/footing/pile system because the sufficiency of suitable connections has not been adequately studied to ensure satisfactory performance at the system level. Therefore, this study was conducted to investigate a prefabricated bridge pier system suitable for accelerated bridge construction (ABC). The proposed system consists of a precast column, a precast pile cap, and steel H-piles. These components are integrally connected utilizing a column socket connection and pile socket connections that are preformed in the pile cap with corrugated steel pipes.</p> <p>An experimental study was performed using eight specimens that modeled the full-scale connection interfaces, demonstrating that side shear strength in the column socket connection is sufficient to transfer large vertical loads from the column to the pile cap. Using a recently built bridge as the prototype, an outdoor test was subsequently conducted at half-scale, modeling a column/footing/pile system at a cohesive soil site. The footing in the test unit was supported by four vertical steel H-piles and four battered steel H-piles. To evaluate the system performance as well as the behavior of various connections and pile foundation, the test unit was subjected to different combinations of vertical and lateral loads. Throughout the test, the socket connections maintained fixity, confirming that the proposed system is an excellent alternative for routine use in accelerated bridge construction.</p>			
17. Key Words accelerated bridge construction (ABC)—bridge column/footing/pile system—outdoor test—precast column—precast pile cap—steel H-pile—socket connection—soil-foundation-structure interaction		18. Distribution Statement No restrictions	
19. Security Classification (of this report) Unclassified.	20. Security Classification (of this page) Unclassified.	21. No. of Pages 116	22. Price NA

DESIGN AND PERFORMANCE VERIFICATION OF A BRIDGE COLUMN/FOOTING/PILE SYSTEM FOR ACCELERATED BRIDGE CONSTRUCTION (ABC)

**Final Report
March 2020**

Principal Investigator

Sri Sritharan, Wilkinson Chair of Interdisciplinary Engineering
Civil, Construction, and Environmental Engineering, Iowa State University

Co-Principal Investigator

Jeremy Ashlock, Richard L. Handy Associate Professor
Civil, Construction, and Environmental Engineering, Iowa State University

Research Assistants

Zhao Cheng

Authors

Zhao Cheng, Sri Sritharan, and Jeremy Ashlock

Sponsored by

Iowa Department of Transportation and
Iowa Highway Research Board
(IHRB Project TR-673)

Preparation of this report was financed in part
through funds provided by the Iowa Department of Transportation
through its Research Management Agreement with the
Institute for Transportation
(InTrans Project 14-495)

A report from

**Bridge Engineering Center
Iowa State University**

2711 South Loop Drive, Suite 4700

Ames, IA 50010-8664

Phone: 515-294-8103 / Fax: 515-294-0467

www.bec.iastate.edu

TABLE OF CONTENTS

ACKNOWLEDGMENTS	ix
EXECUTIVE SUMMARY	xi
CHAPTER 1. INTRODUCTION	1
1.1. Background	1
1.2. Objectives and Scope	2
1.3. Report Organization	2
CHAPTER 2. LITERATURE REVIEW	3
2.1. ABC and Precast Elements	3
2.2. Precast Frame Pier	4
2.3. Connections for Precast Frame Pier	5
2.4. Design of Socket Connection	12
2.5. Construction of Socket Connection	15
CHAPTER 3. PROPOSED BRIDGE COLUMN/FOOTING/PILE SYSTEM	17
3.1. Column Socket Connection and Pile Socket Connection	17
3.2. Assembly of Precast Frame Pier	17
CHAPTER 4. COLUMN SOCKET CONNECTION TEST	20
4.1. Test Unit Design	21
4.2. Test Unit Construction	24
4.3. Test Protocol	26
4.4. Test Setup	26
4.5. Instrumentation	27
4.6. Test Results	28
4.7. Discussion	35
CHAPTER 5. OUTDOOR SYSTEM TEST	36
5.1. Geotechnical Site Conditions	36
5.2. Test Unit Design	44
5.3. Test Unit Construction	46
5.4. Test Setup	54
5.5. Load Protocol	58
5.6. Instrumentation	60
5.7. Test Results	65
5.8. Discussion	91
CHAPTER 6. SUMMARY AND CONCLUSIONS	93
REFERENCES	95
APPENDIX. TEST UNIT DRAWINGS	97

LIST OF FIGURES

Figure 1.1. Use of precast elements in Iowa bridge construction	1
Figure 2.1. Bridge piers	4
Figure 2.2. Precast frame piers: US 6 Bridge over Keg Creek (left) and US 12 Bridge over I-5 at Grand Mound (right)	5
Figure 2.3. Bar coupler types	6
Figure 2.4. Connection details using grouted splice sleeves	6
Figure 2.5. Column-to-footing connections with bar couplers	7
Figure 2.6. Column-to-footing connections with grouted ducts	8
Figure 2.7. Socket connections with CIP footings.....	9
Figure 2.8. Socket connections with precast members	9
Figure 2.9. Jointed connections	11
Figure 2.10. Precast cap to pile connections.....	12
Figure 2.11. Stresses and reinforcement in socket connection: stresses in socket connection under lateral loading (left) and circular reinforcement (right)	13
Figure 2.12. Top reinforcement in footing.....	14
Figure 3.1. Sockets on precast pile cap.....	17
Figure 3.2. Assembly process of precast frame pier.....	19
Figure 4.1. Axial strength of fully penetrated socket connection (left) and partially penetrated socket connection (right)	20
Figure 4.2. Details of socket connection test specimen	23
Figure 4.3. Reinforcing cage and CSP installation for foundation	24
Figure 4.4. Form liner used to create fluted fins on the column.....	24
Figure 4.5. Comparison of trial specimens	25
Figure 4.6. Columns with different surface roughness	25
Figure 4.7. Test setup for socket connection tests	26
Figure 4.8. Configuration of instrumentations (left) and measurement variables (right).....	27
Figure 4.9. LED markers capturing Δ_{grout}	27
Figure 4.10. Failure modes of the specimens	28
Figure 4.11. Overall response of each test specimen.....	30
Figure 4.12. Comparisons of connection responses: (a) GF displacement responses for all specimens, (b) CG displacement responses for specimens with different column surface textures, and (c) CG displacement responses for specimens with different CSP-to-column clearances	31
Figure 4.13. Impact of cyclic loading	32
Figure 4.14. Strain readings versus depths below the top of socket.....	34
Figure 5.1. Locations of CPTs and SPTs.....	36
Figure 5.2. CPT logs for the test site	39
Figure 5.3. SPT boring logs	43
Figure 5.4. Frame pier of the prototype bridge.....	44
Figure 5.5. Column reinforcing cage (left) and joint reinforcing bars (right)	46
Figure 5.6. Formwork for column.....	47
Figure 5.7. Completed precast column (left) and exposed aggregate finish (right)	48
Figure 5.8. Installation details of threaded rods.....	48
Figure 5.9. CSPs and wood locks	49

Figure 5.10. Non-reusable reducer (left), 2 in. × 4 in. reducer supports (center), and reusable reducer (right)	49
Figure 5.11. Plywood for closing the CSP with CSP hanger.....	50
Figure 5.12. Pile cap before concrete pour	50
Figure 5.13. Taking out reusable reducers.....	51
Figure 5.14. Completed precast pile cap.....	51
Figure 5.15. Driven pile template	51
Figure 5.16. Weld-splicing piles.....	52
Figure 5.17. Friction collars and plywood seal-pads	52
Figure 5.18. Nut shimmers underneath column (left) and temporary column bracing (right)	53
Figure 5.19. Grout pouring	53
Figure 5.20. Completed test unit.....	54
Figure 5.21. Vertical reaction frame	54
Figure 5.22. Placing main reaction beam.....	55
Figure 5.23. Single friction pendulum isolator between column and reaction beam	55
Figure 5.24. Lateral reaction column.....	56
Figure 5.25. Precast column segment	56
Figure 5.26. Drilled shaft details.....	57
Figure 5.27. Construction of drilled shaft.....	57
Figure 5.28. Lateral actuator attached on reaction column.....	58
Figure 5.29. Test protocol for Phase I and Phase II.....	59
Figure 5.30. Loading protocol for test Phases III through VI.....	60
Figure 5.31. Strain gauges on column reinforcements	61
Figure 5.32. Strain gauges on CSPs of column socket and pile sockets.....	61
Figure 5.33. Strain gauges on pile cap reinforcements.....	62
Figure 5.34. Strain gauges on embedded piles	63
Figure 5.35. Strain gauges on the piles driven into ground	63
Figure 5.36. Layout and location of BDI strain transducers.....	64
Figure 5.37. Layout of displacement transducers	65
Figure 5.38. Layout of markers for NDI optical measurement system	65
Figure 5.39. Pile nomenclature	66
Figure 5.40. Column drift at the end of Phase I (left) and Phase II (right).....	66
Figure 5.41. Damage at the column base: flexural cracks (left) and cover concrete spalling (right).....	67
Figure 5.42. Buckling of longitudinal reinforcing bar.....	67
Figure 5.43. Column base at the end of Phase II	68
Figure 5.44. No damage on column connection (left) and pile connection at the end of Phase I, (right).....	68
Figure 5.45. Crack at column-to-grout pour interface	69
Figure 5.46. Spalling of grout closure pour at the end of Phase II	69
Figure 5.47. Observations of the piles and their connections	70
Figure 5.48. Vertical load as a function of column top displacement	71
Figure 5.49. Lateral load acting on test unit	71
Figure 5.50. Moments estimated at the section 48 in. above top of the pile cap	72
Figure 5.51. Calculation of column lateral resistance.....	73
Figure 5.52. Column base moment versus column lateral displacement.....	73

Figure 5.53. Lateral load-displacement response measured at pile cap.....	74
Figure 5.54. Moment rotation response measured at pile cap	76
Figure 5.55. Pile head moment as a function of moment at the bottom of the pile cap	77
Figure 5.56. Pile axial force as a function of moment at the bottom of the pile cap	78
Figure 5.57. Pile vertical displacement with respect to the pile cap.....	79
Figure 5.58. Pile rotation with respect to the pile cap	80
Figure 5.59. Strain history of column longitudinal reinforcement	82
Figure 5.60. Strain profile along two column longitudinal reinforcements for Phase I	83
Figure 5.61. Strain profile along two column longitudinal reinforcements for Phase II.....	83
Figure 5.62. Strain profile of column socket CSP for Phase I.....	84
Figure 5.63. Strain profile of column socket CSP for Phase II.....	85
Figure 5.64. Strain history of pile cap reinforcement perpendicular to the loading direction	86
Figure 5.65. Strain profile of pile cap reinforcement perpendicular to the loading direction	86
Figure 5.66. Strain history of pile cap reinforcement parallel to the loading direction	87
Figure 5.67. Strain profile of pile cap reinforcement parallel to the loading direction	88
Figure 5.68. Strain history of headed reinforcement in the pile cap.....	88
Figure 5.69. Strain profile of headed reinforcement in the pile cap	89
Figure 5.70. Strain history of embedded pile head	90
Figure 5.71. Strain profile of embedded pile head.....	90
Figure 5.72. Components of column top displacement (left) and their proportions for Phase I and Phase II (right)	92

LIST OF TABLES

Table 2.1. Precast elements for ABC.....	3
Table 4.1. CSP-to-column clearances for common size precast columns	22
Table 4.2. Testing matrix	23

ACKNOWLEDGMENTS

The authors would like to thank the Iowa Highway Research Board (IHRB) and the Iowa Department of Transportation for sponsoring this research. The authors acknowledge the members of the technical advisory committee: Ahmad Abu-Hawash, Michael Nop, Linda Narigon, Vanessa Goetz, Dean Bierwagen, Mark Dell, Kyle Frame, Chris Cromwell, James Nelson, and Gary Novey, for their advice and suggestions.

EXECUTIVE SUMMARY

Problem Statement

A full substructure system involving prefabricated bridge columns, footings (or pile caps), and piles has not been used in practice because of the lack of suitable connections and performance validation of such a system.

Objectives

- Develop a bridge column/footing/pile system that can be implemented economically and effectively using accelerated bridge construction (ABC) methodologies
- Validate the performance of the proposed connection details through laboratory tests
- Validate system performance through an outdoor test with consideration of soil-foundation-structure interaction
- Formulate design recommendations and details based on test results

Background

About one in five bridges in Iowa were designated as structurally deficient in 2019 and require significant maintenance, rehabilitation, or replacement. ABC using prefabricated bridge components helps to improve the condition of bridges as it allows for faster and better repairs or bridge replacements. The Iowa Department of Transportation (DOT) has successfully implemented prefabricated components in bridge superstructure construction.

Research Description

Proposed Bridge Column/Footing/Pile System

A precast pile cap was used to build the bridge column/footing/pile system for ABC. The sockets were created within the footing using corrugated steel pipes (CSPs). The system was assembled by embedding the precast column and steel piles into the sockets using grout and self-consolidating concrete (SCC), respectively. The column socket was constructed to partially penetrate the pile cap, and the pile sockets were made in the shape of a cone and installed through the pile cap.

To construct the system, both vertical and battered steel piles were driven, and then temporary friction collars were affixed to each pile. The precast pile cap was supported on the friction collars, allowing the piles to be extended into the pile sockets. After erecting and bracing the precast column, the sockets were filled with grout and SCC, respectively.

The friction collars were designed to carry the weights of the precast components until the SCC reached adequate strength. Given that, superstructure construction could begin the day after

completing the closure pours, at which point the high early-strength grout reached the specified compressive strength of 6,500 psi.

Column Socket Connection Tests

The socket connection test was conducted to help determine the key connection parameters and side shear strength for designing the column socket connection. Eight specimens were tested to investigate the effects of the parameters that most influence the strength:

- Surface texture along the embedded length of the precast column
- Clearance between the embedded member and the CSP
- Loading type

Each specimen consisted of a short precast column segment and precast foundation. The surface textures of the column segment specimens included an exposed aggregate finish, a 0.5 in. fluted fin, a 0.75 in. fluted fin, and a smooth finish as a reference. Two clearances, of 1.5 in. and 3 in., were reserved around the column segments.

Compressive force was applied to the top of the column segment so that side shear strength could be evaluated by loading the column until it experienced a sliding failure with respect to the foundation. Four specimens were tested using monotonic loading; whereas, the other four specimens were subjected to cyclic loading.

Outdoor System Test

An outdoor system test was conducted to investigate the performance of the proposed substructure assembly. The unique features of the outdoor system test included the following:

- Incorporation of foundation flexibility in virgin soil
- Use of steel H-piles
- Inclusion of battered piles
- Use of large vertical loads in an outdoor lateral load test

A half-scale test unit was constructed at an outdoor location consisting predominantly of cohesive soil. The test unit incorporated a precast column, a precast pile cap, and eight steel H-piles, including a battered pile in each of the four corners of the pile cap at a slope of 1:6 (horizontal to vertical).

A partially penetrated socket and eight fully penetrated sockets were designed for the pile cap. The column end was roughened to an exposed aggregate finish and embedded into the column socket connection over a length equal to the column diameter. Consistent with current practice, the pile embedment length into the pile cap was 1.5 times the depth of the pile.

The outdoor system subassembly unit was tested under different combinations of vertical and lateral loads. A vertical reaction frame and a lateral reaction column were constructed next to the test unit to apply the vertical and lateral loads simultaneously. For the first two phases, the lateral load was applied at the top of the column to produce a high overturning moment-to-lateral load ratio. For the remainder of the testing phases, the lateral load was applied to the pile cap to fully examine the pile socket connections.

Key Findings

Column Socket Connection Tests

- With the exception of the specimen with the smooth column surface, the specimens provided significant and comparable side shear strengths against the axial loads applied to the column segments.
- The specimens consisted of column segments with deep amplitude surface textures exhibited softer connection responses. A thicker grout closure pour (resulting from wider CSP-to-column clearance) also marginally reduced the stiffness of the socket connection.
- Considering the cost and ease of construction, exposed aggregate for embedded member surface preparation, standard CSP, and high-strength grout are recommended for effectively establishing socket connections.
- For connections following the recommended details, the side shear stress limitations of 1,000 psi and 700 psi are suggested for the column-to-grout interface and CSP-to-surrounding concrete interface, respectively.

Outdoor System Test

- The test unit modeling the proposed bridge column/footing/pile system produced dependable performance when subjected to the factored design loads. There was no damage to the column socket or pile socket connections at this stage of testing.
- When the lateral force was gradually increased to exceed the design demand, damage occurred at the column base due to plastification, as expected given the design, and limited crushing or spalling was observed in the column socket connection with no damage occurring to the pile connections. This confirmed the adequacy of all ABC connections. This observation also confirmed that performance of the prefabricated column-pile cap-pile system was at least as good as, if not better than, that of a comparable, conventional, cast-in-place system.
- For the column socket connection, the embedment length equal to the column diameter is sufficient to fully develop the column flexural capacity; whereas, the pile embedment length

of 1.5 times the depth of the H-pile is recommended to maintain fixity for the pile socket connection.

- Foundation flexibility produced a significant effect on system response. About 40% of the column top lateral displacement was due to foundation flexibility prior to developing flexural inelastic strains in the column critical region. As inelastic action progressed in the column, the percentage contribution of foundation flexibility toward the column top lateral displacement was reduced to about 10%.

Implementation Readiness and Benefits

In this study, the performance of a bridge column/footing/pile system using ABC techniques was successfully verified. The constructability advantages of the prefabricated column-pile cap-pile system are that it is quick and simple to build, as demonstrated through the outdoor test. Using friction collars, SCC, and grout with desirable characteristics, the assembly of the proposed column-pile cap-pile system can be completed within a day after driving the piles.

As a result, the bridge substructure assembly involving prefabricated components can take place shortly after driving the foundation piles. Consequently, the proposed ABC approach for the substructure can reduce construction delays, serviceability problems, and costs, while ensuring quality construction.

CHAPTER 1. INTRODUCTION

1.1. Background

As of 2016, 4,968 bridges in Iowa (about one in five) were designated structurally deficient (ASCE 2017) and thus in need of significant maintenance, rehabilitation, or replacement. Accelerated bridge construction (ABC) using precast bridge elements is facilitating the process of reducing the number of structurally deficient bridges as it allows for faster and better repairs and builds on bridges. The use of precast elements shortens the period of on-site construction, thereby reducing mobility impacts, enhancing work-zone safety, and minimizing environmental impacts (Culmo 2011).

Precast elements also help to improve bridge quality and durability. Due to the advantages over traditional cast-in-place construction, the use of precast bridge elements has recently become a common practice. Successful practices were found nationwide (ABC-UTC 2018). As shown in Figure 1.1, the Iowa Department of Transportation (DOT) has widely implemented precast elements in bridge construction, ranging from superstructures (e.g., full-depth precast deck panels of the 24th Street Bridge in Council Bluffs and precast box girders of the Madison Bridge) to substructures (e.g., precast abutment footings of the Mackey Bridge in Boone County and precast frame piers of the US 6 Bridge over Keg Creek).



Iowa DOT (left) and Iowa DOT/HNTB (right)

Figure 1.1. Use of precast elements in Iowa bridge construction

Due to the difficulty of forming and pouring concrete high above the ground and the opportunity for repetition, the use of precast frame piers has been gaining momentum in recent years. Precast columns and precast pier caps have been used in many states, including the US 6 Bridge over Keg Creek in Iowa, Riverdale Road Bridge over I-84 in Utah, US 12 over I-5 at Grand Mound in Washington, and Route 70 over the Manasquan River in New Jersey. In Iowa, site conditions and construction costs usually favor the use of steel driven piles as the bridge pier foundation (Iowa DOT 2018). However, no precast piers have been constructed on steel driven pile foundations. An important concern of constructing precast frame piers with pile foundations is the lack of connection between a precast pier column and pile foundation. Piles are normally capped with a concrete footing (pile cap) to support a pier column. If a full precast pier is constructed, the

connection between the precast column and precast pile cap as well as the connections between the precast pile cap and steel driven piles have to satisfy a number of challenging design criteria. In addition to requiring they be easy to construct rapidly, these connections must be able to dependably transfer the forces resulting from the bridge weight, traffic, and lateral loads. Several methods have the potential to establish the connections for a precast bridge frame pier, such as a grouted coupler, mechanical coupler, grouted duct that splices the reinforcing bars extending from a precast element, pocket for embedding reinforcing bars extending from a precast element, socket for embedding the end of a precast element, post-tensioning, and welding (Culmo 2009). Among these types of connections, the socket connection offers numerous benefits including speedy erection, ample installation tolerances, and a simplified construction procedure, making this type of connection promising for implementation.

1.2. Objectives and Scope

Given the recent successes in the implementation of precast bridge elements and the limited use of precast piers with steel driven pile foundations, this research aimed to develop a full precast bridge frame pier with pile foundation to further facilitate the use of precast elements for ABC. This was accomplished by developing the connections for constructing a precast pier on a pile foundation, validating the precast pier performance experimentally with soil-foundation-structure interaction effects, and developing a design guide to help with implementation. Taking into account previous studies and practices, a precast pile cap with preformed sockets was used to connect a precast pier column and steel driven piles. For on-site assembly, the precast column and steel driven piles were embedded into these sockets using grout and concrete closure pours.

The performance of the socket connections and the precast pier was explored experimentally. First, a series of socket connection tests was conducted to investigate the behavior of the column socket connection in sustaining axial load resulting from gravity effects. Second, as the soil-structure interaction affects the overall performance of the system as well as the demands on the connections, a system test was performed at an outdoor test site in order to adequately account for the soil-foundation-structure interaction and quantify the overall system performance. Based on the knowledge gained from the literature and the experimental works conducted in this research, best practices to follow and appropriate design procedures for the precast pier system were developed to help with future implementation.

1.3. Report Organization

The second chapter of this report is a review of the literature describing previous practices and studies in order to extensively assess existing connection details for precast elements and develop new connection concepts. A detailed introduction of the connections and the precast pier with steel driven pile foundation is presented in Chapter 3. Chapters 4 and Chapter 5 discuss the component tests of the column socket connection and the outdoor system test of the precast bridge pier, respectively. The details about fabrication, testing methods, and results are also presented in these chapters. The summary and conclusions from this research along with a guide for implementation are presented in the final chapter.

CHAPTER 2. LITERATURE REVIEW

2.1. ABC and Precast Elements

ABC can be defined as bridge construction that uses innovative planning, design, materials, and construction methods in a safe and cost-effective manner to reduce the on-site construction time that occurs when building new bridges or replacing and rehabilitating existing bridges (Culmo 2011). The successes of a number of projects in Iowa and other states prove that ABC techniques offer many advantages over traditional cast-in-place (CIP) bridge construction, which include, but are not limited to, accelerated project delivery, improved construction quality, low life-cycle costs, minimal environmental impacts, improved work-zone safety, and reduced traffic disruptions. The available ABC methods are in two main categories: (1) offline construction where the bridge is constructed away from the final location and then moved into place through a self-propelled modular transporter (SPMT), lateral sliding, longitudinal launching, or a crane-based system, and (2) online construction that constructs the bridge in its final location using prefabricated bridge elements and systems (PBES) (UDOT 2017). Among these methods, online construction using prefabricated elements is the most common strategy for implementing ABC.

Prefabricated elements, especially precast concrete elements, have been an essential part of bridge construction for many years. Because they are constructed in a controlled environment, these elements normally achieve higher quality. The unrestrained condition during curing (i.e., no contact with previously cast concrete) reduces, and eliminates in most cases, shrinkage cracking, thereby minimizing long-term deterioration of the concrete (Culmo 2011). Considering transportation, fabrication, and construction, the height and width of each precast element, including projecting reinforcing, are recommended to be less than 10 ft and 14 ft, respectively (UDOT 2017). In addition, the elements need to be sized based on the weight limits of the available equipment and the proposed shipping routes. Designers should carefully consider the constructability when using precast elements. Some effective methods to improve the constructability include providing repetitive and simple details, minimizing the number of connections, and providing as much tolerance in the system as possible. Based on the emulating principle, the design of individual elements can follow traditional Load and Resistance Factor Design (LRFD) specifications as if they were constructed using CIP techniques. Precast elements can be used for all components in bridges, as listed in Table 2.1.


Table 2.1. Precast elements for ABC

Category	Component
Superstructure	Deck elements
	Beam elements
Substructure	Pier elements
	Abutment and wall elements
Miscellaneous	Approach slab elements
	Barrier elements
	Others

For the purposes of this study, only precast frame piers are discussed in the following section.

2.2. Precast Frame Pier

Most bridge piers can be grouped into frame pier, T-pier, pile bent, or diaphragm pier, as shown in Figure 2.1 (Iowa DOT 2018).



Iowa DOT 2018

Figure 2.1. Bridge piers

Among these pier configurations, a frame pier is the preferred selection for a typical pretensioned prestressed concrete beam (PPCB) or continuous welded plate girder (CWPG). If a bridge is not required to be designed for vehicular collision force and ice loads, a frame pier is preferred because of its low construction cost (Iowa DOT 2018). A frame pier typically consists of a bent cap, columns, and foundation under each column. In Iowa, considering site conditions and construction costs, it often is appropriate to use steel H-piles for the pier foundation (Iowa DOT 2018).

Due to the difficulty of forming and pouring the bent cap and column at height, construction of a frame pier can be challenging. Using precast elements can eliminate the on-site forming and save significant time during construction. With precast technologies, a typical frame pier can be constructed in as little as two days once the footings are in place (Culmo 2011). Many state agencies have utilized precast elements in the construction of frame piers. The Iowa DOT has successfully accomplished the construction of the US 6 Bridge over Keg Creek with precast columns and precast bent caps (Figure 2.2 left).



Iowa DOT/HNTB (left) and WSDOT (right)

Figure 2.2. Precast frame piers: US 6 Bridge over Keg Creek (left) and US 12 Bridge over I-5 at Grand Mound (right)

The Texas DOT (TxDOT) introduced precast reinforced bent caps in the 1990s and has developed precast pretensioned bent cap designs in recent years. Full precast frame piers were constructed for the Riverdale Road Bridge over I-84 in Utah. The Washington State DOT (WSDOT) has successfully implemented precast columns and precast bent caps with CIP spread footings (Figure 2.2 right). To address the challenges from site constraints, precast elements can be used for the construction of foundations. The New Hampshire DOT (NHDOT) and Utah DOT (UDOT) have developed precast spread footings for bridge construction. However, no precast pier has been constructed on the pile foundation.

2.3. Connections for Precast Frame Pier

The connections between precast elements are the most critical parts in ABC projects. These connections should not only be easy to construct but they should also ensure structurally dependable performance. Most ABC projects are based on the concept of emulation design, which requires the precast connections to be designed and detailed to act as a CIP construction joint. Another strategy for connecting precast elements is providing a connection with a strength lower than that of the adjacent components, while still ensuring sufficient energy dissipation and strength to maintain the integrity of the bridge.

The successes in past projects (Culmo 2009) and extensive research projects (Marsh et al. 2011, Restrepo et al. 2011) showed the feasibility of adequately connecting precast bent caps and precast columns in bridge construction. A commercial grouted splice coupler is the most common connection method. Other methods, such as a bar coupler connection, grouted duct connection, pocket connection, or hybrid connection with post-tension technology, are also practical selections. Aside from the connection between precast bent caps and precast columns, the column-to-footing connection is another critical element to successfully implement a precast frame pier. If piles are used as the foundation, the pile cap-to-pile connection is required as well. The following sections describe the findings from the literature and practices on the connections for precast columns and piles.

2.3.1. Column-to-Footing Connections

Based on the force transfer mechanism, connections suitable for a precast column can be classified as bar coupler connection, grouted duct connection, pocket connection, socket connection, and jointed connection. However, due to geometry restraint, the pocket connection is not suitable for connecting a precast column with a precast pile cap.

2.3.1.1. Bar Coupler Connection

A bar coupler works as a connection by splicing the reinforcing bars from the column and footing. Several styles of couplers, as illustrated in Figure 2.3, are commercially available.





Figure 2.3. Bar coupler types


Among these couplers, the grouted splice sleeve and headed bar with mating sleeve are used for connecting a column and footing. Figure 2.4 shows the typical connection details using grouted splice sleeves.



Pantelides et al. 2017/University of Utah Civil and Environmental Engineering

Figure 2.4. Connection details using grouted splice sleeves

A grout bed using non-shrink grout is prepared before the column is placed. Reinforcing bars extending from the footing or the column are grouted into splice sleeves. Another type of bar coupler connection is shown in Figure 2.5.



Haber et al. 2013/Center for Civil Engineering Earthquake Research


Figure 2.5. Column-to-footing connections with bar couplers

Vertical reinforcing bars with headed ends project from the footing and the column. After placing the column on the footing, the link bars are connected by mating sleeves to the bars projecting from the column and footing. Spiral reinforcement is then put around the link bars, and the connection is completed by casting concrete around the splice region at the column base.

For the bar coupler connections, the force transfer mechanism is straightforward, but the main challenges are cost, tolerance, and potential congestion due to the larger diameter of the couplers. Designers can mitigate the cost by minimizing the number of couplers through using large diameter reinforcing bars. Tolerance is a challenge because all projected bars must be aligned in the field. To help with this, a template can be used to position the bars and couplers during fabrication of the column and footing. In order to reduce congestion, it is preferred to embed the coupler into the footing and use larger bars to reduce the number of couplers required. The tests conducted with these connections (Haber et al. 2013) showed that the strain concentration occurred either above or below the couplers, depending on their locations.

2.3.1.2. Grouted Duct Connection

In a grouted duct connection, reinforcing bars projecting from one member are grouted into ducts that are cast into a second member. The force is transferred from the reinforcing bars to the concrete surrounding the ducts. A small number of larger bars are typically used for easier alignment and less congestion. Due to the length required to anchor the large bars, ducts are typically cast into the column, as illustrated in Figure 2.6.




Pang et al. 2008/Washington State Transportation Center

Figure 2.6. Column-to-footing connections with grouted ducts

Using ultra-high-performance concrete (UHPC) to fill the ducts instead of grout requires a shorter length to fully anchor the reinforcing bars such that the ducts can be placed in the footing. Several tests (Tazarv and Saiidi 2015, Pang et al. 2008) have been conducted on this type of connection, and preliminary design guidelines can be found in the Precast/Prestressed Concrete Institute (PCI) Precast and Prestressed Concrete handbook (2014). Similar to the bar coupler connection, the challenges associated with grouted ducts are tolerance and potential congestion.

2.3.1.3. Socket Connection

A socket connection for joining the precast column and footing can be constructed using one of the following two methods: (1) cast a CIP footing around the column, or (2) insert the column into a preformed socket in a CIP or precast footing and secure the connection using a grout closure pour. The surface of the column can be roughened to improve the shear transfer between members. The preformed socket can be accomplished using commercially available corrugated steel pipe (CSP) due to its low cost and variability in size. In addition to serving as stay-in-place formwork, CSP offers confinement effects for the connections and its corrugations support a robust load transfer mechanism. The column reinforcing bars in socket connections are fully encased, and the sockets are preformed and oversized, enabling generous tolerance to be accommodated. WSDOT has developed and successfully implemented a socket connection suitable for a precast column with CIP spread footing, as shown in Figure 2.7.



Haraldsson et al. 2013/University of Washington Civil and Environmental Engineering

Figure 2.7. Socket connections with CIP footings

The option with a precast footing has been investigated as well (Figure 2.8).




Motaref et al. 2011/Center for Civil Engineering Earthquake Research

Figure 2.8. Socket connections with precast members

Motaref et al. (2011) and Kavianipour and Saiidi (2013) tested a precast bridge pier, in which the columns were embedded into the reserved socket in a precast footing with high-strength grout infill. The embedment length of the column in the footing socket was 1.5 times the column diameter. The authors reported that the embedment length was sufficient to develop full fixity at the column base. Mehrsoroush and Saiidi (2016) tested a pier model with precast columns and socket connections in the precast bent cap. In the model, the sockets were made using CSP, and the column embedment length was 1.2 times the column diameter. Results showed that the configurations were adequate to develop moment connections and form plastic hinges in the columns. Another experimental study (Mashal and Palermo 2015) showed that the column embedment length can be shortened to 1.0 times the column diameter. The socket on the precast footing was created by foam, and both the socket wall and base of the column were treated with exposed aggregate finish. The socket connection successfully formed the plastic hinges in the column with no damage to the footings.

2.3.1.4. Jointed Connection

Jointed connections include an unbonded post-tensioning tendon to connect a precast column with its footing. The post-tensioning tendon is designed to remain elastic for a drift at the design-level motion, allowing the column to re-center while not allowing the members to undergo plastic deformation. Keeping the tendon elastic provides very little energy dissipation capacity. Mild reinforcing bars or other innovative devices are installed for dissipating energy, and can be replaced after damage. Figure 2.9 illustrates examples of jointed connections utilizing unbonded post-tensioning.



Motaref et al. 2011/Center for Civil Engineering Earthquake Research


Figure 2.9. Jointed connections

Note that these connections were experimental and have not been used on actual bridges. The challenges associated with a jointed connection include cost, constructability, and durability. Also, this type of connection offers no advantage in non-seismic regions.

2.3.2. Pile Cap-to-Pile Connection

The steel H-pile is a common foundation choice for bridges with frame piers. Pile foundations are normally capped with a concrete footing in order to provide a stable platform to support the column. A pile group with a concrete cap is an indeterminate structure. In most cases (i.e., the piles are surrounded by competent soil), the lateral movement of a pile in a pile group with a concrete cap under lateral loads is very small. Therefore, moments in the pile-to-cap connection can be ignored. Even though the moment is often ignored in the design process, experimental studies (Shama et al. 2002, Xiao et al. 2006) indicated that embedding the pile head into the cap, as typical in current practice, develops significant capacity to sustain a moment.

Few attempts have been made to implement precast pile cap in bridge construction. Only conceptual details have been developed for the connection of precast pile caps to steel H-piles, and one of them is from the PCI Northeast Bridge Technical Committee (Culmo 2009, 2011). As shown in Figure 2.10, leveling bolts are used in the corners of the precast cap to set grade, and concrete is poured through ports to fill the voids around the piles.



Culmo 2009/PCI Northeast Bridge Technical Committee

Figure 2.10. Precast cap to pile connections


Based on research on precast abutments, another conceptual connection has been developed, similar to a socket connection, using CSP voids. The research findings showed that the connection with CSP can provide a large amount of strength to transfer the axial force of steel H-piles (Wipf et al. 2009).

The Wyoming DOT (WYDOT) developed and implemented a connection for connecting precast concrete pier caps to steel H-piles when constructing the bridge over Crow Creek.

To establish the connection, steel plates with shear studs are cast at the pile locations along the bottom of the pier cap. In the field, after the cap is set, the steel H-piles are welded to the steel plates.

2.4. Design of Socket Connection

Because of numerous advantages, including speedy erection and ample installation tolerances, the socket connection is competitive for joining precast elements in the construction of bridge frame piers. Several design details and procedures for this type of connection have been developed based on experimental research findings. When a precast column and a precast footing are connected using a preformed socket, Mashal and Palermo (2015) claimed that a load couple will form in the socket under the lateral loading of the column, which induces compressive stresses in the radial direction and hoop tensile stresses that lie at a perpendicular direction to the compressive stresses, as shown in Figure 2.11.



Mashal and Palermo 2015/© 2015 ASCE, used with permission

Figure 2.11. Stresses and reinforcement in socket connection: stresses in socket connection under lateral loading (left) and circular reinforcement (right)

Hence, circular reinforcement should be provided around the socket. Reinforcement anchorages (i.e., headed end) are also suggested for fully developing the column longitudinal bars without increasing the socket depth. The surface of the socket and the column end need to be roughened to increase the bond. The experimental test indicated that, following the above recommendations, the column embedment length can be shortened to 1.0 times the column diameter to successfully form the plastic hinge in the column.

For square and rectangular column-to-footing connections, Mohebbi et al. (2017) proposed the following design recommendations:

- According to the experimental results and the minimum development length of straight reinforcing steel, the minimum depth of the socket (D_p) should be the greatest of the values in the equation as follows:

$$D_p \geq \left\{ \begin{array}{l} \frac{1.0B_c + Gap}{\sqrt{f'_c}} + Gap \\ \frac{1.56V_{PO} + \sqrt{4.74V_{PO}^2 + 6.22M_{PO}f'_cB_c}}{B_cf'_c} + Gap \end{array} \right\} \quad (1-1)$$

where,

B_c = the column dimension

Gap = the spacing between the column and the socket face, which should not be less than 1.5 in., and should not exceed 4 in.

d_b = the diameter of the column longitudinal bar (in.)


f_{ye} = the expected yield stress of longitudinal reinforcement (ksi)

f'_c = the nominal compressive strength of concrete (ksi)

V_{PO} = the shear force corresponding to column plastic overstrength moment (kip)

M_{PO} = the column plastic overstrength moment (kip-in.)

- The diagonal bars should be placed at 45 degrees, relative to the longitudinal axis of the footing, as shown in Figure 2.12. The spacing of the diagonal bars should not exceed 4 times the bar diameter, and bars should be fully anchored from the corner of the socket.



Mohebbi et al. 2017/Center for Civil Engineering Earthquake Research

Figure 2.12. Top reinforcement in footing

Due to the lack of practice and research, no design recommendations were found for detailing the preformed socket to connect steel H-piles with precast footings. However, design recommendations are made for construction practices with a CIP footing, which establishes CIP socket connections by encasing the top of the piles. The pile head is typically embedded 1 to 2 ft into the CIP cap. In Iowa, the bottom reinforcing mat of the pile cap is placed 1 in. clear above the top of the piles. Placing the bottom reinforcing mat below the top of the piles is also an acceptable option if the piles are widely spaced at 5 ft or more (Iowa DOT 2018). Shama et al. (2002) defined pile-to-cap connection efficiency (ρ) in predicting connection performance, which compares the moment capacity of the pile to the moment capacity of the pile-to-cap connection. Based on the assumed linear stress distribution through the connection zone, the connection efficiency can be quantified as:

$$\rho = \frac{\left(\frac{f_c}{f_y}\right)\left(\frac{d_p}{t_f}\right)\left(\frac{l_e}{d_p}\right)^2}{\left(6 + \frac{l_e}{L^*}\right)} \tag{1-2}$$

where,

- f_c = the allowable concrete compressive stress
- f_y = the yield stress of steel pile section
- d_p = the pile steel section depth
- t_f = the pile steel section flange thickness
- l_e = the embedment depth of the steel pile section inside the concrete cap
- L^* = the distance from the point of application of the lateral load to the neutral axis of the joint

2.5. Construction of Socket Connection

A socket connection is an easy-to-construct detail. The socket on one member can be made using commercially available CSP. After inserting another member into the socket, the connection is secured by using a grout closure pour. The surface of the embedded member can be intentionally roughened to improve the force transfer between concrete and grout as they are cast separately.

The following sections contain information on the materials, the products, and the techniques that are required for establishing a structurally adequate and easy-to-construct socket connection.

2.5.1. Corrugated Steel Pipe

CSP is an effective way to preform a socket in precast elements. In addition to serving as stay-in-place formwork, CSP offers a confinement effect for the connection and its corrugations provide a robust load transfer mechanism. Referring to the specifications for culvert pipes (AASHTO 2017, UDOT 2017), the CSP used for creating sockets shall meet the requirements of American Association of State Highway and Transportation Officials (AASHTO) M 218 (2016). Metallic coating is typically applied to improve the durability of the CSP, but aluminum cladding is not allowed because aluminum is reactive with the surrounding concrete, leading to degradation of the connection over time (UDOT 2017). The seam types of standard CSP include annular corrugations with riveting or resistance spot welding and helical corrugations with lock seam or continuous welding. For establishing sockets, annular corrugations are preferred because any detail to convey water more efficiently is not recommended for structural applications (UDOT 2017). The corrugations of annular seams are 2.67 in. pitch by 0.5 in. depth and 3 in. pitch by 1 in. depth depending on the CSP diameter. For the most common CSPs, ranging from 12 in. to 84 in., the corrugation pattern is 2.67 in. by 0.5 in., where 2.67 in. is measured from crest to crest and 0.5 in. is from valley to crest. Commercially available CSPs have variability in sizes from 12 in. to 144 in. measured on the inside crest of the corrugations. Designers should be aware of manufacturing tolerances when they choose the pipe to fit their projects. For the CSP used in bridge construction, the average inside diameter of the circular pipe shall not vary more than 1% or 0.5 in., whichever is greater, from the nominal inside diameter (AASHTO 2016).

2.5.2. Grout

There are several different types of grouts. Among these grouts, cementitious grouts are inexpensive, generally easy to work with, and develop adequate strengths in reasonable time, making them suitable for bridge construction. These grouts are often prepackaged and composed of hydraulic cement, fine aggregate and other ingredients. Most commercially available cementitious grout requires only the addition of water for use. The manufacturer may allow the job site addition of specific amounts and types of aggregates for some uses. For securing socket connections, the grout is required to have the following desirable properties: fluid consistency, extended working time, high early strength, high strength, and non-shrink. The fluid consistency and extended working time provide the possibility of flowing easily into tight clearances and large placements in bridge socket connections. High early strength (i.e., a compressive strength not less than 4,000 psi at 1 day) allows the connections to gain strength quickly, such that the

project can be completed in a short period. High strength of the grout ensures the strength of the finished connection. Ideally, non-shrink grout will not exhibit dimensional change in the plastic or hardened state. This property tends to reduce the cracks that can occur at the interface between grout and precast elements and in the grout itself, which improves the durability of the connection.

To identify suitable products, information about cementitious grouts available on the market were scanned and sorted (Sritharan and Cheng 2016). After reviewing the technical datasheets and several trial mixes, Rapid Set ULTRAFLOW 4000/8, referred to as ULTRAFLOW, was identified as the one that met the requirements for securing socket connections. This particular type is a fluid consistency, non-shrink, precision grout that provides extended working time up to 30 minutes, but then gains strength quickly after an hour and hits 4,000 psi in 8 hours (CTS Cement 2019). In addition, the ULTRAFLOW grout reaches a specified 28 days compressive strength of 8,500 psi at fluid consistency. Any other products that have comparable properties can be used for socket connections as well.

2.5.3. Concrete Surface Finishing Techniques

In the socket connection, the surface of the embedded element is often intentionally roughened. Different practical methods can be used to achieve different degrees of roughness. Exposed aggregate finish is popular, and deeper texture with regularized patterns can also be created by form liners. Chemical formwork retarders are very effective in exposing coarse aggregate. The application of retarders to the formwork prior to casting the concrete delays the surface cement paste from hardening. After hardening of the concrete mass, the retarded outer layer can be removed by high-pressure water washing. Acid etching is another technique to expose aggregate on the concrete surface. Unlike retarders that are applied prior to casting concrete, acid etching dissolves the surface cement paste after concrete hardens. Note that acid etching is only for light to medium exposures, while formwork retarder can provide deep exposure where the coarse aggregate becomes the major surface feature (PCI 2007). Hardened concrete can also be mechanically roughened with sandblasting or bush hammering to produce an exposed aggregate texture. These finishing techniques are more labor intensive, and may soften the exposed aggregate (PCI 2007). Form liners are made of wood, steel, elastomeric, plastic, or polystyrene. A variety of surface textures can be achieved by casting against form liners that are incorporated in or attached to the surface of formwork. Form liners are the most suitable for flat surfaces.

CHAPTER 3. PROPOSED BRIDGE COLUMN/FOOTING/PILE SYSTEM

3.1. Column Socket Connection and Pile Socket Connection

Taking into consideration previous studies and practices, the socket connection was selected for developing the full precast frame pier with the steel driven pile foundation. A precast pile cap was used to connect the pile column and the pile foundation. Sockets were preformed on the top and bottom of the precast pile cap, and the precast pier was assembled by embedding the column and steel driven piles into these sockets through the use of grout or concrete closure pours. The sockets, as shown in Figure 3.1, are constructed using commercially available CSPs due to their low cost and wide variation in size.





Figure 3.1. Sockets on precast pile cap

In addition to serving as stay-in-place formwork, CSP offers a confinement effect to the connection while its corrugations can provide a robust load transfer mechanism. The socket reserved for the precast column (the column socket) was constructed to partially penetrate the pile cap. Hence, the bottom-layer reinforcing bars of the pile cap can be placed underneath the socket. The sockets for the piles (the pile sockets) penetrate through the pile cap for conducting closure pours, and the upper portions of these sockets were made in the shape of a cone. This configuration allowed the top-layer reinforcing bars to be placed without notches on the CSPs as this would unnecessarily complicate the construction. Headed reinforcing bars, as depicted in with heavier lines in Figure 3.1, were added to help force transfer within the pile cap.


3.2. Assembly of Precast Frame Pier

For constructing the pier, steel piles were driven, for which a template was employed to maintain the piles in proper position and alignment. Then, temporary friction collars were affixed around each pile, on which the precast pile cap is shored. At this stage, the tops of all the piles were positioned into the respective pile sockets. The use of friction collars offered the feasibility of conducting construction in poor ground conditions and achieved better erection tolerance control. After erecting the precast column with an intentionally roughened end, the column, the pile cap, and the piles were connected by filling the column socket and the pile sockets with grout and self-consolidating concrete (SCC), respectively. One commercially available grout with desirable properties such as high early strength, fluid consistency, extended working time, and non-shrink was chosen for securing the column socket. The chosen grout can reach a specified compressive

strength of 4,000 psi in 8 hours, and the friction collars were designed to carry the weight of the pile cap, column, and upper structural components before the SCC reaches adequate strength. Therefore, construction of the upper structure can continue the day after completing closure pours. When the SCC reached the specified short-term strength, the friction collars were removed for reuse. The assembly process is illustrated in Figure 3.2.




1. Driven steel pile with a template




2. Friction collars shoring precast pile cap




3. Plywood sealing the pile sockets




4. Place precast pile cap and column




5. Pour grout and SCC securing sockets



6. Continue construction



7. Take off friction collars



8. Back-fill trench

Figure 3.2. Assembly process of precast frame pier

CHAPTER 4. COLUMN SOCKET CONNECTION TEST

As illustrated in Figure 4.1, the column socket connection can be constructed with full or partial penetration.




Figure 4.1. Axial strength of fully penetrated socket connection (left) and partially penetrated socket connection (right)

With any construction option, when the column is subjected to the design loads, the socket connection should facilitate the transfer of the loads without sustaining any significant sliding. As shown in Figure 4.1 left, the axial strength of a fully penetrated connection depends only on the side shear resistance acting along the embedded portion of the vertical member. For a partially penetrated connection (Figure 4.1 right), the axial load resistance can be provided by side shear and tipping at the end of vertical member. While relying on both side shear and tipping can be attractive to reduce the required embedment length of the vertical member, this option is not favored herein. This is because the design of such a connection is more challenging due to (1) the side shear and tipping mechanisms being unlikely to be active simultaneously and (2) the requirement to design for punching failure caused by the precast vertical member to sustain a tipping mechanism. Given that sufficient axial resistance can be developed over a short embedment length, it is suggested that both fully and partially penetrated connections be designed relying only on side shear.

Several experimental studies have utilized preformed socket connections for bridge columns. However, currently available testing results are not applicable to bridge columns subjected to 25 to 30% of the axial load capacity. In addition, for preformed socket connections that are established using CSPs and grout closure pour, no guideline is available to help determine the key connection parameters and side shear strength for design due to a lack of investigation that examined the failure modes of socket connections. To address this knowledge gap, column socket connection tests were conducted to investigate the failure modes of side shear mechanism in preformed socket connections so that suitable vertical precast members can be designed to transfer large axial loads through socket connections.

4.1. Test Unit Design

When a preformed socket is established using CSP and the connection is established using grout, the side shear strength will depend on a number of parameters. The parameters that most influence the strength include: (1) corrugation pattern of CSP, (2) surface texture along the embedded length of the precast member, (3) clearance between the embedded member and CSP, and (4) the strength and type of grout used for closure pour. More details about each parameter are presented below.

1. A key feature of CSP is its corrugation, which provides additional load transfer capacity. The corrugation types of standard CSPs include annular corrugation and helical corrugation; annular corrugation was chosen in this study. The corrugation pattern in commercially available CSP varies with the pipe size. A pattern with 2.67 in. pitch and 0.50 in. depth is standard for CSPs with inside diameters ranging from 1 ft to 7 ft, which are considered to be applicable to form sockets in bridge construction.
2. Bond strength between the grout closure pour and the embedded member is another important property as shear sliding failure can trigger at this interface. The primary variable that controls the bond strength is surface roughness of the embedded precast member. A smooth surface with no treatment will have lower bond strength, increasing the likelihood of shear sliding at this interface. To ensure adequate shear transfer, the AASHTO LRFD Bridge Design Specifications (2017) suggests intentionally roughening the surface to an amplitude of approximately 0.25 in. Exposed aggregate finish is a popular texture for achieving the desired degree of roughness; regularized patterns with deeper amplitude (e.g., fluted fins and saw-tooth pattern) also have been commonly used. Different practical methods such as chemical formwork retarder, sandblasting, and bush hammering can be used to expose coarse aggregates. Note that the mechanical methods (i.e., sandblasting and bush hammering) may soften the exposed aggregate (PCI 2007), which will degrade the bond strength at the interface. The regularized patterns can be achieved by casting concrete against form liners that are incorporated in or attached to the inside surface of the formwork.
3. The preformed socket connection is secured by filling the clearance between CSP and precast member with grout. The thickness of the grout closure pour that corresponds to the CSP-to-precast member clearance may affect the transfer of side shear. Sufficient clearance must be provided to conduct the grout closure pour and to account for the cumulative effects of all allowed tolerances. For inserting a precast member, a minimum clearance of 1 in. is required around the perimeter between the column and the socket (PCI 2000). This clearance is also controlled by the available sizes of CSPs. For commonly used bridge column sizes, Table 4.1 presents the inside diameters of the appropriate commercially available CSPs and the resultant CSP-to-column clearances.

Table 4.1. CSP-to-column clearances for common size precast columns

Column diameter (in.)	Inside diameter of CSP (in.)	Resultant clearance (in.)
18	21	1.5
24	27	1.5
30	36	3.0
36	42	3.0
42	48	3.0
48	54	3.0

Hence, the clearances of 1.5 in. and 3 in. are two likely construction options in the socket connections for vertical precast members. This clearance represents the minimum distance between the crest of the CSP and the surface of column.


4. For the purpose of establishing a strong socket connection, a high-strength grout with a minimum compressive strength of 8,000 psi is preferred because the strength of the precast member may be in the range of 5,000 to 7,000 psi. Other desirable properties, such as high early strength, fluid consistency, extended working time, and non-shrink, are also required to properly secure the connection. High early strength (i.e., a compressive strength not less than 4,000 psi at 1 day) would facilitate the connection to gain strength quickly, such that curing of grout strength will not cause any construction delays. The extended working time and fluid consistency provide the possibility to complete a large grout pour into the tight clearance between the precast member and CSP. The non-shrink feature of the grout will minimize the formation of cracks at the interfaces or within the grout itself, which is important for the durability of the connection. A scanning of commercially available cementitious grouts has been conducted, and the findings indicated that only limited types of grouts meet all the preceding requirements (Sritharan and Cheng 2016).

Once a specific grout that met the desirable characteristics and commercially available standard CSPs were selected, the side shear strength of a socket connection was determined by the surface texture of the precast column and CSP-to-column clearance. Therefore, a total of eight specimens were designed to understand the effects of these variables. As detailed in Table 4.2, the surface texture of the embedded column, CSP-to-precast member clearance, and type of loading were varied.

Table 4.2. Testing matrix

Test specimen	Column surface texture	CSP-to-column clearance (in.)	Loading type
F1G1M	0.5 in. fluted fin	1.5	monotonic
F2G1M	0.75 in. fluted fin	1.5	monotonic
EG1M	exposed aggregate	1.5	monotonic
F2G2M	0.75 in. fluted fin	3.0	monotonic
EG1C	exposed aggregate	1.5	cyclic
F1G1C	0.5 in. fluted fin	1.5	cyclic
SG1C	Smooth	1.5	cyclic
F1G2C	0.5 in. fluted fin	3.0	cyclic

The surface textures included exposed aggregate finish, 0.5 in. deep fluted fin, 0.75 in. deep fluted fin, and smooth surface. For the fluted fin patterns, the fins are routinely made in a trapezoidal shape, and the fin-to-fin pitches of 1.5 in. and 2 in. are standard for the 0.5 in. and 0.75 in. fin depths, respectively. Two likely CSP-to-column clearances of 1.5 in. and 3 in. were chosen as test variables. Each test specimen, as detailed in Figure 4.2 and Table 4.2, consisted of a short precast column and a precast foundation.

**Figure 4.2. Details of socket connection test specimen**

Considering the limitation of the actuator capacity, the column embedment length was chosen to be 9 in., which was equal to the outer diameter of the column. The 12 in. and 15 in. nominal diameter CSPs with the standard corrugation pattern of 2.67 in. by 0.50 in. were used to reserve, respectively, the 1.5 in. and 3 in. clearances for grouting. An oversized blockout was formed under the socket in each foundation to allow the precast column to be pushed out freely when the side shear mechanism fails. To prevent the columns above the foundation from experiencing damage due to compression, they were confined by a steel tube with grout infill between the column and the tube. A 2 in. gap was left between the steel tube and the top of the foundation so that the tube would not establish contact with the top of the foundation block during testing. This approach allowed the axial load on the column to be increased, forcing failure in the connection.

4.2. Test Unit Construction

To construct the foundation, a 3 in. thick circular piece of Styrofoam was glued on the base formwork for creating the oversize blockout. After fabricating the reinforcing cage, as shown in Figure 4.3, CSP was placed on the Styrofoam and immobilized by a crossing 2 in. by 4 in. wood beam that was clamped to the formwork side.



Figure 4.3. Reinforcing cage and CSP installation for foundation

The columns were constructed with different surface roughness. Surface textures with 0.5 in. and 0.75 in. fluted fins were created through the use of a Scott System elastomeric form liner; the exposed aggregate surface was achieved by applying an Altus Series V In-Form Retarder (175) to the concrete tube form; and the smooth surface was made with a no-treatment concrete tube form. As shown in Figure 4.4, a number of breaches were cut on the fins of the form liner to improve its flexibility, such that the form liner could be rolled into a concrete tube form.



Figure 4.4. Form liner used to create fluted fins on the column

Plywood strips were wedged between the form liner and tube form to adjust the inside diameter to be as specified. To confirm the working time of the retarder, three trial specimens were made. A comparison of the trial specimens (Figure 4.5) indicated that the performance of the retarder is not sensitive to the timing of the application or how soon the power washing was done following casting of the concrete, which makes the use of this retarder in prefabrication very attractive.




Figure 4.5. Comparison of trial specimens

Hence, for the construction of the column with the exposed aggregate surface, the retarder was applied two hours prior to placing concrete. All foundations and columns were completed with one concrete pour. The measured 28 day compressive strength of these members, established following the ASTM C39 (2017), was 5,362 psi. On the third day after the concrete pour, the laitance on the columns was power washed right after stripping the forms. The columns with different surface roughness are shown in Figure 4.6.




Figure 4.6. Columns with different surface roughness

After cleaning the column surface and the inside of the CSP, the gap between the column and CSP was secured by Rapid Set ULTRAFLOW 4000/8 grout, which has a specified early strength of 4,000 psi in 8 hours with a specified compressive strength of 8,500 psi at 28 days according to ASTM C109 (2016), and met other requirements for a closure pour such as fluid consistency, extended working time, and non-shrink characteristics. When the grout reached a compressive strength of 5,500 psi, the Styrofoam was removed. Finally, the test unit was completed after grouting the steel tube with the column.

4.3. Test Protocol

Four test units (F1G1M, F2G1M, EG1M, and F2G2M) were tested using monotonic loading, whereas the rest of the test units (EG1C, F1G1C, SG1C, and F1G2C) were subjected to cyclic loading. The loading procedure consisted of two phases. Phase I included force-controlled steps at 40 kips increments. After the connections exhibited nonlinearity associated with the response, Phase II was conducted with displacement-controlled steps until a sliding failure was observed. For the cyclic loading, one cycle was conducted per force-controlled step, and three cycles were performed per displacement-controlled step.

4.4. Test Setup

The testing setup used for the socket connection tests is shown in Figure 4.7.




Figure 4.7. Test setup for socket connection tests

The test unit was positioned on two base blocks in order to access the bottom of the column for instrumentation purposes. Using a hydraulic actuator that was attached to a reaction frame, vertical downward force was applied on the top of the column until a sliding failure was observed.

4.5. Instrumentation

Each test unit was instrumented with the optical measurement system, direct current differential transformers (DCDTs), string potentiometers (string pots), and strain gauges. As shown in Figure 4.8 left, an array of light-emitting diode (LED) markers was attached to the test unit, so the optical measurement system could capture the connection response, including the relative displacement between the column and the grout closure pour (CG displacement), the relative displacement between the column and the foundation (CF displacement), and the relative displacement between the grout closure pour and the foundation (GF displacement).




Figure 4.8. Configuration of instrumentations (left) and measurement variables (right)

These measurements are detailed in Figure 4.8 right. Two DCDTs were also attached to the column to measure the CG displacement and the CF displacement. Between the two base blocks, one string pot was placed underneath the foundation to capture the column base settlement. In addition to external instrumentation, strain gauges were installed on one longitudinal reinforcing bar in the column for capturing force transfer in the joint region. To determine any vertical movement within the grout, which could originate with shear sliding within the grout, the vertical deformation of the grout closure pour (Δ_{grout}) was measured using LED markers on the top of the grout closure pour. This was monitored only for the test units with 3 in. thick grout closure pours. One LED was located at 0.25 in. and the other at 2.5 in. from the column surface as shown in Figure 4.9.




Figure 4.9. LED markers capturing Δ_{grout}

4.6. Test Results

4.6.1. Failure Modes

Regardless of the type of loading, the specimens exhibited two failure modes as shown in Figure 4.10.




Figure 4.10. Failure modes of the specimens

For the specimen with a smooth column surface and those with a texture of 0.75 in. fluted fins, the sliding failure occurred at the column-to-grout interface, whereas the sliding eventually occurred at the CSP-to-foundation interface for the specimens with exposed aggregated finish and 0.5 in. fluted fins. For the specimens with 0.75 in. fluted fins, the failure was due to shearing off the concrete fins. When the failure was at the CSP-to-foundation interface, sliding of the CSP occurred with respect to the surrounding concrete in the foundation, implying shearing in the concrete of the foundation.

4.6.2. Measured Responses

Figure 4.11 depicts the applied vertical force as a function of CF displacement, which represents the overall response of each specimen.






Figure 4.11. Overall response of each test specimen

With the exception of the one specimen with a smooth column surface, the monotonically loaded specimens generally produced similar resistance but higher stiffness than their counterparts subjected to cyclic loading. The monotonically loaded specimens reached peak strengths in the range of 264 kips to 329 kips, while the cyclically loaded units resisted as much as 261 kips to 308 kips. These ranges correspond, respectively, to 77% to 96% and 76% to 90% of column axial capacity. The specimen with a smooth column surface failed at 161 kips and exhibited limited ductility.

Overall, the intentionally roughened column surfaces provided adequate bond strength between the grout and the embedded column, but the textures with deeper amplitude (i.e., 0.5 in. and 0.75 in. fluted fins) led to softer force-displacement responses. In addition, a thicker grout closure pour resulting from wider CSP-to-column clearance tended to reduce the shear stiffness of the connections as deformation within the connection increased. These phenomenon were evidenced by the captured behavior. The CF displacements consisted of CG displacements, GF displacements, and the grout vertical deformation (Δ_{grout}) especially when a thicker grout closure pour was included. Figure 4.12 describes the connection responses in terms of each component.




Figure 4.12. Comparisons of connection responses: (a) GF displacement responses for all specimens, (b) CG displacement responses for specimens with different column surface textures, and (c) CG displacement responses for specimens with different CSP-to-column clearances

To reveal the contribution of each component, plots were created with the same scale for the axes. As shown in Figure 4.12a, all specimens exhibited comparable GF displacement responses before reaching the peak strength. Hence, the differences in overall connection responses seen in Figure 4.11 were the result of sliding at the column-to-grout interface (CG displacements) and the deformation within the grout closure pour itself (i.e., Δ_{grout}). Figure 4.12b plots the vertical forces versus CG displacements for the specimens with 1.5 in. CSP-to-column clearance, but with different column surface textures. This plot confirms that adequate roughness was necessary to successfully develop the bond strength between the grout and the column. However, the textures with deeper amplitude of fins would soften the response at the column-to-grout interface. Figure 4.12c compares the force versus CG displacement responses for FIG1C and

F1G2C, which have the same column surface texture but different CSP-to-column clearance. FIG2C with a thicker grout closure pour resulting from a wider CSP-to-column clearance showed a softer overall connection response than FIG1C, but the two specimens exhibited similar responses at the column-to-grout interface. Therefore, given the comparable GF displacement responses, a thicker grout closure pour that induces significant Δ_{grout} would soften the connection response. With reference to the loading type, Figure 4.13 presents a comparison of the specimen responses with the same connection parameters but different load types.





Figure 4.13. Impact of cyclic loading


For the specimens with the exposed aggregate finish (i.e., EG1M and EG1C), no significant cumulative damage was caused by the cyclic loading until the applied load was increased to 150 kips, which was approximately 50% of the peak strength. However, the cyclic loading caused increased strength degradation for the specimens with deeper amplitude for the column surface texture (i.e., FIG1M and FIG1C).

4.6.3. Force Transfer Behavior


Figure 4.14 presents the column longitudinal bar strains as a function of embedment depth in the connection at various forces/CF displacements; missing data points are due to loss of data resulting from damaged gauges.




F1G1M



F2G1M



EG1M



F2G2M




Figure 4.14. Strain readings versus depths below the top of socket

The strain values reflect the transfer of force from the column to the foundation. A linear response is assumed between two adjacent gauge locations, which implies a constant shear stress along the column length. Based on the observations from these plots, in the specimens with smooth and exposed aggregate column surface, the shear transfer occurred uniformly along the entire column embedment length. In contrast, for the column surfaces with deeper amplitude texture created using form liners, the force transfer took place mostly in the top half of the connections. Also, the strain readings for the specimens with the same column surface texture but with different CSP-to-column clearance (i.e., F2G1M and F2G2M) revealed that the thicker grout closure pour tended to reduce the force transfer length. As a result, the stress was concentrated at the top portion of the sockets in these specimens.

4.7. Discussion

The performance of the connections presented in this chapter facilitated the characterization of the side shear mechanism and a better understanding of the force transfer behavior. The socket connections consisted of embedded columns with deeper amplitude surface textures exhibited softer force-displacement relationships compared to the one with exposed aggregate surface, while the surface textures in these connections transferred the force in a more efficient manner (i.e., over a shorter depth). The thicker grout closure pour resulting from wider CSP-to-column clearance also reduced the stiffness of the socket connection. The softening was attributed to relatively larger deformations occurring at the column-to-grout interfaces and within the grout closure pour itself, which were caused by the properties of grout. Under the applied loads, the grout exhibited relatively more flexibility than normal concrete due to the lack of hard coarse aggregate and lower modulus. Because of the increased volume of grout, the connections with deeper amplitude surface texture and wider CSP-to-column clearance showed softer connection responses. However, the deeper amplitude increased the shear resistance, enabling the force to be transferred over a reduced embedment depth. Even though the increased volume of grout led to relatively larger deformations, the failure did not occur at the grout closure pour but at the stems of concrete fins or foundation concrete surrounding the CSP because the strength of the grout was significantly higher than that of the concrete. The cyclic loading reduced the stiffness of the connections with deeper amplitude surface texture. However, for the connections with an exposed aggregate surface, a limited effect from the cyclic loading was observed on the connection response when the applied forces were less than 50% of the peak strength.


Based on the experimental investigation presented herein, the preformed socket connection provides great potential for use in practice due to its ease of construction. The socket can be easily established by a CSP that serves as stay-in-place formwork. Through the construction of the specimens, the use of chemical formwork retarder was found to be an efficient method to roughen the embedded member surface. The retarder was applied on the formwork up to three hours ahead of the concrete pour. After removing the formwork when the concrete was three days old, the laitance was easily removed with high-pressure application of water to expose the aggregate. The construction process with form liner was also completed with ease. However, damage to the precast fins could possibly occur during fabrication and transportation. The experimental study also examined potential time saving measures for the assembly of the socket connection. The process will go smoothly if the right grout is identified for the closure pour. The desirable features for the grout include high early strength, extended working time, and appropriate fluid consistency.



GSI Engineering, LLC
 4503 E 47th Street South
 Wichita, KS 67210
 316-554-0725

Project: ISU-NSF Pile Project
 Location: Ames, Iowa

CPT: CPT-1
 Total depth: 50.20 ft, Date: 3/22/2017
 Surface Elevation: 1014.10 ft
 Coords: X:0.00, Y:0.00
 Cone Type: 10T
 Cone Operator: M. Tye






GSI Engineering, LLC
4503 E 47th Street South
Wichita, KS 67210
316-554-0725

Project: ISU-NSF Pile Project
Location: Ames, Iowa

CPT: CPT-2
Total depth: 49.87 ft, Date: 3/22/2017
Surface Elevation: 1013.20 ft
Coords: X:0.00, Y:0.00
Cone Type: 10T
Cone Operator: M. Tye






GSI Engineering, LLC
 4503 E 47th Street South
 Wichita, KS 67210
 316-554-0725

CPT: CPT-3c
 Total depth: 32.48 ft, Date: 3/22/2017
 Surface Elevation: 1013.70 ft
 Coords: X:0.00, Y:0.00
 Cone Type: 10T
 Cone Operator: M. Tye


Project: ISU-NSF Pile Project
 Location: Ames, Iowa



CPeT-IT v.1.7.6.42 - CPTU data presentation & interpretation software - Report created on: 4/5/2017, 8:37:22 AM
 Project file: G:\00BS\Des Moines\2017 Projects\1763\1763013 ISU-NSF Pile Project\ISU-NSF Pile Project.cpt

Figure 5.2. CPT logs for the test site


BORING LOG No. BH-1

BORING NO.		LOCATION OF BORING		ELEVATION	DATUM	DRILLER	LOGGER				
BH-1		See Pile Driving Plan		1014.0 ft.	Center of Drilled Shaft	J. Tinnell	K. Goertz				
WATER LEVEL OBSERVATIONS					TYPE OF SURFACE			DRILL RIG			
WHILE DRILLING		END OF DRILLING		24 HOURS AFTER DRILLING	AFTER DRILLING		Bare Soil		Mobile B-61		
N.E.		57.5 ft.		Boring Plugged After Drilling			3.25-inch Inside Diameter Hollow Stem Augers		TOTAL DEPTH		
									60.0 ft.		
SAMPLE DATA				SOIL DESCRIPTION			LABORATORY DATA				
DEP. FT.	SAMPLE NO. & TYPE	"N" BLOWS (FT)	% REC.	COLOR, CONSISTENCY, MOISTURE		USCS CLASS.	MC %	Dry Dens. pcf	Pocket Pen taf	ELEV. FT.	
				GEOLOGIC DESCRIPTION & OTHER REMARKS							
				Reddish brown clay							
5	U-1	N/A							3.5	1009	
	S-2	11									
10	U-3	N/A								3.5	1004
	S-4	12									
15	U-5	N/A								3.5	999
	S-6	17									
20	U-7	N/A			Gray clay					3.75	994
	S-8	13									
25	U-9	N/A								4.5+	989
	S-10	21									
30	U-11	N/A					CL			4.5	984
	S-12	15									
35	S-13	48			Gravel layer						
					Gray clay						979
40	S-14	34		Olive gray clay						974	




4450 NW Urbandale Dr.
 Urbandale, IA 50322
 515-270-6542

PROJECT: ISU-NSF Pile Project
 LOCATION: Ames, Iowa
 JOB NO.: 1763013
 DATE: March 22, 2017

BORING LOG No. BH-1										
BORING NO.		LOCATION OF BORING		ELEVATION	DATUM		DRILLER		LOGGER	
BH-1		See Pile Driving Plan		1014.0 ft.	Center of Drilled Shaft		J. Tinnell		K. Goertz	
WATER LEVEL OBSERVATIONS						TYPE OF SURFACE			DRILL RIG	
WHILE DRILLING	END OF DRILLING	24 HOURS AFTER DRILLING		AFTER DRILLING		Bare Soil			Mobile B-61	
N.E.	57.5 ft.	Boring Plugged After Drilling				3.25-inch Inside Diameter Hollow Stem Augers			60.0 ft.	
SAMPLE DATA				SOIL DESCRIPTION				LABORATORY DATA		
DEP. FT.	SAMPLE NO. & TYPE	"N" BLOWS (FT)	% REC.	COLOR, CONSISTENCY, MOISTURE		USCS CLASS.	MC %	Dry Dens. pcf	Pocket Pen tsf	ELEV. FT.
				GEOLOGIC DESCRIPTION & OTHER REMARKS						
45	U-14	N/A		Olive brown clay						969
	S-15	24								
50	S-16	26		Dark gray clay						954
55	S-17	97		Reddish brown clay with gravel		CL				959
60	S-18	50/5*		Gray clayey sand		SC				954
				Bottom of Boring @ 60'						
65										949
70										944
75										939
80										934
				4450 NW Urbandale Dr. Urbandale, IA 50322 515-270-6542			PROJECT: ISU-NSF Pile Project LOCATION: Ames, Iowa JOB NO.: 1763013 DATE: March 22, 2017			

BORING LOG No. BH-2											
BORING NO.		LOCATION OF BORING		ELEVATION		DATUM		DRILLER		LOGGER	
BH-2		See Pile Driving Plan		1013.5 ft.		Center of Drilled Shaft		J. Tinnell		K. Goertz	
WATER LEVEL OBSERVATIONS						TYPE OF SURFACE			DRILL RIG		
WHILE DRILLING		END OF DRILLING		24 HOURS AFTER DRILLING		AFTER DRILLING		Bare Soil		Mobile B-61	
N.E.		10.5 ft.		Boring Plugged After Drilling				3.25-inch Inside Diameter Hollow Stem Augers		60.0 ft.	
SAMPLE DATA				SOIL DESCRIPTION				LABORATORY DATA			
DEP. FT.	SAMPLE NO. & TYPE	"N" BLOWS (FT)	% REC.	COLOR, CONSISTENCY, MOISTURE				USCS CLASS.	MC %	Dry Dens. pcf	Pocket Pen tsf
GEOLOGIC DESCRIPTION & OTHER REMARKS											
				Brown clay fill							
5	S-1	8		Reddish brown clay				CL			1008.5
10	S-2	10		Gray clay				CL		4.0	1003.5
	U-3	N/A									
15	S-4	13		Gray sand				SP			998.5
20	S-5	10		Reddish brown clay							993.5
	U-6	N/A									
25	S-7	19		Reddish brown clay							988.5
30	S-8	19		Reddish brown clay							983.5
	U-9	N/A									
35	S-10	27		Reddish brown clay							978.5
40	S-11	28		Reddish brown clay							973.5



4450 NW Urbandale Dr.
Urbandale, IA 50322
515-270-6542

PROJECT: ISU-NSF Pile Project
LOCATION: Ames, Iowa
JOB NO.: 1763013
DATE: March 22, 2017

BORING LOG No. BH-2										
BORING NO.		LOCATION OF BORING		ELEVATION	DATUM	DRILLER	LOGGER			
BH-2		See Pile Driving Plan		1013.5 ft.	Center of Drilled Shaft	J. Tinnell	K. Goertz			
WATER LEVEL OBSERVATIONS					TYPE OF SURFACE		DRILL RIG			
WHILE DRILLING	END OF DRILLING	24 HOURS AFTER DRILLING		AFTER DRILLING	Bare Soil		Mobile B-61			
N.E.	10.5 ft.	Boring Plugged After Drilling			3.25-inch Inside Diameter Hollow Stem Augers		TOTAL DEPTH			
SAMPLE DATA				SOIL DESCRIPTION			LABORATORY DATA			
DEP. FT.	SAMPLE NO. & TYPE	"N" BLOWS (FT)	% REC.	COLOR, CONSISTENCY, MOISTURE		USCS CLASS.	MC %	Dry Dens. pcf	Pocket Pen tsf	ELEV. FT.
				GEOLOGIC DESCRIPTION & OTHER REMARKS						
45	S-12	21			Brown clay					
	U-13	N/A			Dark gray clay				3.5	968.5
	S-14	35			Brown Clay	CL				963.5
55	S-15	48			Dark gray clay					958.5
	U-16	N/A		Gravel lense						
60	S-17	99/10"			Gray sandy clay	68.5				
						CL				953.5
					Bottom of Boring @ 60'					
65										948.5
70										943.5
75										938.5
80										933.5

4450 NW Urbandale Dr.
Urbandale, IA 50322
515-270-6542

PROJECT: ISU-NSF Pile Project
LOCATION: Ames, Iowa
JOB NO.: 1763013
DATE: March 22, 2017

Figure 5.3. SPT boring logs

It was found that the soil at the test site was primarily composed of stiff clays, with a 5 ft thick sand layer at a depth of approximately 35 ft. At the time of testing, the groundwater table was at a depth of approximately 7.5 ft.

5.2. Test Unit Design

A half-scale test unit was designed to represent the precast pier column, the precast pile cap, and the pile foundation in a prototype bridge because of the great reduction in loading magnitudes and construction costs. The prototype bridge was selected to be a three-span pretensioned prestressed concrete beam (PPCB) bridge that was comparable to one in Linn County, Iowa (BRIDGE NEW – PPCB E.B. IA 100 OVER 16TH AVE. ACCESS IN CITY OF CEDAR RAPIDS on preliminary design drawing). The frame pier of the prototype bridge incorporates a precast pier cap and two precast pier columns. Each pier column is supported by steel driven pile foundation with a precast pile cap, as shown in Figure 5.4.




Figure 5.4. Frame pier of the prototype bridge

Since the test unit modeled only a portion of the prototype pier, only the column, the pile cap, and piles were designed in detail. Further information regarding the design are discussed throughout this chapter.

The design stress for the materials used in the prototype bridge were in accordance with the AASHTO LRFD Bridge Design Specifications (2017). They were a 28 day compressive strength of 4.0 ksi for concrete, Grade 60 for the reinforcing bar, and Grade 50 for the structural steel. Because of the similarity between the prototype bridge and the bridge in Linn County, the column size and longitudinal reinforcement of the prototype bridge were designed to be the same as those of the Linn County bridge. The transverse reinforcement was arranged following the

guidelines for column confinement. The design loading requirements for the piles and the pile cap were determined at the specified limit states, including a strength limit state and a limit state that resulted from the full development of the column flexural capacity, hereafter referred to as the column capacity limit state. The strength limit state was identified to ensure that strength and stability were provided to resist the specified statistically significant load combinations during the design life, and the column capacity limit state was identified to fully exercise the connections within the column/pile cap/pile system. The strength limit states for the prototype bridge were taken as those for the bridge in Linn County. Through moment curvature analysis, the column moment capacity was calculated for determining the loading requirements at the column capacity limit state. By comparing the loading requirements resulting from each limit state, the column capacity limit state that produced the most critical load case governed the design of the piles and the pile cap. Two assumptions were made in the analysis of pile reactions including (1) the pile cap is rigid, and (2) the moment at the pile-to-cap connection can be ignored due to a very small lateral movement of pile cap. These assumptions resulted in a linear distribution of pile forces. Hence, for the given layout, the pile reactions at the column hinge limit state were calculated.

The design of the piles, the pile cap, and the socket connections was based on the AASHTO LRFD Bridge Design Specifications (2017), the Iowa DOT's LRFD Bridge Design Manual (2018), and related research articles. In accordance with the structural check with the recommendations of Structural Resistance Level 1 (SRL-1), the piles were selected to be Grade 50 HP 14×73 for the maximum pile reaction. The corner piles were battered at a 1:6 horizontal to vertical slope to laterally stabilize the pile cap. The design of the pile cap followed the present Iowa DOT design practice. The design guidelines required a minimum distance of 1.5 ft between pile centerline and footing edge, which resulted in the pile cap size of 12 ft × 12 ft. Given a typical pile cap thickness of 4 ft, the reinforcements were designed with respect to bending, one-way shear, and the reinforcement detailing requirements. In addition, the capacity of the two-way shear (punching shear) was checked individually for corner piles. The column socket and the pile sockets on the pile cap were created using CSPs. A 42 in. diameter CSP was chosen for reserving the column socket, which was the slenderest commercially available pipe fitting the 3 ft column. In light of the findings from the socket connection tests and previous related experimental research, the embedment length of the column was chosen to be 1.0 times the column diameter. Combining the product tolerance for the precast column length, the depth of the column socket was designed to be 37.5 in. The column transverse reinforcement was extended to the portion of the column that would be inserted into the socket. The side surface of this embedded portion was roughened by using a chemical formwork retarder, in accordance with the recommendations from the socket connection tests. For constructing the pile sockets, a 30 in. diameter CSP was selected to fit the geometry of the battered piles. As per the Iowa DOT practice, the piles were embedded 1.5 ft into the pile sockets.

The half-scale test unit was designed by appropriately scaling the prototype structure. Given the same materials were used in the test unit and the prototype system, the stresses in the test unit and in the prototype need to be identical to represent the prototype behavior. Thus, all dimensions of the test unit were scaled to half of the prototype pier, and the reinforcements in the test unit were arranged to keep a comparable reinforcement ratio with the prototype. A complete set of drawings for the test unit is provided in the Appendix. The column of the test unit was

scaled to be 1.5 ft in diameter with fourteen #5 longitudinal reinforcing bars, resulting in a longitudinal reinforcement ratio of 1.7%. The column critical region was designed to form plastic flexural capacity. This required #3 reinforcing spiral transverse reinforcement at 3 in. spacing (i.e., a transverse reinforcement ratio of 0.88%) near the column base. Since the column was relatively short, this reinforcement detail was used throughout the column height. The height of the column was chosen to be 7 ft, which resulted in a flexure-critical column with a height/depth ratio of 4.67. A socket embedment length of 1.5 ft was added to the column length, which increased the total design length of the column to 8.5 ft. For the purpose of applying vertical and lateral loads, a 3.5 ft × 3.5 ft × 2 ft loading block was added at the top of the column. The column and the block were integrated by extending the column longitudinal and transverse reinforcements into the block. Horizontal and vertical holes were reserved through the block for attaching the loading devices. Scaling of the HP 14×73 piles resulted in W 6×20 piles for the test unit. For conservativeness, only the unit friction of 1.6 kip/ft, which resulted from scaling the Iowa DOT-recommended design value for HP 14×73 in firm silty glacial clay, was used to estimate the pile nominal geotechnical resistance. The resistance factor was chosen as 0.6 since the Iowa DOT Engineering News-Record (ENR) formula was used. Therefore, the length of piles was determined to be 50 ft to provide adequate geotechnical resistance for the maximum pile reaction. The pile cap of the test unit was scaled to be 6 ft × 6 ft × 2 ft. The bottom-layer and the top-layer reinforcements in each axis were composed of fourteen and twelve #4 reinforcing bars, respectively. The pile cap reinforcements also included the full lapped stirrups with 180° hooks on their ends.

5.3. Test Unit Construction

The test unit used for the system test consisted of a precast column with a loading block at its top, a precast pile cap, and eight W 6×20 as the steel driven pile foundation. The column and the pile cap were constructed in the ISU Structural Engineering Research Laboratory. The reinforcing cage for the loading block was first fabricated on the base formwork. The column reinforcing cage was fabricated on the ground, and then erected into the loading block cage, as shown in Figure 5.5 left.




Figure 5.5. Column reinforcing cage (left) and joint reinforcing bars (right)

The joint reinforcing bars (Figure 5.5 right) were added through the column cage to integrally connect the loading block and the column. The polyvinyl chloride (PVC) pipes were immobilized by stitching wires and circular plywood plugs that were screwed on the formwork. These pipes reserved holes through the loading block for attaching loading devices. After casting the loading block, the column formwork was built by means of concrete tube form. In order to create the exposed aggregate surface on the end portion of the column, formwork retarder was applied on the tube form interior surface prior to placing concrete. However, due to the narrow spacing between the reinforcing cage and the tube form, it was difficult to apply retarder once the tube form was installed in place. Hence, the column formwork was built in two segments. A 6 ft long segment (Segment I), which was for the portion of the column without exposed aggregate surface, was erected on the loading block and braced with a temporary 2 in. by 4 in. falsework. Two layers of plywood ring were screwed on the loading block, and the base of Segment I was inserted into the rings for fixing and sealing purposes. A 1.5 ft long segment (Segment II) was utilized for the portion with exposed aggregate surface. A coating of retarder was applied on the interior surface of this segment 1.5 hours before placing concrete, and Segment II was then spliced to Segment I using a sleeve made of thin rubber sheet, as shown in Figure 5.6.




Figure 5.6. Formwork for column

The tube form was removed three days after placing concrete. The exposed aggregate surface at the column end was finished by power washing. Figure 5.7 shows the completed precast column with a close view of the exposed aggregate surface.



Figure 5.7. Completed precast column (left) and exposed aggregate finish (right)

Before placing concrete for the column, five 3/8 in. diameter threaded rods, which were embedded in the column for attaching instrumentation devices, were installed through holes that were drilled on the tube form. Figure 5.8 illustrates the installation details.




Figure 5.8. Installation details of threaded rods

Plywood plugs were used to seal the holes and immobilize the rods. Round neoprene forms with a length of 1 in. and a diameter of 0.75 in. were placed between the transverse reinforcements and tube form. These forms excluded cover concrete that would have encased the rods. Hence, potential spalling of cover concrete would not affect readings of the instrumentation.

For construction of the pile cap, eight 15 in. long, 15 in. diameter CSPs were first positioned on the base formwork. Each CSP was immobilized by three wood locks that were screwed on the base formwork, as shown in Figure 5.9.



Figure 5.9. CSPs and wood locks

The prefabricated reinforcing cage was then placed around the CSPs. Two types of custom pipe reducer (non-reusable and reusable) were manufactured by a local metal fabricator. Five non-reusable reducers with oversized diameter (Figure 5.10 left) were placed on the top of the pile CSPs.




Figure 5.10. Non-reusable reducer (left), 2 in. × 4 in. reducer supports (center), and reusable reducer (right)

Three reusable reducers with shrunken diameter were placed inside the pile CSPs and temporarily supported by 2 in. × 4 in. wood beams, as shown in Figure 5.10 center and Figure 5.10 right. The gaps between the CSPs and the reducers were sealed using GREAT STUFF Gaps & Cracks foam sealant. After fabricating the reinforcing bars beside the reducers, the side formworks were assembled. A 1 ft 8 in. long, 21 in. diameter CSP for creating the column socket was hanged on the crossing beam that was clamped on the side formwork. The bottom of the CSP was closed by a round plywood with a size slightly less than the inside diameter of the CSP, as shown in Figure 5.11, such that the plywood could be taken out through the CSP.



Figure 5.11. Plywood for closing the CSP with CSP hanger

Ten #8 headed bars were vertically tied on the pile cap reinforcing cage, as shown in Figure 5.12.



Figure 5.12. Pile cap before concrete pour

These bars were extended 1 ft 9 in. above the top of the side formwork for constructing the loading block that would be used for testing the pile foundation. The crossing beam and the plywood for closing the CSP were removed after the concrete was set. The reusable reducers were taken out when the pile cap was lifted off the ground with a crane. A reinforcing steel bar was welded across the diameter of the reducer (Figure 5.13), and then by hammering the reinforcing bar, the reusable reducers were easily taken out through the pile CSP.



Figure 5.13. Taking out reusable reducers

Figure 5.14 shows the completed pile cap.



Figure 5.14. Completed precast pile cap

A foot of soil at the testing site was excavated to remove the top layer that was composed of gravel and cobble. To maintain the piles in the proper position and alignment, a plywood template was nailed on the ground using a bent reinforcing steel bar, as shown in Figure 5.15.



Figure 5.15. Driven pile template

The contractor used a swinging lead with a Delmag D12-42 diesel pile hammer for the pile driving job. To avoid buckling the W 6×20 sections, the pile foundation was constructed by

splicing two short pile sections together. The 31 ft long pile sections were driven first, and the top foot was cut if driving damage appeared on the top of piles. Since no damage eventually occurred, the contractor decided to leave the top foot. After the 29 ft long sections were weld-spliced to the 31 ft long sections by an Iowa DOT-certified welder, as shown in Figure 5.16, the piles were driven 51 ft deep such that the preinstalled instrumentation would be located at the specified depth.



Figure 5.16. Weld-splicing piles

The extra length was cut off, and all piles were trimmed to a horizontal line above the ground. After driving the piles, friction collars were installed on each pile as shown in Figure 5.17.



Figure 5.17. Friction collars and plywood seal-pads

The position of each friction collar was adjusted to levelly support the pile cap. Plywood seal-pads with voids that fit the outline of the piles were placed on the friction collars for sealing the pile sockets. To facilitate removal, the seal-pads were made of two pieces and screwed together.

The pile sockets in the cap mostly fit over the driven piles, except one corner battered pile. Due to the damage on the plywood template that occurred at the end of pile driving process, one corner pile was driven with an offset of about 0.5 in. To eliminate this offset, a chain was tightly attached to the pile in question, and the pile was pulled into the specified position using a loader. After adjustment, the precast pile cap was successfully placed on the friction collars.

After cleaning surface laitance in the column socket, the precast column was erected on the pile cap. Four stainless steel nuts, as shown in Figure 5.18, were placed in the socket to shim the column and to create a grout pad underneath the column.



Figure 5.18. Nut shimmers underneath column (left) and temporary column bracing (right)

The column was temporarily braced with chains, and the column plumb was achieved by adjusting the attached ratcheting binders, as shown in Figure 5.18.

The column socket and the pile sockets were then filled with Rapid Set ULTRAFLOW 4000/8 grout and SCC, respectively, to complete the test unit construction. The grout was poured at one spot and allowed to flow around the column to prevent air void in the grout closure pour, as shown in Figure 5.19.



Figure 5.19. Grout pouring

As the product datasheet suggested, the grout was immediately covered with a wet rag and tarp after pouring to avoid shrinkage cracking. The column bracing was removed 10 hours after the grout pour when the grout compressive strength reached 5,231 psi. After the SCC in the pile sockets reached a compressive strength of 4,614 psi 7 days after the concrete pour, the friction collars were taken off. The completed test unit is shown in Figure 5.20.



Figure 5.20. Completed test unit

5.4. Test Setup

A vertical reaction frame and a lateral reaction column were constructed to load the test unit vertically and laterally, respectively. The vertical reaction frame, as shown in Figure 5.21, was composed of four HP 14×73 anchor piles, a main reaction beam, four hollow hydraulic cylinders, and miscellaneous attachments.




Figure 5.21. Vertical reaction frame

The anchor piles were driven 50 ft deep below ground surface with 9 ft 3 in. left above the ground. The attachments were then bolted on the anchor piles, followed by placement of the main reaction beam (Figure 5.22).



Figure 5.22. Placing main reaction beam

As shown in Figure 5.23, a friction pendulum bearing was installed between the top of the column loading block and the main reaction beam.



Figure 5.23. Single friction pendulum isolator between column and reaction beam

This bearing was used to transfer the vertical loads from the main reaction beam to the column with minimal friction against the lateral load, while allowing translation and rotation of the column. The hydraulic cylinders pushed the main reaction beam down as they were pressured, thereby generating gravity effects on the column while subjecting the anchor piles to tension.

The lateral reaction column, as shown in Figure 5.24, was composed of five precast segments and a drilled shaft foundation.




Figure 5.24. Lateral reaction column

The segments and the shaft were connected using four 1.75 in. diameter 150 ksi Williams post-tensioned (PT) rods. As shown in Figure 5.25, a 2 ft × 2 ft squared void with fillet corners was created in each segment in order to minimize weight and to facilitate handling and transportation.




Figure 5.25. Precast column segment

Next to the four vertical holes that were reserved for PT rods, horizontal hole patterns were created on the side faces of each segment to attach an actuator at different heights for different testing phases. Shear keys were provided between the segments. To ensure desired contact between the segments, the segments were match-cast one on top of the other, as shown in Figure 5.25. In the top segment, additional reinforcing hoops were added in the corners to enhance the post-tension anchorage zone. As shown in Figure 5.26, the drilled shaft foundation was 45 ft deep and was reinforced by twenty-six Grade 60 #11 bars.




Figure 5.26. Drilled shaft details

The top of the shaft was 4 ft below the ground for easy demolition after testing. The reinforcing cage, as shown in Figure 5.27 was tied horizontally on temporary supports and then lifted to the vertical for placing in the borehole.



Figure 5.27. Construction of drilled shaft

Four anchor rods were tied on the cage for embedding into the shaft. To avoid forming a weak section, two rods were embedded 11 ft and the other two were embedded 13 ft into the shaft. The top foot of the anchor rods was debonded using duct tape to prevent unexpected cracking at the top of the shaft. A template was installed on the extended portion of the anchor rods to properly position them prior to and during concrete placement. Concrete was placed by the free-fall method, directing the flow into the center of the shaft. After the concrete set, a layer of hydrostone was poured on top of the shaft. The base segment of the reaction column was set in

place prior to hardening of the hydrostone to ensure the desired contact. The post-tensioned rods were connected to the anchor rods using rod couplers. Following the erection of all precast column segments, construction of the lateral reaction column was finished by post-tensioning the rods to the specified force of 200 kips. As shown in Figure 5.28, a hydraulic actuator controlled by an electric servo pump was laterally attached to the reaction column to apply lateral force on the test unit.



Figure 5.28. Lateral actuator attached on reaction column

As seen in Figure 5.24, the actuator was positioned at two different heights for applying the lateral load at either 7 ft or 1 ft above the top of the pile cap in the different test phases.

5.5. Load Protocol

The system test of the column-pile cap-pile system consisted of six phases. Each phase applied a combination of vertical and lateral load. In each phase, positive (push) and negative (pull) lateral loads were gradually increased in multiple levels up to the target maximum amplitude, with three full cycles at each loading level. The peak load was held constant for about 5 minutes in the first cycle of each loading level. In some levels, this load-holding period was longer to enable inspection of the pile group and documentation of observations.

As shown in Figure 5.29, for Phase I and Phase II, the vertical load was targeted at 250 kips and 100 kips, corresponding to the column axial load ratio of 0.25 and 0.1, respectively.




Figure 5.29. Test protocol for Phase I and Phase II

The lateral load of the first two phases acted at 7 ft above the top of the pile cap to produce a high overturning moment-to-lateral load ratio. The target maximum lateral load of Phase I was equal to 5% of the target vertical load. In Phase II, the lateral load that was expected to cause the column longitudinal reinforcement was achieved in four levels. Subsequently, the test unit was subjected to a reversed cyclic lateral displacement history. The peak of each level was controlled by the measured displacement at the location where the lateral load was applied, and the displacement was increased in levels such that the displacement ductility of 1, 1.5, 2, 3, 4, and 6 could be achieved with the lateral displacement of 1.25 in. corresponding to ductility 1.

After Phase II, the lateral load was lowered to 1 ft above the top of the pile cap to reduce the moment-to-load ratio. As shown in Figure 5.30, for Phase III, the target vertical load was 250 kips, and the target maximum lateral load was ± 140 kips.




Figure 5.30. Loading protocol for test Phases III through VI

For Phase IV, the target vertical load was reduced to 100 kips, and the target maximum lateral load was 220 kips. However, the applied negative lateral load was limited by the actuator capacity and therefore only achieved an amplitude of -150 kips. Phase V and Phase VI were conducted to examine the pile group and the pile connections under extreme loading conditions. The target vertical load for Phase V was 250 kips, and was reduced to 0 kips in Phase VI. The maximum applied lateral loads for Phase V and Phase VI were 225 kips and -150 kips, respectively.

5.6. Instrumentation

The exterior instrumentation included calibrated load cells and displacement transducers mounted to the column, pile cap, and piles. In addition, the test unit was heavily instrumented with over 130 strain gauges attached to the reinforcements and piles. Data from the instruments were collected using acquisition systems at a recording frequency of 5 Hz.

Figure 5.31 through Figure 5.35 show the plan view of the strain gauges in the precast column and the precast pile cap.




Figure 5.31. Strain gauges on column reinforcements




Figure 5.32. Strain gauges on CSPs of column socket and pile sockets




Figure 5.33. Strain gauges on pile cap reinforcements




Figure 5.34. Strain gauges on embedded piles




Figure 5.35. Strain gauges on the piles driven into ground

These strain gauges were attached to the selected longitudinal and transverse reinforcements in the column, CSPs of the column socket and the pile sockets, flexural reinforcements, diagonal headed bars, and vertical stirrups in the pile cap. The selected steel H-piles were also instrumented with strain gauges that were attached on the portions embedded in the sockets and the portions driven into the ground.

As shown in Figure 5.36, Bridge Diagnostics Inc. (BDI) strain transducers were installed on the selected H-piles.




Figure 5.36. Layout and location of BDI strain transducers

These transducers were placed 2 in. below the base of the pile cap. The displacements of the test unit were extensively measured using string pots, linear variable differential transformers (LVDTs), a clinometer, and a Northern Digital Inc. (NDI) optical measurement system. Figure 5.37 and Figure 5.38 present the plan view of these displacement transducers.




Figure 5.37. Layout of displacement transducers




Figure 5.38. Layout of markers for NDI optical measurement system

5.7. Test Results

To aid in the description and discussion of the test unit, the lateral load orientation is defined as follows: the push direction is away from the lateral reaction column, and the pull direction is toward the lateral reaction column. The pile nomenclature and the pile cap orientation are defined as shown in Figure 5.39.




Figure 5.39. Pile nomenclature

5.7.1. Observations

In Phase I, no cracking or any other damage was observed on column. Due to about 0.75 in. eccentricity of the vertical load resulting from construction tolerance, the column displaced toward the push direction with increase in vertical loads. However, under the full vertical load of 250 kips, the lateral displacement of the column at the height of the horizontal actuator, hereafter referred to as the column top displacement, was negligible. Under the cyclic lateral loads of Phase I, the column top displacement did not exceed 0.48 in. (Figure 5.40 left).



Figure 5.40. Column drift at the end of Phase I (left) and Phase II (right)

During Phase II, the column experienced displacement up to 7.5 in. at the height of the horizontal actuator, as shown on the right in Figure 5.40. The primary damage occurred at the base of the column as intended. Flexural cracks began to develop at the column base when the applied lateral loads reached 25.2 kips. Cracking continued to develop over the lower 36 in. of the column as testing progressed and the column lateral displacement was progressively

increased. Figure 5.41 left shows the cracks at the column base, in which the cracks that formed in the push and pull cycles were marked in red and blue, respectively.




Figure 5.41. Damage at the column base: flexural cracks (left) and cover concrete spalling (right)

When the column top displacement reached 1.875 in., the concrete cover right above the pile cap began spalling. The extent of spalling increased during the loading cycles of 2.5 in., and the spiral and longitudinal bars were exposed during the loading cycles of 3.75 in. (Figure 5.41 right). During the loading cycles to 5 in., concrete damage extended to the core concrete, and a longitudinal reinforcement buckled between two adjacent spirals near the column base, as shown in Figure 5.42.



Figure 5.42. Buckling of longitudinal reinforcing bar

When the column top displacement was first increased to 7.5 in., the longitudinal reinforcement that buckled in previous load step fractured in tension. As the column cycled at the displacement of 7.5 in., multiple column longitudinal reinforcements fractured, and a significant part of the core concrete was crushed. The damage on the column base at the end of Phase II was shown in Figure 5.43.



Figure 5.43. Column base at the end of Phase II

At the end of Phase I, no damage was observed on any of the column-to-pile cap connection or the pile-to-pile cap connections, as shown in Figure 5.44.



Figure 5.44. No damage on column connection (left) and pile connection at the end of Phase I, (right)

In Phase II, a circular crack, as shown on the left in Figure 5.45, appeared at the interface between the column and the grout closure pour under the applied lateral load of 25.2 kips, and afterward this crack progressed around the column (Figure 5.45 right).



Figure 5.45. Crack at column-to-grout pour interface

Starting with a crack at the grout closure pour-to-CSP interface that formed during the cycles of 1.25 in., the top layer of the grout closure pour spalled as the column cycled. At the end of Phase II, about 0.75 in. of the grout closure pour thickness had spalled off (Figure 5.46), but the column connection maintained its integrity. All pile-to-pile cap connections remained undamaged during Phase II.



Figure 5.46. Spalling of grout closure pour at the end of Phase II

During Phase III, when the lateral loads reached 140 kips, cracks appeared in the connections of the two straight Piles 4 and 5 in succession, but no damage occurred in the other pile-to-pile cap connections. The crack adjacent to Pile 4 expanded as the lateral loads exceeded 160 kips during Phase IV (Figure 5.47a).




Figure 5.47. Observations of the piles and their connections

Under the maximum lateral load applied during Phase IV, yielding was visible on the flanges of Piles 2 and 7 (Figure 5.47b), and battered Piles 3 and 8 slightly pulled out from the pile cap. The high vertical load of Phase V induced additional compression in the piles, thereby impeding the progression of tensile damage in the pile-to-cap connections. Under the combination of the zero vertical load and 225 kips lateral load in Phase VI, the connections of battered Piles 3 and 8 failed in tension (Figure 5.47c), one flange of Piles 1 and 6 buckled (Figure 5.47d), and rotation of Piles 2 and 7 was visible (Figure 5.47e). The formation of gaps between the piles and cohesive soil initiated in Phase II, and the gap width continually grew as the pile group was subjected to cyclic loads in subsequent phases. As shown in Figure 5.47f, the maximum permanent gap at the end of Phase VI was approximately 6 in.

5.7.2. Column Load-Displacement Response

In Figure 5.48 the applied vertical load is shown with respect to the column top displacement.




Figure 5.48. Vertical load as a function of column top displacement

As the column laterally displaced with respect to the main reaction beam, the beam was pushed up due to the concave shape of the bearing base, and thus the hollow hydraulic cylinders for applying vertical load were compressed. As a result, the vertical load increased with the increase of the column displacement. The asymmetry between loads in the push direction (positive displacement) and the pull direction (negative displacement) was caused by an initial eccentricity of the vertical load resulting from the construction tolerance. To avoid overloading the test unit during Phase II, the applied vertical load was intentionally reduced twice when the displacement reached -2.5 in. and -3.75 in..

As illustrated in Figure 5.49, the presence of vertical load caused some lateral resistance at the top of the column due to friction in the pendulum bearing.




Figure 5.49. Lateral load acting on test unit

Therefore, the lateral load transferred to the column, which will be referred to as the column lateral resistance, was not equal to the load applied by the actuator and had to be determined by other means as detailed below.

Two gauges (L_1_48 and L_4_48) captured strains in two extreme column reinforcing bars at a height of 48 in. above the top of the pile cap. The curvature at this height was obtained from the strain measured in one gauge with respect to the other as detailed below:

$$\phi = \frac{\varepsilon_1 - \varepsilon_2}{l_w}$$

where, ε_1 and ε_2 are the strains measured by two gauges, and l_w is the distance between the two gauges. The theoretical moment-curvature relationships were developed for the as-built column section under various axial forces. Therefore, the moment at the section 48 in. above the top of the pile cap was estimated from the theoretical moment-curvature plots shown in Figure 5.50. Note that the moment estimated at the reference section included the component resulting from the P- Δ effect.




Figure 5.50. Moments estimated at the section 48 in. above top of the pile cap

As illustrated by Figure 5.51, the column lateral resistance was calculated as follows:

$$F = \frac{M - P\Delta_1}{h_1}$$

where,

F = column lateral resistance

M = moment estimated at the reference section

P = vertical load

Δ_1 and Δ_2 = eccentricities of the vertical load measured at the reference section and the column base

h_1 and h_2 = distances from where the lateral load was applied to the reference section and the column base




Figure 5.51. Calculation of column lateral resistance

Figure 5.52 presents the moment component at the column base resulting from the estimated column lateral resistance (Fh_2) and the component resulting from the vertical load ($P\Delta_2$), which represents the column lateral response.




Figure 5.52. Column base moment versus column lateral displacement

The column remained elastic during Phase I testing, but it experienced stable nonlinear response with dependable hysteresis loops during Phase II testing. The response remained essentially elastic up to the column lateral deformation of ± 0.98 in., beyond which inelastic behavior dominated the response with a slight positive slope. The maximum moments reached in the push and pull directions were 2,496 kip-in. and -2,434 kip-in., which were estimated at the column displacements of 3.31 in. and 2.30 in., respectively. The first drop of the column base moment occurred when the column displacement reached 4.57 in. due to the damage that occurred to the

core concrete and buckling of a longitudinal reinforcement. As the column was displaced to 7.13 in. in the push direction, one column longitudinal reinforcement fractured in the plastic hinge region, causing a further drop in moment resistance. As more reinforcements fractured when the column was pulled to the deformation of -7.5 in., significant strength degradation occurred.

5.7.3. Pile Cap Load-Displacement Response

The load-displacement responses for the pile group during the different test phases are shown in Figure 5.53, which contains the lateral load transferred to the pile cap versus the displacements measured at the mid-depth of the pile cap. For ease of comparison, the plots are presented with the same scales for both axes.




Figure 5.53. Lateral load-displacement response measured at pile cap

The load-displacement response remained linearly elastic for the duration of Phase I and II. The backbone of the response for Phase III was approximately linear, whereas the responses during individual loading cycles exhibited slight nonlinearities. This phenomenon was due to the

formation of permanent gaps between the piles and cohesive soil. When the pile group first reached a given displacement, the applied lateral load was resisted by the pile stiffness and soil pressure. As the load on the pile group was cycled, gaps developed next to the piles. For pile displacements less than the width of the gap, the resistance was only due to the pile stiffness. As the piles approached the previous maximum displacement, the piles engaged the soil, which progressively provided additional resistance, causing the observed increase in the stiffness of the load-displacement response of the pile group.

For Phase IV, the response under negative load was similar to that for the last loading step of Phase III, but the displacement slightly increased due to progressive plastic failure of the soil as the load on the pile group was cycled at the same negative load level. When the positive lateral load of Phase IV exceeded 124 kips, the slope of the response backbone gradually decreased, which was mainly associated with yielding of the piles and damage in the pile-to-pile cap connections. Creep under constant load occurred during the load-hold periods of the positive loading levels of 182 kips, 200 kips, and 206 kips for Phase IV.

During Phase V, as the high vertical load induced additional compression in the piles, no further significant damage was observed, and the hysteresis responses for the three cycles of each loading level were stable. An exception was the last loading step, in which soil creep occurred during the load-holding period. As evidenced by the tensile failure of the pile connections and buckling of the piles documented at the end of the test, the reduction of vertical load in Phase VI triggered failure of the pile group, causing the continuous increase of lateral displacement under a sustained lateral load of 225 kips.

5.7.4. Pile Cap Moment-Rotation Response

The lateral load applied above the pile cap produced overturning moments acting on the pile cap in all loading phases of the test. The relationships between the overturning moment and pile cap rotation are presented in Figure 5.54.




Figure 5.54. Moment rotation response measured at pile cap

For the duration of Phase I, the moment-rotation response remained linearly elastic. As gaps formed between the piles and soil during Phase II, the moment-rotation response exhibited some nonlinearity but remained elastic. Following the first two phases, the height of lateral load was lowered from 7 ft to 1 ft above the top of the pile cap. As a result, the overturning moment-to-lateral load ratios for the subsequent phases were significantly lower than those for Phases I and II, causing noticeable reductions in the slopes of the moment-rotation responses.

During Phase III, the moment-rotation response exhibited increasing amounts of nonlinearity as the pile-to-soil gaps expanded. Subsequent to the moment reaching 195 kip-ft in Phase IV, the slope of the moment-rotation backbone response decreased, and the hysteresis loop widened. This degradation was associated with damage occurring in the piles and pile-to-pile cap connections, especially pull-out of the battered Piles 3 and 8. For Phase V, the nonlinearity of the moment-rotation response became more pronounced as the gaps around the piles continually grew. The high vertical load in this phase impeded the progression of tensile damage in the pile connections, and thus maintained a stable hysteretic response. With the vertical load reduced to

zero in Phase VI, tension failure of the connections caused the significant deterioration in the moment-rotation response.

5.7.5. Pile Head Forces

The loads acting on the test unit were transferred through the pile group, hence the eight steel H-piles, capped with the pile cap, were subjected to axial force, moment, and shear. As mentioned earlier, BDI strain transducers were installed on a select number of piles. These transducers captured the deformation within the gauge length of 3 in.; therefore, the average axial forces and the moments at the head of Piles 1, 2, 3, 4, and 6 were determined from the measurements of the BDI transducers. In addition, strain gauges captured the forces of Pile 5. With a few exceptions, these instrumentations provided good measurements for the duration of Phase I and Phase II.

The histories of pile head moment are plotted in Figure 5.55 as a function of the moment at the bottom of the pile cap.




Figure 5.55. Pile head moment as a function of moment at the bottom of the pile cap

Because the lateral movement of the pile cap was small, the moments at the pile heads remained low. Therefore, the vertical load and the overturning moment were transferred to the soil mainly in terms of axial forces in the piles.

As shown in Figure 5.56, the axial forces acting on the head of Piles 1, 2, 3, 4, 5, and 6 are plotted as a function of pile cap bottom moment.




Figure 5.56. Pile axial force as a function of moment at the bottom of the pile cap

The figures confirm the regular relationship between the axial forces and the pile cap bottom moment. For Phase I, after the application of a vertical load of 250 kips, the measurements indicated that each pile was subjected to the approximately uniform distributed axial force of 30 kips. As the moment at the bottom of the pile cap increased, the axial force in the rows far from the pile cap centerline (i.e., the row of Piles 1, 4, and 6 and the row of Piles 3 and 5) fairly linearly increased or decreased. The axial force in Pile 2, as it was close to the centerline of the pile cap, exhibited a weak relationship with the pile cap moment.

For Phase II, the initial vertical load was decreased to 100 kips, and the measured initial pile axial forces accordingly dropped to approximately 12 kips. Because of the lower vertical load and the higher moment at the bottom of the pile cap in Phase II, the piles in the extreme rows were subjected to tension up to approximately 10 kips, but the magnitudes of pile axial compression did not exceed those of Phase I. The relationship between the variation of pile axial force and the superimposed moment was similar to that observed in Phase I.

5.7.6. Pile Head Movement

The NDI optical measurement system captured the movement of the pile head and the pile cap, thereby determining the pile displacements with respect to the pile cap. Figure 5.57 presents the pile vertical displacement with respect to the pile cap for Piles 1, 2, and 3, as a function of pile axial force.




Figure 5.57. Pile vertical displacement with respect to the pile cap

The negative displacement values imply a penetration of the piles into the pile cap. For the duration of Phase I and Phase II, the measured pile displacement was negligible. The pile head moment for Piles 1, 2, 4, and 6 are also shown in Figure 5.58 as a function of pile rotations with respect to the pile cap.





Figure 5.58. Pile rotation with respect to the pile cap

The plots are scattered because the magnitude of the rotation was close to the resolution of the measurement system. However, a linearly elastic relationship was recognized between the pile head moment and pile rotation.

5.7.7. Column Reinforcement Strain

Two extreme column longitudinal reinforcements (i.e., Bar 1 and 4) were instrumented with strain gauges; thus, the strains along the height of these two bars were captured. The strain histories recorded by each strain gauge are shown in Figure 5.59.






Figure 5.59. Strain history of column longitudinal reinforcement

In the figure, the strain was plotted with respect to the lateral load acting on the top of the column, and the location of each gauge was indicated. Strain gauges within the column base

region were damaged during Phase II; therefore, higher strains could have occurred but were not properly recorded.

Figure 5.60 and Figure 5.61 present the strain profiles obtained for these two bars for the push (positive load) and pull cycles (negative load) during Phase I and Phase II testing.




Figure 5.60. Strain profile along two column longitudinal reinforcements for Phase I




Figure 5.61. Strain profile along two column longitudinal reinforcements for Phase II

The strain values shown here are those recorded when the peak loads were first achieved during the loading cycles, and the positive values represent tensile strains. The ordinate indicates the distance of the strain gauge from the top of the pile cap. During Phase I, the strains were far below the yielding strain, and the profiles were approximately linear along the height. The strains were largest at 6 in. above the top of the pile cap and decreased down into the pile cap and up into the column. Within the the pile cap, the strain penetration is seen, but the magnitude of measured strains abruptly decreased to a fraction of that measured at the top of the pile cap. The strains were negligible for the portion beyond 6 in. below the pile cap top.

For Phase II testing, the tensile strains significantly increased. Prior to the lateral load exceeding 13.1 kips, the strains remained below the yielding strain, and the profiles stayed approximately linear. As the load increased, for push cycles, the profile indicated that the reinforcing bar between the pile cap top and the height of 12 in. above the pile cap top yielded, and the largest strains occurred at the top of pile cap. The tensile strains during the pull cycles were higher than those recorded in the push cycles, whereas the reinforcing bar yielding was limited to the column base region below the height of 24 in. Reinforcement yielding also penetrated up to 6 in. into the pile cap, but the magnitude of measured strains abruptly decreased to a fraction of that measured at the top of the pile cap. From 12 in. below the pile cap, the values remained below 50% of the yielding strain for the duration of Phase II testing.

5.7.8. Column Socket CSP Strain

The strain profiles at the south and north sides of the CSP of the column socket are shown in Figure 5.62 and Figure 5.63, in which the readings from a gauge that was placed at the east side of the CSP are presented as well.




Figure 5.62. Strain profile of column socket CSP for Phase I




Figure 5.63. Strain profile of column socket CSP for Phase II

With the largest reading of $170 \mu\epsilon$, the strains in the CSP remained far below the yielding value for the duration of Phase I and Phase II. The strains at the north side of the CSP consistently varied with the application of the lateral loads. Generally, the gauges captured compressive strains for the push cycles and tensile strains for the pull cycles. Few exceptions occurred when relatively large pull loads were applied. The strain profiles at the north side exhibited some irregularities in Phase II, which could be attributed to systematic errors in the strain gauges. In the bottom third of the CSP, the strains were negligible regardless of the magnitude of lateral load.

5.7.9. Pile Cap Reinforcement Strain

One quarter of the pile cap was heavily instrumented to capture its response. Of the many strain gauges mounted on the reinforcement of the pile cap, the variation of strain as a function of lateral load is shown only for a few selected gauges that were placed on the bottom reinforcing mat. For the duration of the test, strain gauge readings were small; hence, the strain drift over time due to systematic errors was visible. Strain histories of the gauges that were mounted on the four reinforcing bars parallel to the loading direction are presented in Figure 5.64.




Figure 5.64. Strain history of pile cap reinforcement perpendicular to the loading direction

As indicated in the figure, the gauges were placed along a plane right next to the column and perpendicular to the loading direction. The lateral load did not produce any variation on the readings of BF2, as it was located close to the edge of the pile cap. The readings from BF5, BF6, and BF9, in contrast, increased in a roughly linear fashion as the positive load (i.e., push load) was applied, while the application of negative load (i.e., pull load) reduced the readings from these gauges. As seen in the histories, the recorded strains did not exceed $40 \mu\epsilon$, and the majority of the variation was due to the strain drift. Strain profiles obtained from these histories are shown in Figure 5.65.




Figure 5.65. Strain profile of pile cap reinforcement perpendicular to the loading direction

The ordinate indicates the distance of the strain gauge from the center of the pile cap. The irregularity appearing in Phase II was attributed to the strain drift over time. As observed, the gauges close to the center of the pile cap (i.e., BF5, BF6, and BF9) exhibited greater variation, and the readings of these three gauges were somewhat comparable. Under a similar lateral load (i.e., the lateral load of 17 kips in Phase I and 18 kips in Phase II), the recorded strains in Phase I were slightly higher than those recorded in Phase II.

A number of gauges were placed on two of the pile cap reinforcements parallel to the loading direction, hereafter referred to as Cap Bar A and Cap Bar B, and the reading obtained from five gauges are presented in Figure 5.66.




Figure 5.66. Strain history of pile cap reinforcement parallel to the loading direction

For the gauges located within the portion from the pile centerline to the edge of the pile cap (i.e., BF3, BF4, and BF8), the readings remained low and did not vary with the lateral load. For BF5 and BF9, as seen in the figure, there is an approximately linear correlation between the strain readings and the lateral load. In addition, the strain drift of BF9 was seen. As shown in Figure 5.67, two sets of strain profiles were plotted for Cap Bar A and Cap Bar B, respectively.




Figure 5.67. Strain profile of pile cap reinforcement parallel to the loading direction

The profiles were obtained from the readings under pushing lateral loads, and the missing strain readings at the end of Cap Bar B were assumed to be zero. The distance from the gauges to the center of the pile cap is shown on the horizontal axis. The strains were only induced in the gauges located between the piles and the column (i.e., BF5 and BF9). The recorded strains in Phase I were slightly higher than those recorded in Phase II. During a single phase, in other words, under the same vertical load, the strains increased with rising lateral load. An exception was observed for the profile of Cap Bar B under 31 kips lateral load, which was attributed to the drift of recorded strains.

Three strain gauges were placed on one of the headed reinforcements in the bottom reinforcing mat. The strain histories of these gauges and their profiles are presented in Figure 5.68 and Figure 5.69, respectively.




Figure 5.68. Strain history of headed reinforcement in the pile cap




Figure 5.69. Strain profile of headed reinforcement in the pile cap

The histories are plotted with respect to lateral load, and the horizontal axis of the profiles indicates the distance from the gauges to the head of the bar. The magnitude of the strains remained low for the duration of Phase I and II. The strain drift was visible in the strain histories. The drifting rates for BF13 and BF14 were comparable, whereas the readings of BF15 drifted at a higher rate. An approximately linear relationship could be observed between the recorded strains and the lateral load. For the gauges located farther away from the head, the strain variation was greater. The profiles were roughly straight lines, except for the 31 kips load during Phase II, which was attributed to the greater drift in the readings of BF15. It was also observed that the profile slopes for Phase I were slightly higher than those obtained from Phase II.

5.7.10. Embedded Pile Strain

Strain gauges were mounted on the embedded portion of three piles (i.e., Piles 1, 2, and 4). For each pile, one gauge was placed at the connection interface (i.e., the bottom of the pile cap), and another was located at the mid-depth of the embedded pile (at 4.5 in. from the interface). To ensure comparability in the strain readings, both gauges were mounted along the centerline of the pile's web. The strain histories obtained from the gauges on each pile are presented in Figure 5.70, in which the strain is plotted as a function of pile axial force.




Figure 5.70. Strain history of embedded pile head

For Phase I and Phase II, the recorded pile strains did not exceed 18% of the yield strain, and the strains increased fairly linearly as the pile axial forces increased. Figure 5.71 presents the strain profiles for the embedded pile heads under various pile axial forces.




Figure 5.71. Strain profile of embedded pile head

To develop these profiles, the strain at the top end of the pile was assumed to be zero. However, due to end bearing, the end of pile could be subjected to compressive strains. For Piles 1 and 4, the strains at the mid-depth of the embedded portion decreased to approximately half of their values at the interface regardless of the magnitude of pile axial force, whereas the mid-depth

strains of Pile 2 were higher than half of the interface strains when the pile compressive force exceeded 22 kips.

5.8. Discussion

5.8.1. Column Socket and Pile Socket Connections

Visual observations indicated that, except for limited crushing and spalling of the grout closure pour near the top of the column socket toward the end of the Phase II test, the connections remained mostly damage-free when the column flexural capacity was fully developed. The strain profiles along the column longitudinal reinforcement embedded into the pile cap reflected the force transfer within the connection. In Phase I, with a high axial load and low magnitude lateral forces, the force transfer effectively took place within the top half of the connection, with negligible strains in the column bars in the bottom half of the connection. In Phase II, the column bars strains penetrated deeper into the connection. However, the measured strains confirmed that the provided column embedment length equaling the column diameter was sufficient to develop the column flexural capacity outside the connection above the pile cap. The force transfer capacity of the socket connection was also adequately supported by the CSP. The strain profiles from the CSP also confirmed that the bottom half of the connection did not actively participate in anchoring the column bars into the socket connection. Based on these observations, it can be concluded that flexural columns with axial load ratios similar to those used in testing can be adequately anchored with a socket connection using an embedment length equal to the column diameter. Furthermore, the thickness of the CSP could be reduced by as much as 50% or more without compromising the connection performance.

No damage was observed on the pile socket connections during Phase I and Phase II testing, allowing the pile-to-pile cap connection to remain fixed. The force transfer capacity of the socket connections was reflected by the approximately linear strain profiles along the embedded length of the piles. By embedding the piles 9 in. (i.e., 1.5 times the pile section depth) into the sockets, the connections effectively transferred pile forces to the pile cap, confirming the sufficiency of the pile embedment length. During Phase III to VI, the piles pulled out due to the significant tensile forces, and the pile socket connections were damaged in a ductile manner.

5.8.2. Foundation Flexibility

For the column-pile cap-pile system, it is important to recognize the foundation flexibility, which can be quantified using the measured pile cap response. The lateral load-translation response demonstrates that, as the design required, the foundation remained linearly elastic and damage-free when the column flexural capacity was fully developed at the end of Phase II. The backbone of the response for Phase III was approximately linear, whereas the formation of permanent gaps between the piles and cohesive soil contributed to the nonlinear responses during lateral cyclic loading. Creep under a constant lateral load occurred during the load-hold periods of the positive loading levels for Phase IV.

The effects of foundation flexibility on the system response were quantified in terms of column top lateral displacement. As illustrated in Figure 5.72 left, lateral displacement at the top of the column was induced by column deformation and two other components resulting from pile cap lateral translation and pile cap rotation, respectively.




Figure 5.72. Components of column top displacement (left) and their proportions for Phase I and Phase II (right)

Figure 5.72 right presents the proportions of each component in the column top displacement under various effective lateral loads in Phase I and Phase II. For the duration of Phase I, about 40% of column top displacement was induced by the foundation flexibility, and this proportion remained approximately constant regardless of the magnitude of effective lateral loads. Furthermore, the components due to pile cap translation and rotation remained similar. As the lateral load increased in Phase II, the damage progressed at the base of the column, and the column deformation dominated the column top lateral displacement. The foundation, in contrast, maintained a linearly elastic response and produced less effect on the system’s response, whereas the combined proportion of pile cap translation and rotation components still accounted for 10% of the column top displacement when the effective lateral load reached its maximum resistance of 32.3 kips. The great proportions of column top displacement that resulted from pile cap translation and rotation reflect the significant effect of foundation flexibility. Note that the experiment was conducted at a site of stiff clay, which is generally assumed to provide a fixed foundation condition in routine design practices. However, this assumption would not be accurate as demonstrated by the outdoor test.

5.8.3. Constructability

Based on the experimental investigation and analyses of test data presented herein, the precast pile cap with column socket and pile sockets provides great potential for use in routine practices due to its ease of construction. The sockets can be easily established by commercially available CSPs serving as stay-in-place formwork. Chemical formwork retarder was found to be an efficient method to achieve the desirable surface roughness at the end of the column. The use of friction collars allows quick assembly of the system in all types of ground conditions and facilitates better control on erection tolerances. The closure pour for the column socket went smoothly due to the following desirable features of the grout: high early strength, extended working time, and appropriate fluid consistency.

CHAPTER 6. SUMMARY AND CONCLUSIONS

The focus of this report was to investigate the structural performance of a bridge column/footing/pile system for ABC. Given the numerous advantages over conventional construction, this study sought to develop a fully prefabricated column/footing/pile system. In light of the current state of the art, a suitable prefabricated column-pile cap-pile system was developed. The system consists of a precast column, precast pile cap, and pile foundation. The components are integrally connected utilizing a column socket connection and pile socket connections that are preformed in the pile cap with corrugated steel pipes (CSPs).

To evaluate the side shear strength of the column socket connection with various connection parameters, column socket connection tests were performed using eight specimens that modeled the full-scale connection interfaces. Each specimen consisted of a short precast column segment that was embedded in a socket on a precast foundation. When a compressive force was applied to the top of the column segment, the side shear acting on the connection interface produced resistance. Thus, the side shear strength could be evaluated by loading the column segment until it experienced a sliding failure with respect to the foundation. The specimens were constructed with different surface texture for the embedded portion of the column segment and CSP-to-column segment clearance. They were tested by subjecting them to monotonic and cyclic axial loading. Test results showed that the side shear mechanism in the column socket connections can provide significant resistance, facilitating transfer of large vertical loads.

An outdoor system test was subsequently conducted on the column/footing/pile system at a cohesive soil site. The test unit was constructed as a half-scale representation of the column-pile cap-pile system utilizing a precast column, a precast pile cap, four vertical steel piles, and four battered piles. The test unit was first subjected to combined vertical and lateral loads applied to the top of the column. All components as well as their connections remained undamaged when subjected to the load combination representing the design limit state. With the lateral load and column displacement gradually increased beyond the design demand, damage occurred at the base of the column as expected, and the column socket connection and pile socket connections maintained fixity, confirming the structural sufficiency of the system. After casting a concrete block on top of the pile cap surrounding the damaged column, the foundation of the test unit was further tested under different combinations of vertical and lateral loads. Not only were the magnitude of the loads changed, but the height of the lateral load was also varied to produce different overturning moment-to-lateral load ratios. The foundation exhibited significant resistance to the combined vertical and lateral loads and eventually failed well beyond the targeted design forces due to the combined effects of pile buckling, damage to the pile socket connections, and formation of permanent gaps between the piles and cohesive soil. Based on the test results, the following conclusions can be drawn:

- For the column socket connection, the intentionally roughened column surface, as required by AASHTO, is necessary to develop satisfactory side shear strength to sustain axial loads used in routine design practice.

- The column surface textures with deep amplitude (e.g., fluted fins) exhibited softer connection responses compared to the one with exposed aggregate surface finish. Thicker grout closure pour resulting from wider CSP-to-column clearance also marginally reduced the stiffness of the socket connection.
- Exposed aggregate for column surface preparation, standard CSP, and high-strength grout are recommended for establishing socket connections effectively. For connections established as described in this study, the side shear stress limitations of 1,000 psi and 700 psi are suggested, respectively, for the column-to-grout interface and CSP-to-surrounding concrete interface to determine the minimum depth of the preformed socket.
- The half-scale test unit representing a column/footing/pile system produced dependable performance when subjected to combined vertical and lateral forces. These loads represented factored design loads. There was no damage to the column socket and pile sockets connections.
- When the lateral force was gradually increased beyond the design demand, damage occurred to the column base as intended in design, and superficial crushing and spalling was observed in the column socket connection region with no damage occurring to the pile connections, confirming the adequacy of all connections. This observation confirmed that the performance of the prefabricated column-pile cap-pile system was at least as good as, if not better than, a comparable conventional cast-in-place system.
- For the column socket connection, the embedment length equal to the column diameter is sufficient to fully develop the column flexural capacity, whereas the pile embedment length of 1.5 times the depth of pile is recommended to maintain the fixity of the pile sockets connection.
- Foundation flexibility produced a significant effect on the system response. About 40% of the column top lateral displacement was due to the foundation flexibility prior to the development of inelastic strains induced in the column. As the damage progressed in the column, the foundation flexibility had reduced effect on the column top lateral displacement, while it still accounted for an important component when the column lateral resistance reached its maximum.
- The constructability advantages of the prefabricated column-pile cap-pile system are that it is quick and simple to build, which have been sufficiently demonstrated. The precast column and precast pile cap with no projected reinforcement are easy to build and transport and are unlikely to be damaged during construction. With the use of friction collars and grout with desirable characteristics (including high early strength, extended working time, and appropriate fluid consistency), the assembly of the column-pile cap-pile system can be completed within a day.

REFERENCES






- AASHTO. 2016. *AASHTO M 218: Standard Specification for Steel Sheet, Zinc-Coated Galvanized, for Corrugated Steel Pipe*. American Association of State Highway and Transportation Officials, Washington, DC.
- AASHTO. 2017. *AASHTO LRFD Bridge Design Specifications*. 8th edition. American Association of State Highway and Transportation Officials, Washington, DC.
- ABC-UTC. 2018. Accelerated Bridge Construction University Transportation Center. <https://abc-utc.fiu.edu/>. Accessed April 2018.
- ASCE. 2017. *2017 Infrastructure Report Card: Bridges*. American Society of Civil Engineers, Washington, DC. <https://www.infrastructurereportcard.org/wp-content/uploads/2017/01/Bridges-Final.pdf>.
- ASTM International. 2016. *ASTM C109: Standard Test Method for Compressive Strength of Hydraulic Cement Mortars (Using 2-in. or [50-mm] Cube Specimens)*. ASTM International, West Conshohocken, PA.
- ASTM International. 2017. *ASTM C39: Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens*. ASTM International, West Conshohocken, PA.
- CTS Cement. 2019. *Rapid Set ULTRAFLOW® 4000/8 Non-Shrink Precision Grout*. CTS Cement Manufacturing Corp., Garden Grove, CA. https://www.ctscement.com/assets/doc/datasheets/ULTRAFLOW_Datasheet_DS_112_EN.pdf.
- Culmo, M. P. 2009. *Connection Details for Prefabricated Bridge Elements and Systems*. FHWA-IF-09-010, Federal Highway Administration, Highways for LIFE Program, McLean, VA.
- Culmo, M. P. 2011. *Accelerated Bridge Construction – Experience in Design, Fabrication, and Erection of Prefabricated Bridge Elements and Systems*. Final Manual. FHWA-HIF-12-013. Federal Highway Administration, Highways for LIFE Program, McLean, VA.
- Haber, Z. B., M. S. Saiidi, and D. H. Sanders. 2013. *Precast Column-Footing Connections for Accelerated Bridge Construction in Seismic Zones*. Center for Civil Engineering Earthquake Research, University of Nevada, Reno, NV.
- Haraldsson, O. S., T. M. Janes, M. O. Eberhard, and J. F. Stanton. 2013. *Precast Bent System for High Seismic Regions – Laboratory Tests of Column-to-Footing Socket Connections*. FHWA-HIF-13-039. Federal Highway Administration, Highways for LIFE Program, Washington, DC.
- Iowa DOT. 2018. *LRFD Bridge Design Manual*. Iowa Department of Transportation, Bridges and Structures, Ames, IA.
- Kavianipour, F. and M. S. Saiidi. 2013. Experimental and Analytical Seismic Studies of a Four-Span Bridge System with Composite Piers. Center for Civil Engineering Earthquake Research, Department of Civil and Environmental Engineering, University of Nevada, Reno, NV.
- Marsh, M. L., M. Wernli, B. E. Garrett, J. F. Stanton, M. O. Eberhard, and M. D. Weinert. 2011. *NCHRP Report 698: Application of Accelerated Bridge Construction Connections in Moderate-to-High Seismic Regions*. National Cooperative Highway Research Program, Washington, DC.
- Mashal, M. and A. Palermo. 2015. High-Damage and Low-Damage Seismic Design Technologies for Accelerated Bridge Construction. *Structures Congress 2015*, April 23–25, Portland, OR, pp. 549–560.

- Mehrsorouh, A. and M. S. Saiidi. 2016. Cyclic Response of Precast Bridge Piers with Novel Column-Base Pipe Pins and Pocket Cap Beam Connections. *Journal of Bridge Engineering*, Vol. 21, No. 4, pp. 1–13.
- Mohebbi, A., M. S. Saiidi, and A. Itani. 2017. *Development and Seismic Evaluation of Pier Systems with Pocket Connections, CFRP Tendons, and ECC/UHPC Columns*. Accelerated Bridge Construction University Transportation Center, Miami, FL.
- Motaref, S., M. S. Saiidi, and D. Sanders. 2011. *Seismic Response of Precast Bridge Columns with Energy Dissipating Joints*. Accelerated Bridge Construction University Transportation Center (ABC-UTC), Florida International University, Miami, FL. <http://utcdb.fiu.edu/researchprojectitem?id=76> with Part 1 at [http://utcdb.fiu.edu/final_report_task_1999%20\(Part%201\).pdf](http://utcdb.fiu.edu/final_report_task_1999%20(Part%201).pdf).
- Pang, J. B. K., K. P. Steuck, L. Cohagen, J. F. Stanton, and M. O. Eberhard. 2008. *Rapidly Constructible Large-Bar Precast Bridge-Bent Seismic Connection*. Washington State Transportation Center, University of Washington, Seattle, WA.
- Pantelides, C. P., M. J. Ameli, and L. D. Reaveley. 2017. *Evaluation of Grouted Splice Sleeve Connections for Precast Reinforced Concrete Bridge Piers*. Mountain-Plains Consortium, Upper Great Plains Transportation Institute, North Dakota State University, Fargo, ND.
- PCI. 2000. *Tolerance Manual for Precast and Prestressed Concrete Construction*. Precast/Prestressed Concrete Institute, Chicago, IL.
- PCI. 2007. Section 3.5 of *Architectural Precast Concrete Manual*. Precast/Prestressed Concrete Institute, Chicago, IL.
- PCI. 2014. *Precast and Prestressed Concrete*. Precast/Prestressed Concrete Institute, Chicago, IL.
- Restrepo, J. I., M. J. Tobolski, and E. E. Matsumoto. 2011. *NCHRP Report 681: Development of a Precast Bent Cap System for Seismic Regions*. National Cooperative Highway Research Program, Washington, DC.
- Shama, A. A., J. B. Mander, and A. J. Aref. 2002. Seismic Performance and Retrofit of Steel Pile to Concrete Cap Connections. *Structural Journal*, Vol. 99, No. 1, pp. 51–61.
- Sritharan, S. and Z. Cheng. 2016. Accelerated Bridge Construction (ABC) – Substructure: Grout. <http://sri.cce.iastate.edu/ABC-Guidelines/Grout%20New.html>.
- Tazarv, M. and M. S. Saiidi. 2015. *Design and Construction of Bridge Columns Incorporating Mechanical Bar Splices in Plastic Hinge Zones*. Accelerated Bridge Construction University Transportation Center (ABC-UTC), Florida International University, Miami, FL. <https://abc-utc.fiu.edu/wp-content/uploads/sites/52/2016/02/CCEER-15-07-TazarvSaiidi-1-20-2016.pdf>.
- UDOT. 2017. *Structures Design and Detailing Manual*. Utah Department of Transportation, Salt Lake City, UT.
- Wipf, T. J., F. W. Klaiber, and S. Hockerman. 2009. *Precast Concrete Elements for Accelerated Bridge Construction, Volume 1-1. Laboratory Testing of Precast Substructure Components: Boone County Bridge*. Bridge Engineering Center, Iowa State University, Ames, IA.
- Xiao, Y., H. Wu, T. T. Yaprak, G. R. Martin, and J. B. Mander. 2006. Experimental Studies on Seismic Behavior of Steel Pile-to-Pile-Cap Connections. *Journal of Bridge Engineering*, Vol. 11, No. 2, pp. 151–159.

APPENDIX. TEST UNIT DRAWINGS

NOTE:


1. CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR IS TO BE 1" UNLESS OTHERWISE SHOWN.
2. ALL DIMENSIONS ARE OUT TO OUT.
3. × LOCATION OF STIRRUP.
4. THICKNESS OF PIPES AND PIPE REDUCERS IS TO BE 16 GAUGES.





IOWA DOT ABC SUBSTRUCTURE CONNECTION


TEST UNIT (PILE CAP)

DATE
06/01/2016












SIDE 1




SIDE 2



SHEAR KEY DETAIL



SEGMENT 1



R/F DETAIL

GENERAL NOTES:

1. CONCRETE STRENGTH, $f'_c = 8.0$ KSI.
2. CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR IS TO BE 1.5".
3. VERTICAL DUCT I.D. = 4", AND HORIZONTAL DUCT I.D. = 3".
4. A $\frac{1}{4}$ " THICK A36 STEEL PLATE IS REQUIRED TO EMBEDDED UNDERNEATH SEGMENT 1.

IOWA DOT ABC SUBSTRUCTURE CONNECTION

VERTICAL LOADING TOWER

DATE
07/15/2016

3.1

**THE INSTITUTE FOR TRANSPORTATION IS THE FOCAL POINT FOR TRANSPORTATION
AT IOWA STATE UNIVERSITY.**

InTrans centers and programs perform transportation research and provide technology transfer services for government agencies and private companies;

InTrans contributes to Iowa State University and the College of Engineering's educational programs for transportation students and provides K–12 outreach; and

InTrans conducts local, regional, and national transportation services and continuing education programs.



**IOWA STATE
UNIVERSITY**

Visit InTrans.iastate.edu for color pdfs of this and other research reports.