



# **Modulus and Dynamic Cone Penetrometer Data Collection for Full-Depth Reclamation Projects**

**Derek Tompkins, Principal Investigator**  
American Engineering Testing, Inc.

**February 2021**

Research Project  
Final Report 2021-05

To request this document in an alternative format, such as braille or large print, call [651-366-4718](tel:651-366-4718) or [1-800-657-3774](tel:1-800-657-3774) (Greater Minnesota) or email your request to [ADArequest.dot@state.mn.us](mailto:ADArequest.dot@state.mn.us). Please request at least one week in advance.

## Technical Report Documentation Page

1. Report No. <b>MN 2021-05</b>	2.	3. Recipients Accession No.	
4. Title and Subtitle <b>Modulus and Dynamic Cone Penetrometer Data Collection for Full-Depth Reclamation Projects</b>		5. Report Date <b>February 2021</b>	6.
7. Author(s) <b>Derek Tompkins</b>		8. Performing Organization Report No.	
9. Performing Organization Name and Address <b>American Engineering Testing, Inc. 550 Cleveland Ave N Saint Paul, MN 55114</b>		10. Project/Task/Work Unit No.	
		11. Contract (C) or Grant (G) No. <b>(c) 1031051</b>	
12. Sponsoring Organization Name and Address <b>Minnesota Department of Transportation Office of Research &amp; Innovation 395 John Ireland Boulevard, MS 330 St. Paul, Minnesota 55155-1899</b>		13. Type of Report and Period Covered <b>Final Report</b>	
		14. Sponsoring Agency Code	
15. Supplementary Notes <a href="http://mndot.gov/research/reports/2021/202105.pdf">http://mndot.gov/research/reports/2021/202105.pdf</a>			
16. Abstract (Limit: 250 words) <p>This field study involved falling-weight deflectometer (FWD) and dynamic cone penetrometer (DCP) testing on Minnesota roads using full-depth reclamation (FDR) base layers. The study also included basic backcalculation analysis of collected FWD data using TONN2010. This initial analysis found that FDR layers had an average stiffness, or elastic modulus, of 53.8 ksi and an average DCP Index of 2.81 mm/blow. The report presented these values alongside average DCP indices by location with limited analysis (more advanced analysis being beyond this field study). A more research-oriented review of the FWD and DCP data collected will be required to further verify layer thicknesses and compositions. The results of that review will enable MnDOT to better evaluate the use of DCP indices and the characterization of FDR-composed sublayers in MnPAVE-Flexible.</p>			
17. Document Analysis/Descriptors <b>Pavement design, asphalt based materials, full-depth reclamation, cone penetrometers, asphalt pavements</b>		18. Availability Statement <b>No restrictions. Document available from: National Technical Information Services, Alexandria, Virginia 22312</b>	
19. Security Class (this report) <b>Unclassified</b>	20. Security Class (this page) <b>Unclassified</b>	21. No. of Pages <b>127</b>	22. Price

# **MODULUS AND DYNAMIC CONE PENETROMETER DATA COLLECTION FOR FULL-DEPTH RECLAMATION PROJECTS**

## **FINAL REPORT**

*Prepared by:*

Derek Tompkins  
American Engineering Testing, Inc.  
550 Cleveland Ave N  
Saint Paul, MN 55114

**FEBRUARY 2021**

*Published by:*

Minnesota Department of Transportation  
Office of Research & Innovation  
395 John Ireland Boulevard, MS 330  
St. Paul, Minnesota 55155-1899

This report documents the results of research conducted by the authors and does not necessarily represent the views or policies of the Minnesota Department of Transportation or American Engineering Testing. This report does not contain a standard or specified technique.

The authors, the Minnesota Department of Transportation, and American Engineering Testing do not endorse products or manufacturers. Trade or manufacturers' names appear herein solely because they are considered essential to this report.

# TABLE OF CONTENTS

<b>CHAPTER 1: Introduction .....</b>	<b>1</b>
1.1 Background .....	1
1.2 Scope and objectives .....	1
1.3 Overview of report .....	2
<b>CHAPTER 2: Test Locations.....</b>	<b>3</b>
2.1 Test location resources and selection criteria .....	3
2.2 Selected test locations.....	3
<b>CHAPTER 3: Tests Performed .....</b>	<b>6</b>
3.1 Dynamic Cone Penetrometer and Base Sampling and Observations.....	6
3.2 Falling Weight Deflectometer .....	7
3.3 Laboratory Sieve Analysis and Chemical Extraction Tests of Base Samples .....	7
3.4 Field testing notes .....	7
<b>CHAPTER 4: Results.....</b>	<b>9</b>
4.1 Project testing files .....	9
4.1.1 DCP File Description .....	9
4.2 Test results in summary.....	9
<b>CHAPTER 5: Conclusions .....</b>	<b>15</b>
<b>REFERENCES .....</b>	<b>16</b>
<b>APPENDIX A: Test Location Maps</b>	
<b>APPENDIX B: DCP Reports by Test Site</b>	
<b>APPENDIX C: TONN2010 Analysis Sheets by Location</b>	
<b>APPENDIX D: Sieve Analysis and Chemical Extraction</b>	

## **LIST OF FIGURES**

Figure 1. Characterizing sublayers in MPF with average DCP index .....	2
Figure 2. Map of test locations by regional grouping.....	5
Figure 3. Sieve analysis of composite FDR base samples from each roadway .....	13
Figure 4. Gradation requirements of bases containing 25 percent or more recycled materials (MnDOT 3138, "Aggregate for Surface and Base Courses).....	14

## **LIST OF TABLES**

Table 1. Test location summary from MnDOT records (uses MnDOT internal data headers) .....	4
Table 2. Field test dates and termini .....	6
Table 3. DCP test data by location .....	12
Table 4. FWD analysis by location (with DCP information for comparison) .....	12
Table 5. Results of chemical extraction tests of base samples with FDR base gradation summary .....	13

## EXECUTIVE SUMMARY

The Minnesota Department of Transportation (MnDOT) Office of Materials and Road Research (OMRR) created and maintains the MnPAVE-Flexible (MPF) software for the design of asphalt pavements in Minnesota. MPF relies on sophisticated mechanistic-empirical (M-E) structural models and detailed design parameters to estimate the long-term performance of an asphalt pavement structure. As materials that are used for paving projects change over time, there exists a need to update MnDOT's characterization of these materials for the sake of MPF.

One class of materials that has become increasingly popular in the past few decades is reclaimed materials that result from full-depth reclamation (FDR) paving projects. These materials are composed of a blend of recycled asphalt pavement (i.e., the in-place pavement to be replaced with a new asphalt pavement) and in-place granular base materials (i.e., the base layer under the in-place pavements). Because the composition of reclaimed base materials can vary widely, the resulting field performance of these materials may vary.

To evaluate MPF's treatment of FDR sublayers and assess possible changes to MPF, MnDOT commissioned this field study to perform falling-weight deflectometer (FWD) and dynamic cone penetrometer (DCP) testing on locations using FDR base layers in Minnesota. Engineers in MnDOT OMRR selected field locations of interest. Field tests were performed during fall 2018 and summer 2019. All test data were organized by site and uploaded to the MnDOT Managed File Transfer (MFT) Server for review by MnDOT and possible incorporation into future research involving MPF.

In addition, the project performed basic backcalculation analysis of collected FWD data using TONN2010. This initial analysis found that FDR layers had an average stiffness, or elastic modulus, of 53.8 ksi and an average DCP Index of 2.81 mm/blow. This report presented these values alongside average DCP indices by location with limited analysis (more advanced analysis being beyond this field study).

A more research-oriented review of the FWD and DCP data collected is required to further verify layer thicknesses and compositions. The results of that review will enable MnDOT to better evaluate the use of DCP indices and the characterization of FDR-composed sublayers in MnPAVE-Flexible.

# CHAPTER 1: INTRODUCTION

## 1.1 BACKGROUND

The Minnesota Department of Transportation (MnDOT) Office of Materials and Road Research (OMRR) created and maintains the MnPAVE-Flexible (MPF) software for the design of asphalt pavements in Minnesota (MnDOT, 2019). MPF relies on sophisticated mechanistic-empirical (M-E) structural models and detailed design parameters to estimate the long-term performance of an asphalt pavement structure. As materials that are used for paving projects change over time, there exists a need to update MnDOT's characterization of these materials for the sake of MPF.

One class of materials that has become increasingly popular in the past few decades is reclaimed materials that result from full-depth reclamation (FDR) paving projects. These materials are composed of a blend of recycled asphalt pavement (i.e., the in-place pavement to be replaced with a new asphalt pavement) and in-place granular base materials (i.e., the base layer under the in-place pavements). Because the composition of reclaimed base materials can vary widely, the resulting field performance of these materials may vary.

To evaluate MPF's treatment of FDR sublayers and assess possible changes to MPF, MnDOT requires field data to consider *in-situ* behavior alongside MPF and its M-E models. One such area of study is evaluating the methods that MPF uses to characterize sublayer properties. These methods include the use of dynamic cone penetrometer (DCP) data (Figure 1), which is the focus of this experimental field study.

## 1.2 SCOPE AND OBJECTIVES

The main work objective was to provide MnDOT with a database of falling-weight deflectometer (FWD) and dynamic cone penetrometer (DCP) test data for as many FDR locations in Minnesota as feasible under project scheduling and resource limitations. This database was achieved according to the following items in the project work scope.

- Identify field projects involving FDR that can provide useful FWD and DCP data and/or field samples for OMRR laboratory moisture content/gradation tests
- Conduct field tests and collect field samples using a combination of FWD, DCP, and hand auguring
- Analyze data to determine backcalculated layer stiffnesses (i.e., elastic moduli) and average DCP penetration index values (in mm/blow) from different FDR projects across Minnesota
- Produce a report summarizing the project activities

The project team's understanding is that the ultimate objective of MnDOT OMRR – which lies beyond the scope of this project – is a review of MPF use of DCP to characterize FDR sublayers using the DCP and FWD data collected during this project.

### 1.3 OVERVIEW OF REPORT

This report provides general information on project locations, an overview of the tests performed, a summary of the test results, and observations on the study to assist MnDOT in future work. Appendices to the report include TONN2010 report sheets (from backcalculation analysis) and DCP report sheets by location and test site within each location. All electronic data (including raw FWD basins and scans of field DCP test forms) have been uploaded to MnDOT repositories for review and use in future studies.




Figure 1. Characterizing sublayers in MPF with average DCP index

## CHAPTER 2: TEST LOCATIONS

### 2.1 TEST LOCATION RESOURCES AND SELECTION CRITERIA

Resources available to the team included summaries of known FDR sections developed by MnDOT Grading and Base engineers. The project team used these summaries to explore MnDOT eDiggs Online for construction and design plans and verify the presence of an FDR base layer.

Initially, locations were prioritized by known information (i.e., sections with more comprehensive records were prioritized over those whose records were incomplete). Later reviews and discussions with MnDOT OMRR engineers addressed the need for extensive traffic control on more heavily trafficked roads. To improve field safety conditions for testing, reduce the amount of traffic control required, and narrow the pool of candidate sites, the project team focused on FDR locations with average annual daily traffic (AADT) volumes of less than 1500 vehicles.

Field sites were further evaluated based on proximity to (A) other potential test sites to optimize collected data relative to project resources and scheduling and (B) the Metro district, which is where the project team's field technicians and equipment are located. On the latter point, there was an opportunity to use technicians and equipment from other satellite offices in Minnesota, North Dakota, and South Dakota perform DCP tests on the project team's behalf to limit mobilization costs. Discussions with MnDOT OMRR determined that the best course of action was to use a few experienced technicians for all tests (i.e., those based out of Saint Paul) to ensure consistency and quality in all collected data.

### 2.2 SELECTED TEST LOCATIONS

After reviewing candidate field locations with MnDOT OMRR engineers, the following final locations (Figure 2), distributed among 4 groups by proximity for test mobilization planning, were selected.

- *North Central.* TH-11 and US-71
- *North West.* TH-1, TH-9, and TH-32
- *Central.* TH-55, TH-238, and US-59
- *South West.* TH-62, TH-83, and TH-109

Table 1 summarizes the project team's understanding of FDR section location details for the purposes of the testing protocol and test data summary conducted during this project. A 3.0-mile stretch of each FDR location was selected for DCP and FWD testing. As noted above, properties reported in Table 1 were determined using publicly available MnDOT records. Test section maps are shown in Appendix A.

**Table 1. Test location summary from MnDOT records (uses MnDOT internal data headers)**

aux	d	SP	rehab	age	aadt	pcnt_truck	#1 Thickness	#1 Material	#2 Thickness	#2 Material	Note #1
MN1	U	4502-05	28	8	1240	3.8	5	HMA	--	--	9" reclaim
MN1	U	6901-07	28	8	1240	3.8	4	HMA	4.5	Agg. Base	10" reclaim
MN9	U	5408-11	28	4	771	13.2	5	HMA	14	Agg. Base	9" reclaim
MN9	U	6010-12	28	6	662	13.9	4.5	HMA	6	Agg. Base	10" reclaim
MN11	U	3604-26	28	7	580	27.1	6	HMA	14.5	Agg. Base	12" reclaim
MN32	U	6006-13	28	8	1400	12.6	4.5	HMA	--	--	8" reclaim
MN32	U	6006-13	28	8	1400	12.6	4.5	HMA	4	Agg. Base	8" reclaim
MN55	U	6107-03	28	7	670	15.7	5	HMA	6	Agg. Base	5" reclaim
MN62	U	2507-07	28	3	876	14.4	4	HMA	14.75	Agg. Base	10" reclaim
MN83	U	8107-10	28	6	703	13.1	5	HMA	2.5	Agg. Base	12" reclaim & 3.5" soil-cement base
MN83	U	0711-16	28	6	688	13.2	12.5	HMA	2.5	Agg. Base	12" reclaim & 3.5" soil-cement base
MN109	U	2212-11	28	5	814	12.8	3	HMA	18	Agg. Base	<No note on reclaimed depth>
MN238	U	0	28	0	1047	3.9	1.5	HMA	2	Agg. Base	<No note on reclaimed depth, assumed 4" over 8" as 1.5 is too low>
US59	U	6010-08	28	1	1055	22.7	4.5	HMA	3.25	Agg. Base	10" reclaim
US71	U	3611-15	28	6	670	9.6	5	HMA	9.75	Agg. Base	10" reclaim
US71	U	3611-23	28	12	580	9.8	4.5	HMA	1.5	Agg. Base	8" reclaim




Figure 2. Map of test locations by regional grouping

## CHAPTER 3: TESTS PERFORMED

The project team performed tests described in the following sections. Appropriate test standards and resources are cited to provide additional detail. The tests were performed by location as indicated in Table 2. Inclement weather in Fall 2018 and late May/June 2019 delayed the original field testing schedule, however tests of all sections were completed by Fall 2019 without issue. Appendix A illustrates each test section – Table 2 indicates GPS coordinates for termini.

**Table 2. Field test dates and termini**

Section	Test Date	From		To	
		Lat	Long	Lat	Long
TH001	6/19/2019	48.1952285	-96.7166718	48.1953401	-96.6522469
TH009	6/19/2019	47.7446186	-96.5673442	47.7016399	-96.5678367
TH011	6/20/2019	48.6523774	-94.2500457	48.6485189	-94.1870590
TH032	6/19/2019	47.3693815	-96.2805731	47.4133168	-96.2812268
TH055	10/11/2018	45.7371620	-95.5820284	45.7568934	-95.6386508
TH059	10/12/2018	45.2842571	-95.9120541	45.3333109	-95.9116142
TH062	10/12/2018	43.8623662	-95.5437658	43.8624588	-95.4779318
TH071	6/20/2019	48.0949670	-93.9369857	48.1264640	-93.8900040
TH083	10/13/2018	43.9354219	-93.7023348	43.8904114	-93.6975968
TH109	10/13/2018	43.7605201	-93.9876216	43.7603651	-94.0590845
TH238	10/11/2018	45.7290215	-94.5899511	45.6751551	-94.6036357

### 3.1 DYNAMIC CONE PENETROMETER AND BASE SAMPLING AND OBSERVATIONS

Field DCP testing followed ASTM D6951, “Standard Test Method for Use of the Dynamic Cone Penetrometer in Shallow Pavement Applications.” DCP tests were performed at five (5) regularly spaced sites within each 3.0-mile FDR location. Field technicians performed the test using a Kessler Soils Engineering (KSE) Dynamic Cone Penetrometer Model K-100A with disposable metal cone tips. The DCP procedure included the following basic steps.

- The asphalt pavement was cored to provide access for the DCP test at the top of the base layer.
- Note: Pavement cores were reserved and later photographed in the lab to verify pavement thickness for later analysis and for MnDOT OMRR records.
- DCP testing was performed to a depth of 18 inches minimum, the depth being measured from the top of the base layer (i.e., the bottom of the pavement core hole). This practice was performed – regardless of the base depth indicated in plans or other MnDOT records – to ensure there is useful DCP data to characterize all base layers tested, including those whose thicknesses may later be found to be inaccurate in MnDOT records.

- DCP testing of other sublayers was not performed as subbase/subgrade characterization was not in the original work scope.
- Disposable metal cone tips were recovered (if possible) or left in-situ.

After DCP tests were complete at a given test site, technicians performed the following steps before proceeding to the next site or location.

- Sampled base materials were stored for possible laboratory tests (e.g. sieve analysis for gradation, chemical extraction or ignition for approximate RAP content).
- Approximately 3-5 pounds of base materials were sampled per site.
- Core holes were backfilled with MnDOT Class 5 aggregate (to replace base materials) and asphalt patching material (to replace the pavement core). As some districts had requested a special patch material (UPM Bituminous Cold Mix #4), this patching material was used at all test sites/locations.

### **3.2 FALLING WEIGHT DEFLECTOMETER**

All FWD tests were performed using either a Dynatest Model 8001 or 8002 FWD test trailer, which includes nine deflectometers. The Dynatest FWD Test System used for all tests performed in this field study meets ASTM D4694, “Standard Test Method for Deflections with a Falling-Weight-Type Impulse Load Device.” Technicians performed FWD tests at 0.1-mile intervals within each 3.0-mile test location – that is, a minimum of 30 regularly spaced drops were performed at each location.

### **3.3 LABORATORY SIEVE ANALYSIS AND CHEMICAL EXTRACTION TESTS OF BASE SAMPLES**

Samples of base materials from each road section were blended to form a representative composite base sample for the roadway. Sample collection and volumes are discussed in Section 3.1.2. The composite samples by roadway were tested in the laboratory according to the following procedures from the *MnDOT Materials Laboratory Manual No. 5-695* (MnDOT, 2014).

- MnDOT 1202/1203, “Coarse/Fine Aggregate Sieve Analysis” (MnDOT-modified AASHTO T 27)
- MnDOT 1852, “Quantitative Extraction of Bituminous Mixtures (Centrifuge)” (MnDOT-modified AASHTO T 164, Method A)

The chemical extraction testing made all reasonable efforts to ensure that the level of fines present in the extraction specimen reflected those of the larger composite sample.

### **3.4 FIELD TESTING NOTES**

As the project team regularly conducts pavement field testing, the FWD and DCP tests were largely routine. The primary observation from field testing was the difficulty technicians encountered when attempting to distinguish the base layer from either the subbase or subgrade layer visually (i.e., inspection of core hole) or mechanically (through feedback from DCP testing). For this reason, the DCP

electronic reports and brief TONN2010 analysis that was performed relied on plan thicknesses from MnDOT records.

DCP field test reports included some observations of conditions that temporarily complicated testing. While none of the observations have significant bearing on the final results, they are recorded here for completeness.

- Particles of RAP larger than approximately 1.5 inches (as approximated by technicians) were encountered at sites within some sections (e.g. TH-059, Site 3). These large particles occasionally complicated DCP testing. To proceed with the DCP test, the technician had to remove the oversized aggregate in the path of the cone, then resume the test. Special notes were made in field test files to indicate the complication, however field notes may not be comprehensive.
- The top of inch base was disturbed by coring operations in a few instances (e.g. TH-083, Site 3).
- Geogrid was encountered in a few instances (e.g. TH-011).
- Based on DCP penetration and observations in the core hole, field technicians made a note of layers being apparently separated into a finer upper lift and coarser lower lift in a few instances (e.g. TH-001, Site 3).

No notes on difficulties or special conditions were made during FWD testing.

# CHAPTER 4: RESULTS

## 4.1 PROJECT TESTING FILES

All project files have been uploaded to the MnDOT MFT Server for OMRR use. These files include the following items.

- Scans of DCP field test forms (completed by hand)
- Core and core hole photos from field DCP testing
- Electronic DCP report sheets (entered from field forms)
- FWD raw data
- TONN2010 analysis files of FWD data

Backcalculated results and electronic DCP summaries are included as appendices to this report. Other files, including raw data FWD files, are excluded given their length and the fact that they are immediately available to MnDOT through the MFT Server.

### 4.1.1 DCP File Description

The DCP reports produced include the original completed field test forms and the formatted electronic files. For MnDOT's convenience and to avoid confusion about which DCP data applies to which location through the sublayer cross-section, the electronic files limit DCP results to those for the thickness indicated in MnDOT records. The scanned field notes can be consulted should MnDOT OMRR learn that plan thicknesses are inaccurate – these field notes contain DCP blow counts and penetration depths for the full test to a minimum depth of 18 inches.

## 4.2 TEST RESULTS IN SUMMARY

Given that the analysis performed was very limited in scope, that analysis is reported within this subsection, rather than in a conventional chapter dedicated to analysis and/or discussion. All test results are provided in full in the appendices to this report.

- Average DCP results by site and location are reported in Table 3. DCP results by test site are provided in full in Appendix B.
- FWD analysis relating directly to base modulus is summarized in Table 4. Full backcalculated results (including moduli for other layers) by location are provided in Appendix C.
- Results of sieve analysis and chemical extraction tests of base samples are summarized in Table 5 and provided in full in Appendix D.

Backcalculation analysis assumptions about the pavement cross-section were based on MnDOT records. Some adjustment to layer thicknesses were made based on collected cores and field observations. These adjustments are noted in Table 4, which also reports the backcalculated stiffness (with basic statistical analysis) for the base layer alongside the average DCP index for the project team's understanding of the

corresponding base layer thickness. Also included in Table 4 – for discussion only and not for research purposes – are columns that convert the average DCP index to potentially relevant parameters

- An estimated laboratory resilient modulus (MR) using  $MR = 78.05 \cdot DPI^{-0.6645}$ , which is a relationship established by Chen et al (2005) where DPI is measured in mm per blow and MR is measured in ksi.
- The estimated pavement design MR of  $MR = 96.7 \cdot DPI^{-0.717}$  for the AASHTO M-E procedure, based on expressions for CBR (given DPI) and MR (given CBR) in the NCHRP 1-37A final report, where DPI and MR are in mm per blow and ksi, respectively (ERES 2004).

Overall, the average backcalculated stiffnesses for the FDR base layers is 53.8 ksi, which is slightly higher than the value a pavement engineer would expect (i.e., 25-45 ksi) for a given base layer in the State of Minnesota. However, note that the data is skewed by a few sections – the median base modulus for all tested sections is 47.1 ksi, which is closer to expectations but still slightly higher than the expectations described above.

The observed DCP index for FDR base layers was 2.81 mm/blow on average. The fitness of the average DCP indices (in terms of characterizing base properties) is otherwise difficult to gauge given the inherent challenge of DCP interpretation. A first-pass inspection of Table 4 yields a few interesting observations.

- DPI is generally less uniform across all observations by location than the backcalculated base stiffness – that is, the coefficient of variation (the ratio of the standard deviation to the mean, or COV) for DPI by location is 0.44, which is higher than the COV for FWD data by location (0.33).
- One indicator that certain locations may contain data sets with larger variation can be observed by inspection. The FWD data for TH-055 is a clear outlier in terms of variability – its COV is 0.59, nearly twice the average COV for FWD observations. Likewise, the DCP data for TH-083 and TH-001 may be worth additional review, as their COVs were 0.68 and 0.59 respectively.

This first-impression analysis should, of course, be reviewed and replaced (in a research sense) with more in-depth analysis by MnDOT OMRR. There are many MnDOT resources to advise future efforts on how best to account for DCP indices and base stiffness in MPF. Those resources include, but are not limited to Burnham (1997), which established expected DPI limits for paving materials in Minnesota; Dai and Kremer (2005), which elaborated on base characterization using DCP; and Ghasemi et al (2018), which characterized stabilized FDR bases using DCP testing of Minnesota roads. Please note that Ghasemi et al (2018) did not include FWD testing.

Finally, the results of sieve analysis indicate that the particle distribution of the sampled bases from each location is similar. When compared to the current specified gradation for a MnDOT Class 6 base containing 25 percent or more recycled aggregates, as shown in Figure 3, the sampled bases were generally finer than the levels required in MnDOT Table 3138-4, which is reproduced in Figure 4. Some differences between the tested FDR bases and MnDOT recommendations for Class 6 bases containing recycled materials are as follows.

- 21.7 percent of tested FDR base aggregate (on average) was retained on the No. 4 sieve – this is below the MnDOT minimum requirement of 30 percent from MnDOT Table 3138-4
- 33.9 percent of tested FDR base aggregate (on average) was retained on the No. 10 sieve – this is below the MnDOT minimum requirement of 45 percent from MnDOT Table 3138-4
- 7.5 percent of tested FDR bases passed the No. 200 sieve, which is over the required maximum of 7.0 percent in MnDOT Table 3138-4.

These observations regard aged materials and not the base materials immediately after reclamation. While the gradation of the base material may change (become finer) over time, the asphalt content of the RAP in the base material should not. Reported asphalt contents (along with summary sieve analysis) for each roadway are reported in Table 5. On average the samples contained 1.7 percent asphalt binder.

Interpretation of the asphalt binder content – in terms of judging RAP content in the reclaimed blend – varies by roadway and mix design for the original asphalt concrete pavement. A very broad rule to judge extraction results for reclaimed materials is that levels of roughly 2.5 percent asphalt binder content in a blend corresponds to roughly 50 percent RAP content in the blend. The rationale for this rule is based on general expectations of hot-mix asphalt to contain roughly 5.0 percent asphalt binder by weight.

Using the general rule described above, the tested road sections contained roughly 35 percent RAP on average. Expectations for RAP content in FDR base materials is anywhere between 30 and 70 percent (based on construction plan review and general experience on Minnesota road design and construction). The reliability of the RAP content estimate from extracted binder content is arguable. As noted in Section 3.1.3, the loss of fines in the extraction specimen may result in underestimation of asphalt content. While the tests were performed in a controlled environment by experienced personnel, fine loss (or rather, a specimen whose gradation may not represent that of the source material) is unavoidable.

Finally, the chemical extraction results were performed to supplement MnDOT's understanding of these road sections – that is, these results are for information only. They do not form a valid basis to infer properties of the reclaimed blend. Additional sampling, testing, and consulting of MnDOT District construction records should be performed to better gauge the amount of RAP present in these FDR bases, particularly as regards associating structural performance with a level of RAP or tested asphalt content.

**Table 3. DCP test data by location**

ID	Locn	Avg DCI (mm/blow)
01-1	TH 01	2.89
01-2	TH 01	1.88
01-3	TH 01	2.06
01-4	TH 01	2.01
01-5	TH 01	2.86
09-1	TH 09	3.08
09-2	TH 09	1.63
09-3	TH 09	2.00
09-4	TH 09	2.25
09-5	TH 09	1.42
11-1	TH 11	1.95
11-2	TH 11	2.06
11-3	TH 11	2.27
11-4	TH 11	2.21
11-5	TH 11	2.10
32-1	TH 32	2.58
32-2	TH 32	2.29
32-3	TH 32	1.53
32-4	TH 32	2.35
32-5	TH 32	2.40

ID	Locn	Avg DCI (mm/blow)
55-1	TH 55	2.95
55-2	TH 55	4.30
55-3	TH 55	3.16
55-4	TH 55	4.67
55-5	TH 55	2.81
59-1	TH 59	4.06
59-2	TH 59	2.48
59-3	TH 59	3.04
59-4	TH 59	4.21
59-5	TH 59	3.27
62-1	TH 62	2.66
62-2	TH 62	3.19
62-3	TH 62	2.32
62-4	TH 62	2.00
62-5	TH 62	2.84
71-1	TH 71	1.78
71-2	TH 71	2.51
71-3	TH 71	3.33
71-4	TH 71	2.20
71-5	TH 71	2.47


ID	Locn	Avg DCI (mm/blow)
83-1	TH 83	3.40
83-2	TH 83	3.80
83-3	TH 83	5.00
83-4	TH 83	3.51
83-5	TH 83	3.14
109-1	TH 109	3.10
109-2	TH 109	1.33
109-3	TH 109	3.10
109-4	TH 109	7.50
109-5	TH 109	1.92
238-1	TH 238	2.73
238-2	TH 238	3.56
238-3	TH 238	3.45
238-4	TH 238	2.75
238-5	TH 238	2.43

**Table 4. FWD analysis by location (with DCP information for comparison)**

Section	Layer Thickness		GE [in]		Base Elastic Modulus [ksi]		DPI [mm/blow]		Interpreted MR [ksi] from DPI	
	AC	Base	Avg	SD	Avg	SD	Avg	SD	Lab (Chen)	Design (AASHTO)
TH001	5.0	9.0	25.3	2.0	61.7	18.9	2.3	1.36	44.9	53.2
TH009	4.5	10.0	31.6	3.3	64.2	17.4	2.1	1.02	47.7	56.8
TH011	6.0	12.0	29.5	2.8	32.9	8.1	2.1	0.87	47.7	56.8
TH032	4.5	8.0	19.5	2.3	47.1	11.5	2.2	0.90	46.2	54.9
TH055	5.0	5.0	19.1	2.7	109.7	35.8	3.6	1.33	33.3	38.6
TH059	7.0	10.0	22.3	2.2	61.2	33.0	3.4	1.06	34.6	40.2
TH062	4.0	10.0	17.0	2.0	42.1	12.9	2.6	0.92	41.4	48.7
TH071	4.5	8.0	22.6	2.9	34.5	8.7	2.5	0.79	42.5	50.1
TH083	5.0	15.5	21.8	1.7	34.1	13.2	3.4	2.31	34.6	40.2
TH109	5.0	18.0	19.2	2.2	32.5	10.7	3.8	1.87	32.1	37.1
TH238	4.0	8.0	17.3	2.4	72.1	27.4	3.0	1.36	37.6	44.0

**Table 5. Results of chemical extraction tests of base samples with FDR base gradation summary**

	TH001	TH009	TH011	TH032	TH055	TH059	TH062	TH071	TH083	TH109	TH238
Retained at $\frac{3}{4}''$ (%)	4.1	0.0	3.2	1.0	0.0	5.7	1.0	0.0	0.0	1.4	0.7
Retained at #4 (%)	21.2	18.9	21.3	22.2	17.1	28.1	15.9	17.7	28.6	23.9	24.3
Passing #200 (%)	6.3	6.0	9.1	6.2	8.1	6.9	7.4	7.1	10.7	8.2	6.5
Asphalt Content (%)	0.9	1.4	2.8	1.5	2.8	0.5	1.7	1.7	0.9	1.7	3.2



**Figure 3. Sieve analysis of composite FDR base samples from each roadway**

<b>Table 3138-4</b> <b>Base and Surfacing Aggregate</b> (containing 25% or more recycled aggregates & 75% or less recycled concrete) Total Percent Passing *						
Sieve Size	Class 1 (Surfacing £)	Class 3 (Subbase)	Class 4 (Subbase)	Class 5 (Base)	Class 5Q (Base)	Class 6 (Base)
2 in	—	100	100	—	100	—
1½ in	—	—	—	100	—	100
1 in	—	—	—		65 - 95	
¾ in	100	—	—	70 - 100	45 - 85	70 - 100
⅜ in	65 - 95	—	—	45 - 90	35 - 70	45 - 85
No. 4	40 - 85	35 - 100	35 - 100	35 - 80	15 - 45	35 - 70
No. 10	25 - 70	20 - 100	20 - 100	20 - 65	10 - 30	20 - 55
No. 40	10 - 45 † 5 - 45	5 - 50	5 - 35	10 - 35	5 - 25	10 - 30
No. 200	5.0 - 15.0 + 0 - 15.0	0 - 10.0	0 - 10.0	0 - 10.0	0 - 10.0	0 - 7.0

\* Add letters in parentheses for each aggregate blend designating the type of recycled products included in the mixture.  
(B) = Bituminous, (C) = Concrete, (G) = Glass  
(BC) = Bituminous and Concrete, (BG) = Bituminous and Glass  
(CG) = Concrete and Glass, (BCG) = Bituminous, Concrete, and Glass  
† Note: For Class 1, if the bitumen content is ≥ 1.5%, the gradation requirement is modified to 5 - 45% for the #40 sieve and 0 - 15.0% for the #200 sieve.  
£ Recycled concrete is only allowed for shoulders

**Figure 4. Gradation requirements of bases containing 25 percent or more recycled materials (MnDOT 3138,  
“Aggregate for Surface and Base Courses”)**

## CHAPTER 5: CONCLUSIONS

Tests of all FDR locations were successful. All project data were successfully uploaded to the MnDOT MFT Server.


The project team organized collected test data to minimize complications when future studies access the results of this field study. In addition, limited analysis was performed on collected FWD data to provide MnDOT OMRR with a first impression of backcalculated base stiffness relative to DCP indices by location.

Overall, the assembled data provides MnDOT with the ability to assess future research involving (A) the use of DCP by MPF for FDR (or other) sublayers, (B) the characterization and performance of FDR sublayers as modeled by MPF, and/or (C) assumed values of stiffness of FDR base layers for other Minnesota pavement design procedures.


## REFERENCES

- ASTM Standard D4694. (2015). Standard Test Method for Deflections with a Falling-Weight-Type Impulse Load Device. ASTM International, West Conshohocken, PA
- ASTM Standard D6951 (2018). Standard Test Method for Use of the Dynamic Cone Penetrometer in Shallow Pavement Applications. ASTM International, West Conshohocken, PA
- Burnham, T. (1997). *Application of the Dynamic Cone Penetrometer to Minnesota Department of Transportation Pavement Assessment Procedures* (MnDOT Report 1997-19). Minnesota Department of Transportation, Saint Paul, MN.
- Burnham, T., & D. Johnson (1993). *In-Situ Foundation Characterization using the DCP* (MnDOT Report 1993-05). Minnesota Department of Transportation, Saint Paul, MN.
- Chen, D., D. Lin, P. Liau, & J. Bilyeu (2005). A Correlation Between Dynamic Cone Penetrometer Values and Pavement Layer Moduli. *Geotechnical Testing Journal*, 28(1), 42–49
- Dai, S., & C. Kremer (2005). *Improvement and Validation of Mn/DOT DCP Specifications for Aggregate Base Materials and Select Granular* (MnDOT Report 2005-32). Minnesota Department of Transportation, Saint Paul, MN.
- ERES Consultants. (2004). *Guide for Mechanistic Empirical Design of New and Rehabilitated Pavement Structures* (NCHRP 1-37A Final Report). National Cooperative Highway Research Program, Transportation Research Board, National Research Council, Washington, DC.
- Ghasemi, P., J. Yu, P. Ledtji, R. C. Williams, & C. Jahren (2018). *Field Investigation of Stabilized Full-Depth Reclamation (SFDR)* (MnDOT Report 2018-33). Minnesota Department of Transportation, Saint Paul, MN.
- Minnesota Department of Transportation. (2014). *MnDOT Materials Laboratory Manual No. 5-695*. Minnesota Department of Transportation, Saint Paul, MN. Retrieved from <https://www.dot.state.mn.us/materials/labmanual.html>
- Minnesota Department of Transportation. (2018). *Standard Specifications for Construction*. Minnesota Department of Transportation, Saint Paul, MN. Retrieved from <https://www.dot.state.mn.us/pre-letting/spec/>
- Minnesota Department of Transportation. (2019). MnPAVE Flexible 6.405 software. Minnesota Department of Transportation, Saint Paul, MN. Retrieved from <https://www.dot.state.mn.us/app/mnpave/>

## **APPENDIX A: TEST LOCATION MAPS**



A-1



US 71

A-2


A-2



TH 1




TH 9




TH 32

A-5  
A-5



TH 55 (AREA IN RED ONLY)


A-7







US 59

A-8  
A-8






TH 62



TH 109



A-12

TH 83

A-12

## **APPENDIX B: DCP REPORTS BY TEST SITE**



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 01
Test No.	01-1
Date Tested:	7/23/2019

Tested by:	RS
Test Location:	48.195195, -96.708092
Hammer Weight:	17.6 lbs
Weather:	Sunny 70

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.9 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


<b>Client:</b>	Office of Materials and Road Research	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	MnDOT Contract No. 1031051 TH 01 East 1.0 mile #2		

## General Information

Road:	TH 01
Test No.	01-2
Date Tested:	7/23/2019

Tested by:	RS
Test Location:	48.1952022, -96.697347
Hammer Weight:	17.6 lbs
Weather:	Sunny 70

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 1.9 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051  
TH 01 East 1.5 mile #3

This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.


---

## General Information

Road:	TH 01
Test No.	01-3
Date Tested:	7/23/2019

Tested by:	RS
Test Location:	48.1952769, -96.686607
Hammer Weight:	17.6 lbs
Weather:	Sunny 70

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.1 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


<b>Client:</b>	Office of Materials and Road Research	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	MnDOT Contract No. 1031051 TH 01 East 2.0 mile #4		

## General Information

Road:	TH 01
Test No.	01-4
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	48.1953592, -96.675864
Hammer Weight:	17.6 lbs
Weather:	Sunny 74

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.0 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


<b>Client:</b>	Office of Materials and Road Research	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	MnDOT Contract No. 1031051 TH 01 East mile 2.5 #5		

## General Information

Road:	TH 01
Test No.	01-5
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	48.1954438, -96.665135
Hammer Weight:	17.6 lbs
Weather:	Sunny 70

### **Dynamic Cone Penetrometer Testing (ASTM: D6951)**



Average DCP Index 2.9 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b> MNDOT	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b> 27-20000 TH 01 East		<hr/>
	Date of issue:	
	Reviewed By:	

## **General Information**

Road:	TH 01
Test No.	
Date Tested:	7/23/2019

Tested by:	RS
Test Location:	See below
Hammer Weight:	17.6 lbs
Weather:	Sunny 70

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 09
Test No.	09-1
Date Tested:	7/23/2019

Tested by:	RS
Test Location:	47.7389876, -96.568090
Hammer Weight:	17.6 lbs
Weather:	Sunny, 79 F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	80			
2	94	14	0.6	
3	110	16	1.2	5.3
6	132	22	2.0	3.7
3	140	8	2.4	2.7
3	145	5	2.6	1.7
3	150	5	2.8	1.7
3	155	5	3.0	1.7
3	160	5	3.1	1.7
3	165	5	3.3	1.7
3	171	6	3.6	2.0
3	178	7	3.9	2.3
3	185	7	4.1	2.3
3	195	10	4.5	3.3
3	205	10	4.9	3.3
3	215	10	5.3	3.3
3	227	12	5.8	4.0
3	245	18	6.5	6.0
3	262	17	7.2	5.7



Average DCP Index 3.1 mm/blow

## Comments



## Material Test Report

Client: Office of Materials and Road Research      CC:  
Project: MnDOT Contract No. 1031051

This document shall not  
be reproduced except in  
full, without written  
approval from American  
Engineering Testing,  
Inc.


### General Information

Road:	TH 09
Test No.	09-2
Date Tested:	7/23/2019

Tested by:	RS
Test Location:	47.7318009, -96.568112
Hammer Weight:	17.6 lbs
Weather:	Sunny, 79 F

### Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	65			
2	80	15	0.6	
3	90	10	1.0	3.3
9	105	15	1.6	1.7
6	115	10	2.0	1.7
6	127	12	2.4	2.0
12	145	18	3.1	1.5
12	165	20	3.9	1.7
9	180	15	4.5	1.7
12	197	17	5.2	1.4
12	220	23	6.1	1.9
12	245	25	7.1	2.1
12	260	15	7.7	1.3
12	278	18	8.4	1.5
12	298	20	9.2	1.7
12	303	5	9.4	0.4
12	308	5	9.6	0.4
12	320	12	10.0	1.0
12	342	22	10.9	1.8
12	370	28	12.0	2.3



Average DCP Index 1.6 mm/blow

### Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 09
Test No.	09-3
Date Tested:	7/23/2019

Tested by:	RS
Test Location:	47.7246298, -96.568053
Hammer Weight:	17.6 lbs
Weather:	Sunny, 79 F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	70			
2	88	18	0.7	
3	90	2	0.8	0.7
3	95	5	1.0	1.7
6	110	15	1.6	2.5
6	122	12	2.0	2.0
6	132	10	2.4	1.7
9	148	16	3.1	1.8
9	165	17	3.7	1.9
9	180	15	4.3	1.7
9	200	20	5.1	2.2
9	215	15	5.7	1.7
9	235	20	6.5	2.2
9	255	20	7.3	2.2
9	275	20	8.1	2.2
9	295	20	8.9	2.2
9	305	10	9.3	1.1
9	325	20	10.0	2.2
9	350	25	11.0	2.8
9	380	30	12.2	3.3



Average DCP Index 2.0 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 09
Test No.	09-4
Date Tested:	7/23/2019

Tested by:	RS
Test Location:	47.7174385, -96.567982
Hammer Weight:	17.6 lbs
Weather:	Sunny, 79 F

Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.3 mm/blow

## Comments



## Material Test Report

**Client:** Office of Materials and Road Research      **CC:**

**Project:** MnDOT Contract No. 1031051

This document shall not  
be reproduced except in  
full, without written  
approval from American  
Engineering Testing,  
Inc.


### General Information

Road:	TH 09
Test No.	09-5
Date Tested:	7/23/2019

Tested by:	RS
Test Location:	47.7102685, -96.567924
Hammer Weight:	17.6 lbs
Weather:	Sunny, 79 F

### Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	70			
2	85	15	0.6	
3	95	10	1.0	3.3
6	110	15	1.6	2.5
6	125	15	2.2	2.5
9	140	15	2.8	1.7
9	152	12	3.2	1.3
9	165	13	3.7	1.4
9	178	13	4.3	1.4
9	192	14	4.8	1.6
9	204	12	5.3	1.3
9	215	11	5.7	1.2
9	224	9	6.1	1.0
9	235	11	6.5	1.2
9	245	10	6.9	1.1
9	260	15	7.5	1.7
9	272	12	8.0	1.3
9	276	4	8.1	0.4
9	285	9	8.5	1.0
9	295	10	8.9	1.1
12	304	9	9.2	0.8
12	310	6	9.4	0.5



Average DCP Index 1.4 mm/blow

### Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b>	MNDOT	<b>CC:</b>	
<b>Project:</b>	27-20000 TH 09 South		This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.  Date of issue: _____ Reviewed By: _____

## **General Information**

Road:	TH 09	Tested by:	RS
Date Stabilized:	09-1	Test Location:	See below
Date Tested:	7/23/2019	Hammer Weight:	17.6 lbs
Days after stabilization:	-406	Weather:	Sunny, 79 F

#### **Dynamic Cone Penetrometer Testing (ASTM: D6951)**

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 11
Test No.	11-1
Date Tested:	7/30/2019

Tested by:	RS
Test Location:	48.648454, -94.236720
Hammer Weight:	17.6 lbs
Weather:	Sunny, 79F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 1.9 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 11
Test No.	11-2
Date Tested:	7/30/2019

Tested by:	RS
Test Location:	48.646759, -94.225612
Hammer Weight:	17.6 lbs
Weather:	Sunny, 79F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.1 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 11
Test No.	11-3
Date Tested:	7/30/2019

Tested by:	RS
Test Location:	48.647400, -94.213781
Hammer Weight:	17.6 lbs
Weather:	Sunny, 79F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.3 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 11
Test No.	11-4
Date Tested:	7/30/2019

Tested by:	RS
Test Location:	48.648494, -94.203496
Hammer Weight:	17.6 lbs
Weather:	Sunny, 79F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.2 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 11
Test No.	11-5
Date Tested:	7/30/2019

Tested by:	RS
Test Location:	48.648846, -94.191014
Hammer Weight:	17.6 lbs
Weather:	Sunny, 79F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.1 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b>	Office of Materials and Road Research	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	MnDOT Contract No. 1031051		Date of issue: _____
			Reviewed By: _____

## **General Information**

Road:	TH 11	Tested by:	RS
Date Stabilized:	11-1	Test Location:	See below
Date Tested:	7/30/2019	Hammer Weight:	17.6 lbs
Days after stabilization:	-460	Weather:	Sunny, 79F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 32
Test No.	32-1
Date Tested:	7/22/2019

Tested by:	RS
Test Location:	47.3759881, -96.280737
Hammer Weight:	17.6 lbs
Weather:	Sunny, 80F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.6 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.

## General Information

Road:	TH 32
Test No.	32-2
Date Tested:	7/22/2019

Tested by:	RS
Test Location:	47.3831674, -96.281057
Hammer Weight:	17.6 lbs
Weather:	Sunny, 80F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.3 mm/blow

## Comments



## Material Test Report

**Client:** Office of Materials and Road Research      **CC:**

**Project:** MnDOT Contract No. 1031051

This document shall not  
be reproduced except in  
full, without written  
approval from American  
Engineering Testing,  
Inc.


### General Information

Road:	TH 32
Test No.	32-3
Date Tested:	7/22/2019

Tested by:	RS
Test Location:	47.390351, -96.281412
Hammer Weight:	17.6 lbs
Weather:	Sunny, 80F

### Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	70			
2	85	15	0.6	
3	95	10	1.0	3.3
9	122	27	2.0	3.0
15	162	40	3.6	2.7
9	180	18	4.3	2.0
9	195	15	4.9	1.7
18	217	22	5.8	1.2
6	222	5	6.0	0.8
9	235	13	6.5	1.4
12	250	15	7.1	1.3
9	265	15	7.7	1.7
15	280	15	8.3	1.0
9	292	12	8.7	1.3
15	308	16	9.4	1.1
12	325	17	10.0	1.4
12	335	10	10.4	0.8
15	350	15	11.0	1.0
12	360	10	11.4	0.8
12	385	25	12.4	2.1
12	390	5	12.6	0.4



Average DCP Index 1.5 mm/blow

### Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 32
Test No.	32-4
Date Tested:	7/22/2019

Tested by:	RS
Test Location:	47.3975329, -96.281761
Hammer Weight:	17.6 lbs
Weather:	Sunny, 80F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.4 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 32
Test No.	32-5
Date Tested:	7/22/2019

Tested by:	RS
Test Location:	47.4047202, -96.281548
Hammer Weight:	17.6 lbs
Weather:	Sunny, 80F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.4 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b>	MNDOT	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	27-20000 TH 32 North		Date of issue: _____ Reviewed By: _____

## General Information

Road:	TH 32	Tested by:	RS
Date Stabilized:	32-1	Test Location:	See below
Date Tested:	7/22/2019	Hammer Weight:	17.6 lbs
Days after stabilization:	#VALUE!	Weather:	Sunny, 80F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).



## Material Test Report

Client: Office of Materials and Road Research      CC:  
Project: MnDOT Contract No. 1031051

This document shall not  
be reproduced except in  
full, without written  
approval from American  
Engineering Testing,  
Inc.


### General Information

Road:	TH 55
Test No.	55-1
Date Tested:	7/22/2016

Tested by:	RS
Test Location:	45.7174036, -95.539210
Hammer Weight:	17.6 lbs
Weather:	Sunny, 83F

### Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	68			
2	95	27	1.1	
3	110	15	1.7	5.0
3	120	10	2.0	3.3
9	145	25	3.0	2.8
12	174	29	4.2	2.4
12	205	31	5.4	2.6
12	240	35	6.8	2.9
15	287	47	8.6	3.1
12	326	39	10.2	3.3
12	360	34	11.5	2.8
12	375	15	12.1	1.3
2				



Average DCP Index 2.9 mm/blow

### Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 55
Test No.	55-2
Date Tested:	7/18/2019

Tested by:	RS
Test Location:	45.7216562, -95.547534
Hammer Weight:	17.6 lbs
Weather:	Sunny, 83F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 4.3 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 55
Test No.	55-3
Date Tested:	7/18/2019

Tested by:	RS
Test Location:	45.7258976, -95.555850
Hammer Weight:	17.6 lbs
Weather:	Sunny, 83F

### **Dynamic Cone Penetrometer Testing (ASTM: D6951)**



Average DCP Index 3.2 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 55
Test No.	55-4
Date Tested:	7/18/2019

Tested by:	RS
Test Location:	45.7297974, -95.564482
Hammer Weight:	17.6 lbs
Weather:	Sunny, 83F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 4.7 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 55
Test No.	55-5
Date Tested:	7/18/2019

Tested by:	RS
Test Location:	45.7329562, -95.573741
Hammer Weight:	17.6 lbs
Weather:	Sunny, 83F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.8 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b>	MNDOT	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	27-20000 TH 55 North		Date of issue: _____ Reviewed By: _____

## **General Information**

Road:	55	Tested by:	RS
Date Stabilized:	55-1	Test Location:	See below
Date Tested:	7/18/2019	Hammer Weight:	17.6 lbs
Days after stabilization:	#VALUE!	Weather:	Sunny, 83F

#### **Dynamic Cone Penetrometer Testing (ASTM: D6951)**

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 59
Test No.	59-1
Date Tested:	7/22/2016

Tested by:	RS
Test Location:	45.2900244, -95.912035
Hammer Weight:	17.6 lbs
Weather:	Sunny, 92F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 4.1 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 59
Test No.	59-2
Date Tested:	7/22/2016

Tested by:	RS
Test Location:	45.2972384, -95.912013
Hammer Weight:	17.6 lbs
Weather:	Sunny, 92F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.5 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 59
Test No.	59-3
Date Tested:	7/19/2019

Tested by:	RS
Test Location:	45.304459, -95.911958
Hammer Weight:	17.6 lbs
Weather:	Sunny, 92F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 3.0 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 59
Test No.	59-4
Date Tested:	7/19/2019

Tested by:	RS
Test Location:	45.3116708, -95911911
Hammer Weight:	17.6 lbs
Weather:	Sunny, 92F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	67			
2	85	18	0.7	
3	100	15	1.3	5.0
3	115	15	1.9	5.0
3	130	15	2.5	5.0
3	140	10	2.9	3.3
3	152	12	3.3	4.0
6	175	23	4.3	3.8
6	200	25	5.2	4.2
6	220	20	6.0	3.3
6	245	25	7.0	4.2
6	270	25	8.0	4.2
6	300	30	9.2	5.0
6	330	30	10.4	5.0
6	347	17	11.0	2.8
6	372	25	12.0	4.2
6				



Average DCP Index 4.2 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 59
Test No.	59-5
Date Tested:	7/19/2019

Tested by:	RS
Test Location:	45.3188898, -95.911859
Hammer Weight:	17.6 lbs
Weather:	Sunny, 92F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	70			
2	95	25	1.0	
3	110	15	1.6	5.0
6	130	20	2.4	3.3
6	145	15	3.0	2.5
6	160	15	3.5	2.5
6	175	15	4.1	2.5
6	190	15	4.7	2.5
6	205	15	5.3	2.5
6	220	15	5.9	2.5
6	240	20	6.7	3.3
6	264	24	7.6	4.0
6	290	26	8.7	4.3
6	315	25	9.6	4.2
6	340	25	10.6	4.2
6	355	15	11.2	2.5
6	374	19	12.0	3.2
6				



Average DCP Index 3.3 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b>	MNDOT	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	27-20000 TH 59 North		Date of issue: _____ Reviewed By: _____

## **General Information**

Road:	TH 59	Tested by:	RS
Date Stabilized:	59-1	Test Location:	See below
Date Tested:	7/18/2019	Hammer Weight:	17.6 lbs
Days after stabilization:	#VALUE!	Weather:	Sunny, 92F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 62
Test No.	62-1
Date Tested:	7/17/2019

Tested by:	RS
Test Location:	48.8624446, -95.538800
Hammer Weight:	17.6 lbs
Weather:	Rain

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.7 mm/blow

## Comments



## Material Test Report

Client: Office of Materials and Road Research      CC:  
Project: MnDOT Contract No. 1031051

This document shall not  
be reproduced except in  
full, without written  
approval from American  
Engineering Testing,  
Inc.


### General Information

Road:	TH 62
Test No.	62-2
Date Tested:	7/17/2019

Tested by:	RS
Test Location:	43.8624622, -95.523822
Hammer Weight:	17.6 lbs
Weather:	Rain

### Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	80			
2	92	12	0.5	
3	110	18	1.2	6.0
3	120	10	1.6	3.3
3	130	10	2.0	3.3
3	140	10	2.4	3.3
3	150	10	2.8	3.3
3	157	7	3.0	2.3
3	165	8	3.3	2.7
6	185	20	4.1	3.3
6	200	15	4.7	2.5
6	220	20	5.5	3.3
6	235	15	6.1	2.5
6	255	20	6.9	3.3
6	272	17	7.6	2.8
6	285	13	8.1	2.2
6	305	20	8.9	3.3
6	320	15	9.4	2.5
9	350	30	10.6	3.3
9	385	35	12.0	3.9



Average DCP Index 3.2 mm/blow

### Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 62
Test No.	62-3
Date Tested:	7/17/2019

Tested by:	RS
Test Location:	43.8624751, -95.513852
Hammer Weight:	17.6 lbs
Weather:	Rain

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	68			
2	90	22	0.9	
3	105	15	1.5	5.0
6	124	19	2.2	3.2
6	141	17	2.9	2.8
6	155	14	3.4	2.3
6	172	17	4.1	2.8
9	193	21	4.9	2.3
9	214	21	5.7	2.3
9	233	19	6.5	2.1
9	251	18	7.2	2.0
9	266	15	7.8	1.7
9	280	14	8.3	1.6
9	292	12	8.8	1.3
9	306	14	9.4	1.6
9	321	15	10.0	1.7
9	338	17	10.6	1.9
9	360	22	11.5	2.4



Average DCP Index 2.3 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 62
Test No.	62-4
Date Tested:	7/17/2019

Tested by:	RS
Test Location:	43.8624854, -95.503878
Hammer Weight:	17.6 lbs
Weather:	Rain

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.0 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 62
Test No.	62-5
Date Tested:	7/17/2019

Tested by:	RS
Test Location:	43.8624817, -95.493895
Hammer Weight:	17.6 lbs
Weather:	Rain

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	70			
2	95	25	1.0	
3	110	15	1.6	5.0
3	125	15	2.2	5.0
6	145	20	3.0	3.3
3	150	5	3.1	1.7
6	165	15	3.7	2.5
6	180	15	4.3	2.5
6	195	15	4.9	2.5
6	210	15	5.5	2.5
6	225	15	6.1	2.5
6	237	12	6.6	2.0
6	250	13	7.1	2.2
6	264	14	7.6	2.3
6	278	14	8.2	2.3
6	295	17	8.9	2.8
9	322	27	9.9	3.0
9	352	30	11.1	3.3



Average DCP Index 2.8 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b>	MNDOT	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	27-20000 TH 62 East		Date of issue: _____ Reviewed By: _____

## **General Information**

Road:	62
Date Stabilized:	62-1
Date Tested:	7/17/2019
Days after stabilization:	#VALUE!

Tested by:	RS
Test Location:	See below
Hammer Weight:	17.6 lbs
Weather:	Rain

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 71
Test No.	71-1
Date Tested:	7/30/2019

Tested by:	RS
Test Location:	48.098223, -93.931970
Hammer Weight:	17.6 lbs
Weather:	Sunny, 74F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 1.8 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 71
Test No.	71-2
Date Tested:	7/30/2019

Tested by:	RS
Test Location:	48.103968, -93925898
Hammer Weight:	17.6 lbs
Weather:	Sunny, 74F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.5 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


<b>Client:</b>	Office of Materials and Road Research	<b>CC:</b>	
<b>Project:</b>	MnDOT Contract No. 1031051		This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.

## General Information

Road:	TH 71
Test No.	71-3
Date Tested:	7/30/2019

Tested by:	RS
Test Location:	48.108173, -93.916704
Hammer Weight:	17.6 lbs
Weather:	Sunny, 74F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 3.3 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 71
Test No.	71-4
Date Tested:	7/30/2019

Tested by:	RS
Test Location:	48.113590, -93909336
Hammer Weight:	17.6 lbs
Weather:	Sunny, 74F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	80			
2	95	15	0.6	
3	105	10	1.0	3.3
6	122	17	1.7	2.8
6	135	13	2.2	2.2
9	150	15	2.8	1.7
9	170	20	3.5	2.2
6	180	10	3.9	1.7
6	195	15	4.5	2.5
6	210	15	5.1	2.5
6	225	15	5.7	2.5
6	240	15	6.3	2.5
6	252	12	6.8	2.0
6	265	13	7.3	2.2
6	280	15	7.9	2.5
6	292	12	8.3	2.0
6	300	8	8.7	1.3
6	315	15	9.3	2.5
6	325	10	9.6	1.7
6	334	9	10.0	1.5



Average DCP Index 2.2 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 71
Test No.	71-5
Date Tested:	7/30/2019

Tested by:	RS
Test Location:	48.118232, -93.899777
Hammer Weight:	17.6 lbs
Weather:	Sunny, 74F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.5 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b>	MNDOT	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	27-20000 TH 71 NE		<hr/>
		Date of issue:	
		Reviewed By:	

## **General Information**

Road:	TH 71	Tested by:	Rel Seykora
Date Stabilized:	71-1	Test Location:	See below
Date Tested:	7/30/2019	Hammer Weight:	17.6 lbs
Days after stabilization:	#VALUE!	Weather:	Sunny, 74F

#### **Dynamic Cone Penetrometer Testing (ASTM: D6951)**

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 83
Test No.	83-1
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	43.9293175, -93.698210
Hammer Weight:	17.6 lbs
Weather:	Sunny

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	67			
2	92	25	1.0	
3	105	13	1.5	4.3
3	119	14	2.0	4.7
3	130	11	2.5	3.7
3	140	10	2.9	3.3
3	150	10	3.3	3.3
3	157	7	3.5	2.3
6	175	18	4.3	3.0
6	197	22	5.1	3.7
6	222	25	6.1	4.2
6	245	23	7.0	3.8
6	274	29	8.1	4.8
6	297	23	9.1	3.8
6	312	15	9.6	2.5
6	321	9	10.0	1.5
6	334	13	10.5	2.2
6	347	13	11.0	2.2
6	374	27	12.1	4.5



Average DCP Index 3.4 mm/blow

## Comments



## Material Test Report

Client: Office of Materials and Road Research      CC:  
Project: MnDOT Contract No. 1031051

This document shall not  
be reproduced except in  
full, without written  
approval from American  
Engineering Testing,  
Inc.


### General Information

Road:	TH 83
Test No.	83-2
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	43.9221416, -93.697599
Hammer Weight:	17.6 lbs
Weather:	Sunny

### Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	75			
2	100	25	1.0	
3	120	20	1.8	6.7
3	135	15	2.4	5.0
3	155	20	3.1	6.7
3	165	10	3.5	3.3
3	174	9	3.9	3.0
3	186	12	4.4	4.0
3	200	14	4.9	4.7
3	210	10	5.3	3.3
3	220	10	5.7	3.3
6	240	20	6.5	3.3
6	260	20	7.3	3.3
6	285	25	8.3	4.2
6	310	25	9.3	4.2
6	327	17	9.9	2.8
3	332	5	10.1	1.7
3	340	8	10.4	2.7
6	355	15	11.0	2.5



Average DCP Index 3.8 mm/blow

### Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 83
Test No.	83-3
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	43.9149320, -93.697750
Hammer Weight:	17.6 lbs
Weather:	Sunny

### **Dynamic Cone Penetrometer Testing (ASTM: D6951)**

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	75			
2	110	35	1.4	
3	130	20	2.2	6.7
3	147	17	2.8	5.7
3	158	11	3.3	3.7
3	165	7	3.5	2.3
3	180	15	4.1	5.0
3	195	15	4.7	5.0
3	205	10	5.1	3.3
3	220	15	5.7	5.0
3	230	10	6.1	3.3
3	240	10	6.5	3.3
3	245	5	6.7	1.7
3	250	5	6.9	1.7
3	255	5	7.1	1.7
3	270	15	7.7	5.0
3	280	10	8.1	3.3
3	300	20	8.9	6.7
3	325	25	9.8	8.3
3	380	55	12.0	18.3



Average DCP Index 5.0 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 83
Test No.	83-4
Date Tested:	7/16/2019

Tested by:	RS
Test Location:	43.9077229, -93.697636
Hammer Weight:	17.6 lbs
Weather:	Sunny

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 3.5 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 83
Test No.	83-5
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	43.9005092, -93.697411
Hammer Weight:	17.6 lbs
Weather:	Sunny

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	82			
2	100	18	0.7	
3	115	15	1.3	5.0
3	127	12	1.8	4.0
3	135	8	2.1	2.7
3	150	15	2.7	5.0
3	160	10	3.1	3.3
3	170	10	3.5	3.3
3	180	10	3.9	3.3
6	205	25	4.8	4.2
6	233	28	5.9	4.7
6	257	24	6.9	4.0
6	270	13	7.4	2.2
6	273	3	7.5	0.5
6	280	7	7.8	1.2
6	285	5	8.0	0.8
6	295	10	8.4	1.7
6	315	20	9.2	3.3
6	340	25	10.2	4.2



Average DCP Index 3.1 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b>	MNDOT	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	27-20000 TH 83 South		Date of issue: _____ Reviewed By: _____

## **General Information**

Road:	83	Tested by:	Rel Seykora
Date Stabilized:	83-1	Test Location:	See below
Date Tested:	7/16/2019	Hammer Weight:	17.6 lbs
Days after stabilization:	#VALUE!	Weather:	Sunny

#### **Dynamic Cone Penetrometer Testing (ASTM: D6951)**

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 109
Test No.	109-1
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	43.7605718, -93.997369
Hammer Weight:	17.6 lbs
Weather:	Sunny, 75F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 3.1 mm/blow

## Comments



## Material Test Report

**Client:** Office of Materials and Road Research      **CC:**

**Project:** MnDOT Contract No. 1031051

This document shall not  
be reproduced except in  
full, without written  
approval from American  
Engineering Testing,  
Inc.


### General Information

Road:	TH 109
Test No.	109-2
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	43.7605414, -94.007325
Hammer Weight:	17.6 lbs
Weather:	Sunny, 75F

### Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	70			
2	92	22	0.9	
3	97	5	1.1	1.7
6	108	11	1.5	1.8
6	116	8	1.8	1.3
9	135	19	2.6	2.1
12	151	16	3.2	1.3
12	168	17	3.9	1.4
15	185	17	4.5	1.1
15	203	18	5.2	1.2
15	222	19	6.0	1.3
15	243	21	6.8	1.4
15	264	21	7.6	1.4
15	287	23	8.5	1.5
15	309	22	9.4	1.5
15	315	6	9.6	0.4
15	327	12	10.1	0.8
12	339	12	10.6	1.0
12	355	16	11.2	1.3



Average DCP Index 1.3 mm/blow

### Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 109
Test No.	109-3
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	43.7604880, -94.017292
Hammer Weight:	17.6 lbs
Weather:	Sunny, 75F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 3.1 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.

## General Information

Road:	TH 109
Test No.	109-4
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	43.7604950, -94.027231
Hammer Weight:	17.6 lbs
Weather:	Sunny, 75F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 7.5 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## **General Information**

Road:	TH 109
Test No.	109-5
Date Tested:	7/24/2019

Tested by:	RS
Test Location:	43.7605007, -94.037183
Hammer Weight:	17.6 lbs
Weather:	Sunny, 75F

#### **Dynamic Cone Penetrometer Testing (ASTM: D6951)**



Average DCP Index 1.9 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b> MNDOT	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b> 27-20000 TH 109 West		Date of issue: _____ Reviewed By: _____

## **General Information**

Road:	109	Tested by:	RS
Date Stabilized:	109-1	Test Location:	See below
Date Tested:	7/24/2019	Hammer Weight:	17.6 lbs
Days after stabilization:	#VALUE!	Weather:	Sunny, 75F

#### **Dynamic Cone Penetrometer Testing (ASTM: D6951)**

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 238
Test No.	238-1
Date Tested:	7/29/2019

Tested by:	RS
Test Location:	45.7239862, -94.593792
Hammer Weight:	17.6 lbs
Weather:	Overcast, 70F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.7 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 238
Test No.	238-2
Date Tested:	7/29/2019

Tested by:	RS
Test Location:	45.709007, -94.602747
Hammer Weight:	17.6 lbs
Weather:	Overcast, 70F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 3.6 mm/blow

## Comments



## Material Test Report

Client: Office of Materials and Road Research      CC:  
Project: MnDOT Contract No. 1031051

This document shall not  
be reproduced except in  
full, without written  
approval from American  
Engineering Testing,  
Inc.


### General Information

Road:	TH 238
Test No.	238-3
Date Tested:	7/29/2019

Tested by:	RS
Test Location:	45.700779, -94.605120
Hammer Weight:	17.6 lbs
Weather:	Overcast, 70F

### Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	90			
2	110	20	0.8	
3	125	15	1.4	5.0
3	135	10	1.8	3.3
3	142	7	2.0	2.3
3	150	8	2.4	2.7
3	157	7	2.6	2.3
3	167	10	3.0	3.3
3	175	8	3.3	2.7
3	184	9	3.7	3.0
3	190	6	3.9	2.0
3	200	10	4.3	3.3
3	215	15	4.9	5.0
3	224	9	5.3	3.0
3	232	8	5.6	2.7
6	246	14	6.1	2.3
6	265	19	6.9	3.2
6	290	25	7.9	4.2
6	340	50	9.8	8.3



Average DCP Index 3.5 mm/blow

### Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051


## General Information

Road:	TH 238
Test No.	238-4
Date Tested:	7/29/2019

Tested by:	RS
Test Location:	45.688692, -94.604301
Hammer Weight:	17.6 lbs
Weather:	Overcast, 70F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

Number of Blows	DCP Readings (mm)	Difference (mm)	Depth (in)	DCP Index (mm/blow)
	75			
2	95	20	0.8	
3	115	20	1.6	6.7
6	125	10	2.0	1.7
6	142	17	2.6	2.8
6	160	18	3.3	3.0
6	177	17	4.0	2.8
6	195	18	4.7	3.0
6	210	15	5.3	2.5
6	220	10	5.7	1.7
6	232	12	6.2	2.0
6	245	13	6.7	2.2
6	260	15	7.3	2.5
6	270	10	7.7	1.7
6	282	12	8.1	2.0
6	295	13	8.7	2.2
6	312	17	9.3	2.8
6	325	13	9.8	2.2
6	355	30	11.0	5.0



Average DCP Index 2.7 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report


**Client:** Office of Materials and Road Research      **CC:** \_\_\_\_\_  
**Project:** MnDOT Contract No. 1031051

## General Information

Road:	TH 238
Test No.	238-5
Date Tested:	7/29/2019

Tested by:	RS
Test Location:	45.681660, -94.603741
Hammer Weight:	17.6 lbs
Weather:	Overcast, 70F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)



Average DCP Index 2.4 mm/blow

## Comments



# AMERICAN ENGINEERING TESTING, INC.

American Engineering Testing, Inc.  
Saint Paul  
550 Cleveland Ave N  
St. Paul, MN 55114  
(651) 659-9001  
Toll Free: (800) 972-6364  
[www.amengtest.com](http://www.amengtest.com)

# Material Test Report

<b>Client:</b>	MNDOT	<b>CC:</b>	This document shall not be reproduced except in full, without written approval from American Engineering Testing, Inc.
<b>Project:</b>	27-20000 TH 238 North		<hr/>
		Date of issue:	
		Reviewed By:	

## **General Information**

Road:	238	Tested by:	Rel Seykora
Date Stabilized:	238-1	Test Location:	See below
Date Tested:	7/29/2019	Hammer Weight:	17.6 lbs
Days after stabilization:	#VALUE!	Weather:	Overcast, 70F

## Dynamic Cone Penetrometer Testing (ASTM: D6951)

## Comments

For all soils except CL<10 CBR and CH soils, CBR=292/(DPI<sup>1.12</sup>). For CL<10, CBR=1/((0.017019\*DPI)<sup>2</sup>. For CH soils CBR=1/(0.002871\*DPI).

## **APPENDIX C: TONN2010 ANALYSIS SHEETS BY LOCATION**

Version TONN2010-1.06	<b>Get FWD Data</b>	<b>Segments (20 max)</b>		
6/19/2019				
<b>Roadway</b>	From Station	State	To Station	<b>Segments (20 max)</b>
Mn Road	0.100	Aid	Aid	96.8
<b>Previous Day's</b>				
Max. Temp °F	57			
Min. Temp °F	61			
Avg. Temp °F	59			
<b>HMA Thickness (inches)</b>				
5	Fill			
0.10	5.0	P	3	9.0
0.20	5.0	P	3	9.0
0.32	5.0	P	3	9.0
0.40	5.0	P	3	9.0
0.50	5.0	P	3	9.0
0.61	5.0	P	3	9.0
0.70	5.0	P	3	9.0
0.80	5.0	P	3	9.0
0.90	5.0	P	3	9.0
1.00	5.0	P	3	9.0
1.10	5.0	P	3	9.0
1.20	5.0	P	3	9.0
1.30	5.0	P	3	9.0
1.40	5.0	P	3	9.0
1.50	5.0	P	3	9.0
1.60	5.0	P	3	9.0
1.70	5.0	P	3	9.0
1.80	5.0	P	3	9.0
1.90	5.0	P	3	9.0
2.00	5.0	P	3	9.0
<b>Base Thickness (inches)</b>				
9	Fill			
0.10	5.0	P	3	9.0
0.20	5.0	P	3	9.0
0.32	5.0	P	3	9.0
0.40	5.0	P	3	9.0
0.50	5.0	P	3	9.0
0.61	5.0	P	3	9.0
0.70	5.0	P	3	9.0
0.80	5.0	P	3	9.0
0.90	5.0	P	3	9.0
1.00	5.0	P	3	9.0
1.10	5.0	P	3	9.0
1.20	5.0	P	3	9.0
1.30	5.0	P	3	9.0
1.40	5.0	P	3	9.0
1.50	5.0	P	3	9.0
1.60	5.0	P	3	9.0
1.70	5.0	P	3	9.0
1.80	5.0	P	3	9.0
1.90	5.0	P	3	9.0
2.00	5.0	P	3	9.0
<b>Design ESALS</b>				
1,000,000	Fill			
0.10	5.0	P	3	9.0
0.20	5.0	P	3	9.0
0.32	5.0	P	3	9.0
0.40	5.0	P	3	9.0
0.50	5.0	P	3	9.0
0.61	5.0	P	3	9.0
0.70	5.0	P	3	9.0
0.80	5.0	P	3	9.0
0.90	5.0	P	3	9.0
1.00	5.0	P	3	9.0
1.10	5.0	P	3	9.0
1.20	5.0	P	3	9.0
1.30	5.0	P	3	9.0
1.40	5.0	P	3	9.0
1.50	5.0	P	3	9.0
1.60	5.0	P	3	9.0
1.70	5.0	P	3	9.0
1.80	5.0	P	3	9.0
1.90	5.0	P	3	9.0
2.00	5.0	P	3	9.0
<b>County</b>				
McLeod	Fill			
Mahnomen	Fill			
Marshall	Fill			
<b>Begin Overlay Design</b>				
<b>Run TONN2010</b>				
<b>Soil Type</b>				
Plastic	Fill			
Conventional	Fill			
Conv/Ful Depth	Conventional			
<b>Traffic Category</b>				
3 - ADT 1000-3000	HCADT 50-150	►		
2.40	5.0	P	3	9.0
2.50	5.0	P	3	9.0
2.60	5.0	P	3	9.0
2.70	5.0	P	3	9.0
2.80	5.0	P	3	9.0
2.90	5.0	P	3	9.0
3.00	5.0	P	3	9.0
3.10	5.0	P	3	9.0
<b>HIDE STATE AID</b>				
This button will estimate the number of ESALS that will result in a rating of 10-tons.				
<b>Estimate Number of ESALS for 10-Ton Rating</b>				
<b>Make KML File</b>				

Test Date		Pave. Temp.		Segments (20 max)
6/19/2019		96.8		
<b>Roadway</b>	From Station	State	To Station	<b>Segments (20 max)</b>
Mn Road	0.100	Aid	Aid	96.8
<b>Previous Day's</b>				
Max. Temp °F	57			
Min. Temp °F	61			
Avg. Temp °F	59			
<b>HMA Thickness (inches)</b>				
5	Fill			
0.10	5.0	P	3	9.0
0.20	5.0	P	3	9.0
0.32	5.0	P	3	9.0
0.40	5.0	P	3	9.0
0.50	5.0	P	3	9.0
0.61	5.0	P	3	9.0
0.70	5.0	P	3	9.0
0.80	5.0	P	3	9.0
0.90	5.0	P	3	9.0
1.00	5.0	P	3	9.0
1.10	5.0	P	3	9.0
1.20	5.0	P	3	9.0
1.30	5.0	P	3	9.0
1.40	5.0	P	3	9.0
1.50	5.0	P	3	9.0
1.60	5.0	P	3	9.0
1.70	5.0	P	3	9.0
1.80	5.0	P	3	9.0
1.90	5.0	P	3	9.0
2.00	5.0	P	3	9.0
<b>Base Thickness (inches)</b>				
9	Fill			
0.10	5.0	P	3	9.0
0.20	5.0	P	3	9.0
0.32	5.0	P	3	9.0
0.40	5.0	P	3	9.0
0.50	5.0	P	3	9.0
0.61	5.0	P	3	9.0
0.70	5.0	P	3	9.0
0.80	5.0	P	3	9.0
0.90	5.0	P	3	9.0
1.00	5.0	P	3	9.0
1.10	5.0	P	3	9.0
1.20	5.0	P	3	9.0
1.30	5.0	P	3	9.0
1.40	5.0	P	3	9.0
1.50	5.0	P	3	9.0
1.60	5.0	P	3	9.0
1.70	5.0	P	3	9.0
1.80	5.0	P	3	9.0
1.90	5.0	P	3	9.0
2.00	5.0	P	3	9.0
<b>Design ESALS</b>				
1,000,000	Fill			
0.10	5.0	P	3	9.0
0.20	5.0	P	3	9.0
0.32	5.0	P	3	9.0
0.40	5.0	P	3	9.0
0.50	5.0	P	3	9.0
0.61	5.0	P	3	9.0
0.70	5.0	P	3	9.0
0.80	5.0	P	3	9.0
0.90	5.0	P	3	9.0
1.00	5.0	P	3	9.0
1.10	5.0	P	3	9.0
1.20	5.0	P	3	9.0
1.30	5.0	P	3	9.0
1.40	5.0	P	3	9.0
1.50	5.0	P	3	9.0
1.60	5.0	P	3	9.0
1.70	5.0	P	3	9.0
1.80	5.0	P	3	9.0
1.90	5.0	P	3	9.0
2.00	5.0	P	3	9.0
<b>County</b>				
McLeod	Fill			
Mahnomen	Fill			
Marshall	Fill			
<b>Begin Overlay Design</b>				
<b>Run TONN2010</b>				
<b>Soil Type</b>				
Plastic	Fill			
Conventional	Fill			
Conv/Ful Depth	Conventional			
<b>Traffic Category</b>				
3 - ADT 1000-3000	HCADT 50-150	►		
2.40	5.0	P	3	9.0
2.50	5.0	P	3	9.0
2.60	5.0	P	3	9.0
2.70	5.0	P	3	9.0
2.80	5.0	P	3	9.0
2.90	5.0	P	3	9.0
3.00	5.0	P	3	9.0
3.10	5.0	P	3	9.0
<b>HIDE STATE AID</b>				
This button will estimate the number of ESALS that will result in a rating of 10-tons.				
<b>Estimate Number of ESALS for 10-Ton Rating</b>				
<b>Make KML File</b>				

Test Date				Pave. Temp.		Segments (20 max)	
6/19/2019				94.5		1	
Roadway		From Station	State	To Station	District		
Min Roads		0.100	Aid	Aid	3.100	0	
Station	HMA Thickness	Soil Type	Traffic Cat.	Base Thickness	ESALS		
0.10	4.0	P	2	10.0	1,000,000		
0.20	4.0	P	2	10.0	1,000,000		
0.30	4.0	P	2	10.0	1,000,000		
0.40	4.0	P	2	10.0	1,000,000		
0.50	4.0	P	2	10.0	1,000,000		
0.60	4.0	P	2	10.0	1,000,000		
0.70	4.0	P	2	10.0	1,000,000		
0.80	4.0	P	2	10.0	1,000,000		
0.90	4.0	P	2	10.0	1,000,000		
1.00	4.0	P	2	10.0	1,000,000		
1.10	4.0	P	2	10.0	1,000,000		
1.20	4.0	P	2	10.0	1,000,000		
1.30	4.0	P	2	10.0	1,000,000		
1.40	4.0	P	2	10.0	1,000,000		
1.50	4.0	P	2	10.0	1,000,000		
1.60	4.0	P	2	10.0	1,000,000		
1.70	4.0	P	2	10.0	1,000,000		
1.80	4.0	P	2	10.0	1,000,000		
1.90	4.0	P	2	10.0	1,000,000		
2.00	4.0	P	2	10.0	1,000,000		
2.10	4.0	P	2	10.0	1,000,000		
2.20	4.0	P	2	10.0	1,000,000		
2.30	4.0	P	2	10.0	1,000,000		
2.40	4.0	P	2	10.0	1,000,000		
2.50	4.0	P	2	10.0	1,000,000		
2.60	4.0	P	2	10.0	1,000,000		
2.70	4.0	P	2	10.0	1,000,000		
2.80	4.0	P	2	10.0	1,000,000		
2.90	4.0	P	2	10.0	1,000,000		
3.00	4.0	P	2	10.0	1,000,000		
3.10	4.0	P	2	10.0	1,000,000		

This button will estimate the number of ESALs that will result in a rating of 10-tons.

**Estimate Number of  
ESALs for 10-Ton Rating**

**Make KML File**

Version TONN2010-1.06	<b>Get FWD Data</b>	<b>Segments (20 max)</b>									
6/20/2019		87.3									
Roadway	From Station	State	To Station	District	State	Control Section	Lane	Direction	Lat. and Long.	State	
Mn Road	0.100	Aid	Aid	3.100	0	Aid	TH 11 EB	0	Increasing	48.6524, -94.25	
<b>Previous Day's</b>	<b>7</b>										
Max. Temp °F	64.21										
Min. Temp °F	66.21										
Avg. Temp °F	65.21										
<b>HMA Thickness (inches)</b>	<b>85% Percentile</b>										
6	Fill	0.10	6.0	P	2	12.0	1,000,000	31.9	10.4	GE Capacity, Tons	
0.20	Fill	0.20	6.0	P	2	12.0	1,000,000	29.9	10.1	HMA (72° F)	
0.30	Fill	0.30	6.0	P	2	12.0	1,000,000	34.2	11.5	Moduli Statistics	
0.40	Fill	0.40	6.0	P	2	12.0	1,000,000	27.5	9.1	#1 Defl. (mils)	
0.50	Fill	0.50	6.0	P	2	12.0	1,000,000	25.7	9.7	R-value	
0.60	Fill	0.60	6.0	P	2	12.0	1,000,000	30.6	12.3	14	
0.70	Fill	0.70	6.0	P	2	12.0	1,000,000	31.5	9.9	19	
0.80	Fill	0.80	6.0	P	2	12.0	1,000,000	29.2	9.7	6	
0.90	Fill	0.90	6.0	P	2	12.0	1,000,000	26.1	7.7		
1.00	Fill	1.00	6.0	P	2	12.0	1,000,000	29.5	10.0		
1.10	Fill	1.10	6.0	P	2	12.0	1,000,000	31.2	9.9		
1.20	Fill	1.20	6.0	P	2	12.0	1,000,000	26.1	9.5		
1.30	Fill	1.30	6.0	P	2	12.0	1,000,000	29.9	10.7		
1.40	Fill	1.40	6.0	P	2	12.0	1,000,000	30.8	14.9		
1.50	Fill	1.50	6.0	P	2	12.0	1,000,000	29.0	11.2		
1.60	Fill	1.60	6.0	P	2	12.0	1,000,000	29.6	11.2		
1.70	Fill	1.70	6.0	P	2	12.0	1,000,000	22.8	9.6		
1.80	Fill	1.80	6.0	P	2	12.0	1,000,000	32.6	11.0		
1.91	Fill	1.91	6.0	P	2	12.0	1,000,000	31.2	10.6		
2.00	Fill	2.00	6.0	P	2	12.0	1,000,000	28.8	9.5		
2.10	Fill	2.10	6.0	P	2	12.0	1,000,000	28.9	9.7		
2.20	Fill	2.20	6.0	P	2	12.0	1,000,000	30.6	10.9		
2.30	Fill	2.30	6.0	P	2	12.0	1,000,000	27.6	9.4		
2.40	Fill	2.40	6.0	P	2	12.0	1,000,000	31.2	11.4		
2.50	Fill	2.50	6.0	P	2	12.0	1,000,000	33.4	11.3		
2.60	Fill	2.60	6.0	P	2	12.0	1,000,000	33.0	10.6		
2.70	Fill	2.70	6.0	P	2	12.0	1,000,000	32.7	11.7		
2.80	Fill	2.80	6.0	P	2	12.0	1,000,000	22.6	7.7		
2.90	Fill	2.90	6.0	P	2	12.0	1,000,000	29.8	9.1		
3.00	Fill	3.00	6.0	P	2	12.0	1,000,000	28.9	9.0		
3.10	Fill	3.10	6.0	P	2	12.0	1,000,000	28.2	8.7		

**Begin Overlay Design**

**Run TONN2010**

**Soil Type**

**Plastic**

**Fill**

**Traffic Category**

**2 - ADT 500-1000 HCADT 25-50**

**Fill**

**CONV/FUL Depth**

**CONVENTIONAL**

**HIDE STATE AID**

**Estimate Number of ESALs for 10-Ton Rating**

This button will estimate the number of ESALs that will result in a rating of 10-ton.

**Make KML File**

Test Date		Pave. Temp.	Segments (20 max)								
6/20/2019		87.3									
Roadway	From Station	State	To Station	District	State	Control Section	Lane	Direction	Lat. and Long.	State	
Mn Road	0.100	Aid	Aid	3.100	0	Aid	TH 11 EB	0	Increasing	48.6524, -94.25	Aid
<b>GE</b>	<b>Capacity, Tons</b>	<b>9.1</b>	<b>HMA (72° F)</b>	<b>10.3</b>	<b>489,371</b>	<b>32,884</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>187,874</b>	<b>8,091</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>463,467</b>	<b>37,642</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>326,836</b>	<b>42,036</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>633,299</b>	<b>44,509</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>270,136</b>	<b>33,939</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>202,636</b>	<b>56,044</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>544,738</b>	<b>52,527</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>523,667</b>	<b>9,417</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>328,339</b>	<b>37,091</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>222,475</b>	<b>22,941</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>345,701</b>	<b>38,701</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>550,617</b>	<b>27,600</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>299,873</b>	<b>33,664</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>790,746</b>	<b>23,195</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>936,706</b>	<b>16,290</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>637,954</b>	<b>16,635</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>678,302</b>	<b>16,371</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>244,774</b>	<b>31,035</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>797,071</b>	<b>30,332</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>586,944</b>	<b>10,478</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>491,088</b>	<b>12,447</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>546,119</b>	<b>15,116</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>494,033</b>	<b>27,174</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>581,538</b>	<b>31,583</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>424,153</b>	<b>12,403</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>30,332</b>	<b>10,478</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>546,119</b>	<b>12,447</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>494,033</b>	<b>14,166</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>461,085</b>	<b>47,936</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>622,746</b>	<b>39,589</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>506,849</b>	<b>38,753</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>753,120</b>	<b>36,210</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>29,005</b>	<b>5,647</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>173,228</b>	<b>24</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>464,909</b>	<b>25,024</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>454,684</b>	<b>21,436</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>
<b>GE</b>	<b>Capacity, Tons</b>	<b>10.4</b>	<b>HMA (72° F)</b>	<b>10.4</b>	<b>403,381</b>	<b>21,438</b>	<b>Subgrade</b>	<b>1.40</b>	<b>11,057</b>	<b>2,991</b>	<b>3.4</b>

Test Date				Pave. Temp		Segments (20 max)					
6/19/2019				93.7		1					
Roadway		From Station	State	State	To Station	District		Average Std. Dev.			
Mn Road		0.040	Aid	Aid	3.100	0					
Station	HMA Thickness	Soil Type	Traffic Cat.	Base Thickness	ESALs						
0.04	4.5	P	3	8.0	1,000,000						
0.10	4.5	P	3	8.0	1,000,000						
0.20	4.5	P	3	8.0	1,000,000						
0.30	4.5	P	3	8.0	1,000,000						
0.40	4.5	P	3	8.0	1,000,000						
0.50	4.5	P	3	8.0	1,000,000						
0.60	4.5	P	3	8.0	1,000,000						
0.70	4.5	P	3	8.0	1,000,000						
0.80	4.5	P	3	8.0	1,000,000						
0.90	4.5	P	3	8.0	1,000,000						
1.00	4.5	P	3	8.0	1,000,000						
1.10	4.5	P	3	8.0	1,000,000						
1.20	4.5	P	3	8.0	1,000,000						
1.30	4.5	P	3	8.0	1,000,000						
1.40	4.5	P	3	8.0	1,000,000						
1.50	4.5	P	3	8.0	1,000,000						
1.60	4.5	P	3	8.0	1,000,000						
1.70	4.5	P	3	8.0	1,000,000						
1.80	4.5	P	3	8.0	1,000,000						
1.90	4.5	P	3	8.0	1,000,000						
2.00	4.5	P	3	8.0	1,000,000						
2.10	4.5	P	3	8.0	1,000,000						
2.20	4.5	P	3	8.0	1,000,000						
2.30	4.5	P	3	8.0	1,000,000						
2.40	4.5	P	3	8.0	1,000,000						
2.50	4.5	P	3	8.0	1,000,000						
2.60	4.5	P	3	8.0	1,000,000						
2.70	4.5	P	3	8.0	1,000,000						
2.80	4.5	P	3	8.0	1,000,000						
2.90	4.5	P	3	8.0	1,000,000						
3.00	4.5	P	3	8.0	1,000,000						
3.10	4.5	P	3	8.0	1,000,000						

<b>Get FWD Data</b>	<b>Previous Days'</b>	<b>HMATHickness (inches)</b>	<b>Base Thickness (inches)</b>	<b>Design ESALs</b>	<b>County</b>	<b>Traffic Category</b>	<b>Soil Type</b>	<b>HIDE STATE AID</b>	<b>Estimate Number of ESALs for 10-Ton Rating</b>	<b>Make KML File</b>
	Max. Temp. °F Min. Temp. °F Avg. Temp. °F	4.5	Fill	8	Fill	1,000,000	Plastic	Fill	3 - ADT 1000-3000 CConv/Full Depth	HCADT 50-150 Conventional
	59.61 61.61 60.61				Nicollet Nobles Norman				This button will estimate the number of ESALs that will result in a rating of 10-ton.	

C-4



Test Date	10/12/2018
Roadway	DE TR TH59NB Right w/
Station	27-00000 TH59NB Right w/
Previous Day's Max. Temp. °F	32
Min. Temp. °F	33.54
Avg. Temp. °F	32.77
HMAT Thickness (inches)	7
Base Thickness (inches)	10
Design ESALs	1,000,000
County	Steel Stevens Swift
Run TONN2010	
Begin Overlay Design	
Soil Type	Fill Plastic
Traffic Category	3 - ADT 1000-3000 HCADT 50-150 Convex/Full Depth Conventional
HIDE STATE AID	
Estimate Number of ESALs for 10-Ton Rating	This button will estimate the number of ESALs that will result in a rating of 10-ton.
Make KML File	

Control Section		Lane	Direction	Lat. and Long.		State
State	id	TH59	0	Increasing	45.2243, -95.9121	Aid
Capacity, Tons	HMA(72° F)	Moduli Statistics	Subgrade	#1 Deft. (mils)	R-value	
<b>EE</b>	<b>11.0</b>	724.412	61,216	<b>11.249</b>	10.3	<b>15</b>
.7	12.1	157,472	32,990	2,473	2.4	5
<b>EE</b>	<b>TONN2010</b>		Moduli	#1 Deft. (mils)	S.A.	R-Value
Capacity, Tons	HMA(72° F)	Base	Subgrade			
.6	12.0	822,352	75,617	8,763	11	14
.8	12.0	705,498	77,806	9,599	11	16
.3	12.0	758,576	67,891	9,997	11	17
.1	11.7	803,385	46,536	10,423	11	18
.4	12.3	816,768	74,642	9,781	10	17
.6	12.3	866,872	55,520	11,129	9	19
.9	12.3	719,977	46,073	13,378	10	24
.7	12.0	820,550	58,926	10,271	10	18
.8	12.0	531,099	97,058	10,188	10	17
.5	13.2	1,070,814		5		
.3	13.8	774,810	122,812	12,892	9	23
.8	13.7	765,276	121,924	12,192	9	22
.5	11.4	740,894	59,228	8,861	11	15
.7	12.5	750,271	68,948	11,817	10	21
.9	13.2	671,364	132,350	14,620	8	27
.9	13.3	967,238	66,890	12,359	9	22
.8	12.6	782,215	65,555	12,111	9	21
.6	10.7	416,596	52,975	11,177	12	19
.7	13.8	663,630	110,189	17,884	8	35
.1	14.2	805,164	120,767	6		
.7	10.5	657,812	39,906	8,647	12	14
.8	11.9	716,930	23,325	13,346	11	24
.3	8.8	343,429	9,083	9,083	19	15
.5	9.1	558,734	20,276	7,004	15	11
0	11.1	875,498	12,073	8,943	12	15
.2	12.1	794,648	85,134	8,513	10	14
.2	12.6	795,155	64,692	12,063	10	21
.5	11.9	455,577	46,955	16,221	10	31
9	10.1	523,441	35,830	9,327	13	16
.1	12.9	839,539	26,362	15,086	10	28
.5	11.0	710,149	58,393	8,158	11	13
.1	14.4	588,238	25,279	8		
.2	12.2	886,733	43,544	11,333	10	20
.5	12.1	851,299	20,666	12,503	10	22
.1	11.1	491,876	48,125	12,299	12	22

Test Date										Segments (20 max)										State			
10/12/2018					Pave. Temp.					1					Lat. and Long.					Aid			
Roadway		From Station		State	State	To Station	District	State		Aid		GE		Control Section		Lane		Direction		Lat. and Long.			
0.0000 TH 62 EB Right wh		0.000		Aid	Aid	3.300	0	Aid		GE		TH62		0		Increasing		43.8224, -95.5438		R-value			
85% Percentile		15.5		7.9		Capacity, Tons		HMA(72° F)		Moduli Statistics		#1 Defl.		Lat. and Long.		19		23		Aid			
Average		17.0		8.6		716,832		Base		Subgrade		(mils)		16.3		2,246		2.2		5			
Std Dev.		2.05		0.73		TONN2010		Moduli		#1 Defl.		(mils)		S.A.		R-value		19		23			
m DEPARTMENT OF TRANSPORTATION		HMA		Soil		Traffic		Base		Thickness		ESALS		GE		Capacity, Tons		HMA(72° F)		Base		Subgrade	
Station	Thickness	Type	Cat.	Thickness	ESALS	GE	Capacity, Tons	HMA(72° F)	Base	Capacity, Tons	GE	Capacity, Tons	HMA(72° F)	GE	Capacity, Tons	HMA(72° F)	Base	Moduli	#1 Defl.	(mils)	S.A.	R-value	
0.00	4.0	P	2	10.0	1,000,000	15.5	8.6	732,395	24,862	15.349	17	29	732,395	8.6	15.349	17	29	15.349	17	29	29	29	
0.10	4.0	P	2	10.0	1,000,000	11.2	8.0	354,847	31,891	15.237	19	29	354,847	8.0	15.237	19	29	15.237	19	29	29	29	
0.20	4.0	P	2	10.0	1,000,000	16.6	9.4	1,007,944	16,768	16,761	16	32	1,007,944	9.4	16,768	16	32	16,761	16	32	32	32	
0.30	4.0	P	2	10.0	1,000,000	11.4	9.9	394,306	67,377	67,377	13	13	394,306	9.9	67,377	13	13	67,377	13	13	13	13	
0.40	4.0	P	2	10.0	1,000,000	18.5	9.4	912,781	48,822	15,226	14	29	912,781	9.4	48,822	14	29	15,226	14	29	29	29	
0.50	4.0	P	2	10.0	1,000,000	16.3	8.2	659,097	43,839	11,475	16	20	659,097	8.2	43,839	16	20	11,475	16	20	20	20	
0.60	4.0	P	2	10.0	1,000,000	16.7	7.4	640,463	29,381	10,150	20	17	640,463	7.4	29,381	20	17	10,150	20	17	17	17	
0.70	4.0	P	2	10.0	1,000,000	16.5	7.4	574,001	30,811	10,644	20	18	574,001	7.4	30,811	20	18	10,644	20	18	18	18	
0.80	4.0	P	2	10.0	1,000,000	16.6	8.7	570,977	62,400	11,856	15	21	570,977	8.7	62,400	15	21	11,856	15	21	21	21	
0.90	4.0	P	2	10.0	1,000,000	16.8	7.6	562,528	35,934	10,940	19	19	562,528	7.6	35,934	19	19	10,940	19	19	19	19	
1.00	4.0	P	2	10.0	1,000,000	18.7	7.7	660,003	39,204	9,849	19	17	660,003	7.7	39,204	19	17	9,849	19	17	17	17	
1.10	4.0	P	2	10.0	1,000,000	20.2	8.2	76,094	55,631	9,496	17	16	76,094	8.2	55,631	17	16	9,496	17	16	16	16	
1.20	4.0	P	2	10.0	1,000,000	19.2	8.8	931,125	47,043	12,396	15	22	931,125	8.8	47,043	15	22	12,396	15	22	22	22	
1.30	4.0	P	2	10.0	1,000,000	18.9	8.4	841,944	38,831	12,112	16	21	841,944	8.4	38,831	16	21	12,112	16	21	21	21	
1.40	4.0	P	2	10.0	1,000,000	19.8	8.6	746,232	59,969	10,453	16	18	746,232	8.6	59,969	16	18	10,453	16	18	18	18	
1.50	4.0	P	2	10.0	1,000,000	18.0	9.5	792,682	56,875	15,287	14	29	792,682	9.5	56,875	14	29	15,287	14	29	29	29	
1.60	4.0	P	2	10.0	1,000,000	19.6	8.7	991,921	37,714	12,318	16	22	991,921	8.7	37,714	16	22	12,318	16	22	22	22	
1.70	4.0	P	2	10.0	1,000,000	18.7	8.7	702,848	53,045	12,291	16	22	702,848	8.7	53,045	16	22	12,291	16	22	22	22	
1.80	4.0	P	2	10.0	1,000,000	18.7	8.5	633,986	55,557	11,600	16	20	633,986	8.5	55,557	16	20	11,600	16	20	20	20	
1.90	4.0	P	2	10.0	1,000,000	15.8	9.4	640,738	55,656	15,958	14	30	640,738	9.4	55,656	14	30	15,958	14	30	30	30	
2.00	4.0	P	2	10.0	1,000,000	16.6	10.1	896,299	46,198	12,166	12	25	896,299	10.1	46,198	12	25	12,166	12	25	25	25	
2.10	4.0	P	2	10.0	1,000,000	14.7	9.7	722,895	45,668	18,863	13	37	722,895	9.7	45,668	13	37	18,863	13	37	37	37	
2.20	4.0	P	2	10.0	1,000,000	16.6	8.2	665,974	34,166	12,735	17	23	665,974	8.2	34,166	17	23	12,735	17	23	23	23	
2.30	4.0	P	2	10.0	1,000,000	17.5	8.0	653,048	37,322	11,675	18	21	653,048	8.0	37,322	18	21	11,675	18	21	21	21	
2.40	4.0	P	2	10.0	1,000,000	19.0	8.9	688,886	58,831	12,413	15	22	688,886	8.9	58,831	15	22	12,413	15	22	22	22	
2.50	4.0	P	2	10.0	1,000,000	19.3	9.3	872,538	55,452	13,671	14	25	872,538	9.3	55,452	14	25	13,671	14	25	25	25	
2.60	4.0	P	2	10.0	1,000,000	17.8	8.7	767,447	42,249	13,411	15	24	767,447	8.7	42,249	15	24	13,411	15	24	24	24	
2.70	4.0	P	2	10.0	1,000,000	16.7	9.3	878,061	33,454	16,506	14	32	878,061	9.3	33,454	14	32	16,506	14	32	32	32	
2.80	4.0	P	2	10.0	1,000,000	15.5	7.9	628,587	27,367	12,663	18	23	628,587	7.9	27,367	18	23	12,663	18	23	23	23	
2.90	4.0	P	2	10.0	1,000,000	15.2	7.9	563,265	40,070	11,442	17	20	563,265	7.9	40,070	17	20	11,442	17	20	20	20	
3.00	4.0	P	2	10.0	1,000,000	17.1	7.9	774,964	23,648	12,044	18	21	774,964	7.9	23,648	18	21	12,044	18	21	21	21	
3.10	4.0	P	2	10.0	1,000,000	15.9	7.5	696,730	18,800	11,388	20	20	696,730	7.5	18,800	20	20	11,388	20	20	20	20	
3.20	4.0	P	2	10.0	1,000,000	17.0	8.7	777,021	38,881	13,833	15	25	777,021	8.7	38,881	15	25	13,833	15	25	25	25	
3.30	4.0	P	2	10.0	1,000,000	16.2	7.9	668,639	37,199	11,294	17	20	668,639	7.9	37,199	17	20	11,294	17	20	20	20	

Version TONNN2010-1.06	<b>get FWD Data</b>
<b>Previous Days</b>	
Max. Temp. °F	33.07
Min. Temp. °F	35.07
Avg. Temp. °F	34.07
<b>HMA Thickness (inches)</b>	<b>Fill</b>
4	
<b>Base Thickness (inches)</b>	<b>Fill</b>
10	
<b>Design ESALs</b>	<b>Fill</b>
1,000,000	
<b>County</b>	
Morrison	<input type="button" value="▲"/>
Mower	<input type="button" value="▼"/>
Murray	<input type="button" value="▶"/>
<b>Run TONNN2010</b>	<b>Fill</b>
<b>Begin Overlay Design</b>	
<b>Soil Type</b>	<b>Fill</b>
Plastic	<input type="button" value="▶"/>
<b>Traffic Category</b>	<b>Fill</b>
2 - ADT 300-1000	<input type="button" value="▶"/>
HAIDI 25-50	<input type="button" value="▶"/>
<b>Conv/Full Depth</b>	<b>Conventional</b>
<b>HIDE STATE AID</b>	
<i>This button will estimate the number of ESALs that will result in a rating of 10-tonns.</i>	
<b>Estimate Number of ESALs for 10-Ton Rating</b>	
<i>This button will estimate the number of ESALs that will result in a rating of 10-tonns.</i>	
<b>Make KML File</b>	

Version TONN2010-1.06	<b>Get FWD Data</b>	<b>Segments (20 max)</b>										
6/20/2019		100.4										
Roadway	From Station	State	State	To Station	District	Control Section	Lane	Direction	Lat. and Long.	State		
MN Road	0.100	Aid	Aid	3.200	0	Aid	US 71 NE	0	Increasing	48°09'5,-93.937		
<b>Previous Day's</b>	<b>Segments (20 max)</b>											
Max. Temp °F	57.03											
Min. Temp °F	59.03											
Avg. Temp °F	58.03											
<b>HMA Thickness (inches)</b>	<b>85% Percentile</b>											
4.5	Fill	0.10	4.5	P	2	8.0	1,000,000	23.3	GE	Capacity, Tons		
0.20	Fill	0.20	4.5	P	2	8.0	1,000,000	22.9	GE	Capacity, Tons		
4.5	Fill	0.30	4.5	P	2	8.0	1,000,000	17.8	GE	Capacity, Tons		
4.5	Fill	0.40	4.5	P	2	8.0	1,000,000	14.4	GE	Capacity, Tons		
4.5	Fill	0.50	4.5	P	2	8.0	1,000,000	16.7	GE	Capacity, Tons		
4.5	Fill	0.60	4.5	P	2	8.0	1,000,000	23.2	GE	Capacity, Tons		
4.5	Fill	0.70	4.5	P	2	8.0	1,000,000	15.8	GE	Capacity, Tons		
4.5	Fill	0.80	4.5	P	2	8.0	1,000,000	22.5	GE	Capacity, Tons		
4.5	Fill	0.90	4.5	P	2	8.0	1,000,000	20.9	GE	Capacity, Tons		
4.5	Fill	1.01	4.5	P	2	8.0	1,000,000	24.3	GE	Capacity, Tons		
4.5	Fill	1.10	4.5	P	2	8.0	1,000,000	21.9	GE	Capacity, Tons		
4.5	Fill	1.20	4.5	P	2	8.0	1,000,000	22.1	GE	Capacity, Tons		
4.5	Fill	1.30	4.5	P	2	8.0	1,000,000	21.0	GE	Capacity, Tons		
4.5	Fill	1.40	4.5	P	2	8.0	1,000,000	23.6	GE	Capacity, Tons		
4.5	Fill	1.50	4.5	P	2	8.0	1,000,000	23.2	GE	Capacity, Tons		
4.5	Fill	1.60	4.5	P	2	8.0	1,000,000	23.7	GE	Capacity, Tons		
4.5	Fill	1.70	4.5	P	2	8.0	1,000,000	22.7	GE	Capacity, Tons		
4.5	Fill	1.80	4.5	P	2	8.0	1,000,000	23.8	GE	Capacity, Tons		
4.5	Fill	1.90	4.5	P	2	8.0	1,000,000	26.8	GE	Capacity, Tons		
4.5	Fill	2.00	4.5	P	2	8.0	1,000,000	24.9	GE	Capacity, Tons		
4.5	Fill	2.10	4.5	P	2	8.0	1,000,000	25.1	GE	Capacity, Tons		
4.5	Fill	2.20	4.5	P	2	8.0	1,000,000	25.5	GE	Capacity, Tons		
4.5	Fill	2.30	4.5	P	2	8.0	1,000,000	22.7	GE	Capacity, Tons		
4.5	Fill	2.40	4.5	P	2	8.0	1,000,000	23.5	GE	Capacity, Tons		
4.5	Fill	2.50	4.5	P	2	8.0	1,000,000	24.9	GE	Capacity, Tons		
4.5	Fill	2.60	4.5	P	2	8.0	1,000,000	23.9	GE	Capacity, Tons		
4.5	Fill	2.70	4.5	P	2	8.0	1,000,000	22.4	GE	Capacity, Tons		
4.5	Fill	2.80	4.5	P	2	8.0	1,000,000	25.1	GE	Capacity, Tons		
4.5	Fill	2.90	4.5	P	2	8.0	1,000,000	26.6	GE	Capacity, Tons		
4.5	Fill	3.00	4.5	P	2	8.0	1,000,000	22.8	GE	Capacity, Tons		
4.5	Fill	3.11	4.5	P	2	8.0	1,000,000	22.0	GE	Capacity, Tons		
4.5	Fill	3.20	4.5	P	2	8.0	1,000,000	23.1	GE	Capacity, Tons		
<b>Begin Overlay Design</b>												
<b>Traffic Category</b>												
2 - ADT 500-1000 HCADT 25-50	►	<b>Fill</b>										
CONV/FUL Depth	Conventional	►										
This button will estimate the number of ESALs that will result in a rating of 10-ton.											<b>Estimate Number of ESALs for 10-Ton Rating</b>	
											<b>Make KML File</b>	

Test Date	10/13/2018
Roadway	TH835B Waldorf
Station	0.03 0.10 0.20 0.30 0.40 0.50 0.60 0.70 0.80 0.90 1.00 1.10 1.20 1.30 1.40 1.50 1.60 1.70 1.80 1.90 2.00 2.10 2.20 2.30 2.40 2.50 2.60 2.70 2.80 2.90 3.00 3.10 3.20

State	Control Section		Lane		Direction		Lat. and Long.		State Aid
	Aid	TH83	0	Increasing		43.9354, -93.7023			
GE	Capacity, Tons	Moduli Statistics						#1 Defl. (mils)	R-value
		HMA (72° F)	Base	Subgrade					
20.0	<b>10.1</b>	1,358,484	34,095	<b>11,108</b>	2,492	11.0	19	<b>14</b>	
21.8	11.6	265,780	13,232	2,492	1.9	1.9	5		
21.0	<b>TONN2010</b>								
GE	Capacity, Tons	HMA (72° F)	Base	Subgrade				S.A.	R-Value
24.4	12.8	1,688,979	50,419	13,069	8	8	24		
22.8	13.2	1,238,329	9,556	11	11	16			
24.8	13.8	1,887,483	12,564	8	8	22			
22.4	10.4	1,268,604	24,949	9,536	13	16			
22.7	10.7	1,277,383	26,116	13,201	11	11	24		
22.2	12.7	1,207,388	77,640	9,050	9	15			
23.2	12.5	1,529,093	37,225	9,881	11	17			
23.1	12.1	1,590,304	32,989	11,576	11	20			
24.7	14.5	1,590,258	56,749	10,294	10	18			
24.3	13.0	1,843,584	11,851	7	7	21			
21.3	12.7	1,698,773	35,715	16,390	9	31			
21.1	13.6	1,734,056	43,617	12,563	9	22			
19.7	11.8	1,309,018	34,360	16,728	9	32			
21.0	10.6	1,397,793	24,125	12,388	11	22			
20.1	9.8	1,398,764	18,928	14,442	11	27			
21.3	13.1	1,252,126	49,032	9,674	10	16			
21.1	11.2	1,420,210	27,786	14,010	10	26			
22.3	12.8	1,256,241	46,072	8,047	11	13			
21.2	10.6	1,391,681	24,283	9,448	12	16			
20.7	11.6	1,091,473	37,774	8,939	12	15			
21.7	11.3	1,567,930	26,492	13,690	10	25			
19.7	10.3	1,122,342	26,065	10,012	12	17			
22.3	12.8	1,438,323	41,043	13,128	10	24			
20.6	9.1	1,066,299	18,535	9,518	14	16			
20.3	10.2	999,233	27,281	8,260	14	13			
22.1	10.8	1,596,848	22,702	13,339	11	24			
22.2	11.6	1,073,211	38,733	6,780	14	11			
19.5	8.9	930,747	19,468	8,151	15	13			
21.9	11.8	1,293,919	35,588	8,594	12	14			
19.7	9.4	929,004	22,512	11,939	14	21			
22.6	12.7	1,504,296	40,070	9,242	11	15			
25.6	12.9	1,363,241	8,361	10	14				

Test Date				Pave. Temp.		Segments (20 max)	
10/13/2018				44.8		<i>J</i>	
Roadway		From Station		State		To Station	
TH109 WB Delaware		Aid	Aid	Aid	Aid	3,600	0
Station	HMA Thickness (inches)	Soil Type	Traffic Cat.	Base Thickness	ESALs	GE	Capacity, Tons
0.01	5.0	P	2	18.0	1,000,000	16.4	10.4
0.10	5.0	P	2	18.0	1,000,000	21.4	12.5
0.20	5.0	P	2	18.0	1,000,000	23.1	12.9
0.30	5.0	P	2	18.0	1,000,000	20.7	12.8
0.40	5.0	P	2	18.0	1,000,000	19.1	9.6
0.50	5.0	P	2	18.0	1,000,000	17.4	8.8
0.60	5.0	P	2	18.0	1,000,000	19.4	10.6
0.70	5.0	P	2	18.0	1,000,000	17.0	9.8
0.80	5.0	P	2	18.0	1,000,000	14.4	8.0
0.90	5.0	P	2	18.0	1,000,000	20.0	10.9
1.00	5.0	P	2	18.0	1,000,000	19.0	12.2
1.10	5.0	P	2	18.0	1,000,000	18.1	9.2
1.20	5.0	P	2	18.0	1,000,000	20.2	8.7
1.30	5.0	P	2	18.0	1,000,000	21.1	9.9
1.40	5.0	P	2	18.0	1,000,000	20.1	8.5
1.50	5.0	P	2	18.0	1,000,000	22.8	13.0
1.60	5.0	P	2	18.0	1,000,000	15.5	9.0
1.70	5.0	P	2	18.0	1,000,000	17.4	8.0
1.80	5.0	P	2	18.0	1,000,000	19.6	10.0
1.90	5.0	P	2	18.0	1,000,000	20.3	10.9
2.00	5.0	P	2	18.0	1,000,000	22.1	11.2
2.10	5.0	P	2	18.0	1,000,000	19.4	9.0
2.20	5.0	P	2	18.0	1,000,000	18.9	9.5
2.30	5.0	P	2	18.0	1,000,000	17.9	8.4
2.40	5.0	P	2	18.0	1,000,000	22.6	10.5
2.50	5.0	P	2	18.0	1,000,000	22.0	9.9
2.60	5.0	P	2	18.0	1,000,000	13.2	6.8
2.70	5.0	P	2	18.0	1,000,000	20.8	8.5
2.80	5.0	P	2	18.0	1,000,000	18.6	9.5
2.90	5.0	P	2	18.0	1,000,000	21.0	10.4
3.00	5.0	P	2	18.0	1,000,000	18.2	9.8
3.10	5.0	P	2	18.0	1,000,000	19.2	11.5
3.20	5.0	P	2	18.0	1,000,000	20.3	9.4
3.31	5.0	P	2	18.0	1,000,000	19.3	9.1
3.40	5.0	P	2	18.0	1,000,000	18.2	11.3
3.50	5.0	P	2	18.0	1,000,000	17.7	11.8
3.60	5.0	P	2	18.0	1,000,000	17.6	10.3

Version TONN2010-1.06	Get FWD Data	Begin Overlay Design	Soil Type ▾	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
Get FWD Data	Run TONN2010	Begin Overlay Design	Plastic	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
Previous Day's Max. Temp °F	34.33	Run TONN2010	Cohesive	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
Min. Temp °F	36.33	Begin Overlay Design	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
Avg. Temp °F	35.33	Soil Category	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
HCADT 25-50	►	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2 - ADT 500-1000	►	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2.00	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2.10	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2.20	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2.30	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2.40	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2.50	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2.60	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2.70	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2.80	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
2.90	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
3.00	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
3.10	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
3.20	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
3.31	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
3.40	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
3.50	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File
3.60	5.0	Soil Type ▾	Conventional	Fill	Hide State Aid	Estimate Number of ESALs for 10-Ton Rating	Make KML File

This button will estimate the number of ESALs that will result in a rating of 10-ton.

Segment (20 max)											
Test Date	Pave Temp.			Segments (20 max)							
10/11/2018	30.2										
Roadway	From Station	State	To Station	District	State	238 SB beg at hwy	ane	Direction	Lat. and Long.	State	
238 SB right wheel lane	0.100	Aid	4.000	0		238 SB beg at hwy	0	Increasing	45.729, -94.59	Aid	
Max. Temp. °F	34										
Min. Temp. °F	38										
Avg. Temp. °F	36										
Station	HMA Thickness	Soil Traffic	Base	Thickness	ESALs	GE	TONN2010	Moduli	#1 Defl.	R-Value	
0.10	4.0	P	3	8.0	1,000,000	22.2	13.4	18,704		37	
0.20	4.0	P	3	8.0	1,000,000	17.3	9.2	10,433,730	14,713	27	
0.30	4.0	P	3	8.0	1,000,000	17.1	10.6	1,008,897	85,574	33	
0.40	4.0	P	3	8.0	1,000,000	16.2	10.3	818,438	84,587	32	
0.50	4.0	P	3	8.0	1,000,000	17.6	9.0	883,418	50,839	24	
0.60	4.0	P	3	8.0	1,000,000	16.2	11.3	931,539	19,417	39	
0.70	4.0	P	3	8.0	1,000,000	18.8	9.5	883,576	10,369	18	
0.80	4.0	P	3	8.0	1,000,000	15.1	7.9	759,882	12,426	22	
0.90	4.0	P	3	8.0	1,000,000	16.7	7.9	681,353	59,206	18	
1.00	4.0	P	3	8.0	1,000,000	14.0	8.8	720,619	28,696	30	
1.10	4.0	P	3	8.0	1,000,000	15.1	8.6	700,552	45,711	25	
1.20	4.0	P	3	8.0	1,000,000	15.7	9.1	838,126	37,792	29	
1.30	4.0	P	3	8.0	1,000,000	15.0	8.6	746,728	38,669	16	
1.40	4.0	P	3	8.0	1,000,000	18.7	10.1	917,238	9,082	15	
1.50	4.0	P	3	8.0	1,000,000	19.0	9.3	904,482	97,769	16	
1.60	4.0	P	3	8.0	1,000,000	18.6	9.3	1,168,207	53,439	14	
1.70	4.0	P	3	8.0	1,000,000	18.5	10.1	1,256,945	62,414	12	
1.80	4.0	P	3	8.0	1,000,000	17.0	9.3	810,518	65,681	14	
1.90	4.0	P	3	8.0	1,000,000	17.5	10.7	1,202,454	72,654	27	
2.00	4.0	P	3	8.0	1,000,000	15.9	9.0	735,325	67,982	17	
2.10	4.0	P	3	8.0	1,000,000	20.3	10.2		60,303	25	
2.20	4.0	P	3	8.0	1,000,000	17.5	9.2	847,299	57,010	15	
2.30	4.0	P	3	8.0	1,000,000	16.7	8.3	673,554	50,080	17	
2.40	4.0	P	3	8.0	1,000,000	14.8	8.8	409,163	81,897	21	
2.50	4.0	P	3	8.0	1,000,000	10.2	10.5	340,690	94,099	24	
2.60	4.0	P	3	8.0	1,000,000	15.9	10.1	686,064	86,680	22	
2.70	4.0	P	3	8.0	1,000,000	15.9	9.8	741,443	73,969	31	
2.80	4.0	P	3	8.0	1,000,000	16.5	10.4	600,121	116,565	29	
2.90	4.0	P	3	8.0	1,000,000	19.6	10.5	753,715	128,884	23	
3.00	4.0	P	3	8.0	1,000,000	21.2	10.2	864,600	121,645	18	
3.10	4.0	P	3	8.0	1,000,000	17.0	9.0	619,230	72,656	22	
3.20	4.0	P	3	8.0	1,000,000	18.8	9.5	850,666	106,385	23	
3.30	4.0	P	3	8.0	1,000,000	15.2	8.7	760,743	13,004	29	
3.40	4.0	P	3	8.0	1,000,000	17.3	8.3	502,753	40,683	23	
3.50	4.0	P	3	8.0	1,000,000	18.9	8.9	613,941	14,133	16	
3.60	4.0	P	3	8.0	1,000,000	19.6	9.2	605,445	10,639	18	
3.70	4.0	P	3	8.0	1,000,000	23.3	9.3	988,967	9,695	16	
3.80	4.0	P	3	8.0	1,000,000	18.2	9.1	599,896	89,233	21	
3.90	4.0	P	3	8.0	1,000,000	17.0	9.7	610,802	11,808	26	
4.00	4.0	P	3	8.0	1,000,000	14.2	8.3	673,147	14,267	17	

## **APPENDIX D: SIEVE ANALYSIS AND CHEMICAL EXTRACTION**



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S1


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
	St. Paul MN		
Job No:	27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S1	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH01	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	96
Location		1/2in (12.5mm)	94
Date Submitted	6/17/2020	3/8in (9.5mm)	89
		No.4 (4.75mm)	79
		No.8 (2.36mm)	65
		No.10 (2.0mm)	61
		No.16 (1.18mm)	50
		No.30 (600µm)	38
		No.40 (425µm)	32
		No.50 (300µm)	24
		No.100 (150µm)	10
		No.200 (75µm)	6.3

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	0.9	

## Chart



## Comments

N/A



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S2


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
St. Paul MN			
Job No:	27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S2	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH09	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	100
Location		1/2in (12.5mm)	93
Date Submitted	6/17/2020	3/8in (9.5mm)	90
		No.4 (4.75mm)	81
		No.8 (2.36mm)	72
		No.10 (2.0mm)	69
		No.16 (1.18mm)	60
		No.30 (600µm)	45
		No.40 (425µm)	35
		No.50 (300µm)	25
		No.100 (150µm)	11
		No.200 (75µm)	6.0

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	1.4	

## Chart



## Comments

N/A



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S3


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
Job No:	St. Paul MN 27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S3	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH11	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	97
Location		1/2in (12.5mm)	91
Date Submitted	6/17/2020	3/8in (9.5mm)	88
		No.4 (4.75mm)	79
		No.8 (2.36mm)	71
		No.10 (2.0mm)	68
		No.16 (1.18mm)	60
		No.30 (600µm)	47
		No.40 (425µm)	39
		No.50 (300µm)	31
		No.100 (150µm)	17
		No.200 (75µm)	9.1

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	2.8	

## Chart



## Comments

N/A



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S4


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
	St. Paul MN		
Job No:	27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S4	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH32	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	99
Location		1/2in (12.5mm)	93
Date Submitted	6/17/2020	3/8in (9.5mm)	90
		No.4 (4.75mm)	78
		No.8 (2.36mm)	65
		No.10 (2.0mm)	61
		No.16 (1.18mm)	53
		No.30 (600µm)	42
		No.40 (425µm)	34
		No.50 (300µm)	24
		No.100 (150µm)	9
		No.200 (75µm)	6.2

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	1.5	

## Chart



## Comments

N/A



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S5


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
Job No:	St. Paul MN 27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S5	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH55	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	100
Location		1/2in (12.5mm)	96
Date Submitted	6/17/2020	3/8in (9.5mm)	93
		No.4 (4.75mm)	83
		No.8 (2.36mm)	70
		No.10 (2.0mm)	66
		No.16 (1.18mm)	55
		No.30 (600µm)	38
		No.40 (425µm)	30
		No.50 (300µm)	21
		No.100 (150µm)	11
		No.200 (75µm)	8.1

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	2.8	

## Chart



## Comments

N/A



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S6


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
	St. Paul MN		
Job No:	27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S6	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH59	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	94
Location		1/2in (12.5mm)	87
Date Submitted	6/17/2020	3/8in (9.5mm)	83
		No.4 (4.75mm)	72
		No.8 (2.36mm)	60
		No.10 (2.0mm)	57
		No.16 (1.18mm)	47
		No.30 (600µm)	31
		No.40 (425µm)	21
		No.50 (300µm)	14
		No.100 (150µm)	9
		No.200 (75µm)	6.9

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	0.5	

## Chart



## Comments

N/A



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S7


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
Job No:	St. Paul MN 27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S7	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH62	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	99
Location		1/2in (12.5mm)	95
Date Submitted	6/18/2020	3/8in (9.5mm)	93
		No.4 (4.75mm)	84
		No.8 (2.36mm)	73
		No.10 (2.0mm)	70
		No.16 (1.18mm)	59
		No.30 (600µm)	37
		No.40 (425µm)	25
		No.50 (300µm)	17
		No.100 (150µm)	10
		No.200 (75µm)	7.4

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	1.7	

## Chart



## Comments

N/A



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S8


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
	St. Paul MN		
Job No:	27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S8	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH71	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	100
Location		1/2in (12.5mm)	95
Date Submitted	6/18/2020	3/8in (9.5mm)	92
		No.4 (4.75mm)	82
		No.8 (2.36mm)	72
		No.10 (2.0mm)	69
		No.16 (1.18mm)	60
		No.30 (600µm)	45
		No.40 (425µm)	35
		No.50 (300µm)	27
		No.100 (150µm)	13
		No.200 (75µm)	7.1

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	1.7	

## Chart



## Comments

N/A



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S9


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
	St. Paul MN		
Job No:	27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S9	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH83	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	100
Location		1/2in (12.5mm)	91
Date Submitted	6/18/2020	3/8in (9.5mm)	83
		No.4 (4.75mm)	71
		No.8 (2.36mm)	60
		No.10 (2.0mm)	57
		No.16 (1.18mm)	50
		No.30 (600µm)	39
		No.40 (425µm)	33
		No.50 (300µm)	28
		No.100 (150µm)	18
		No.200 (75µm)	10.7

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	0.9	

## Chart



## Comments

N/A



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S10


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
	St. Paul MN		
Job No:	27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S10	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH109	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	99
Location		1/2in (12.5mm)	94
Date Submitted	6/18/2020	3/8in (9.5mm)	88
		No.4 (4.75mm)	76
		No.8 (2.36mm)	68
		No.10 (2.0mm)	66
		No.16 (1.18mm)	61
		No.30 (600µm)	53
		No.40 (425µm)	45
		No.50 (300µm)	37
		No.100 (150µm)	17
		No.200 (75µm)	8.2

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	1.7	

## Chart



## Comments

N/A



American Engineering Testing, Inc.  
St. Paul Albertville  
550 Cleveland Ave N 5548 Barthel Ind Dr, Ste 500  
St. Paul, MN 55114 Albertville, MN 55301  
(651) 659-9001 (763) 428-5573  
Toll Free: (800) 972-6364 www.amengtest.com

# Material Test Report

Report No: MAT:20-11563-S11


Client:	MINNESOTA DEPT OF TRANSPORTATION	CC:	Draft Report - Subject to change pending final review
Project:	DCP FDR Tests		Date of Issue: 6/18/2020
	St. Paul MN		
Job No:	27-20000		

Sample Details		Particle Size Distribution	
Sample ID	20-11563-S11	Method:	MnDOT 1202, MnDOT 1203
Field Sample ID	TH238	Date Tested:	
Date Sampled		Tested By:	
Source			
Material			
Specification	Gradation	Sieve Size	% Passing
Sampling Method		3/4in (19.0mm)	99
Location		1/2in (12.5mm)	93
Date Submitted	6/18/2020	3/8in (9.5mm)	89
		No.4 (4.75mm)	76
		No.8 (2.36mm)	63
		No.10 (2.0mm)	59
		No.16 (1.18mm)	50
		No.30 (600µm)	34
		No.40 (425µm)	26
		No.50 (300µm)	18
		No.100 (150µm)	10
		No.200 (75µm)	6.5

## Other Test Results

Description	Method	Result	Limits
Granular Ratio	MnDOT 1202, MnDOT 1203		
Asphalt Content (of Total Sample) (%)	MnDOT 1852	3.2	

## Chart



## Comments

N/A