
Louisiana Transportation Research Center

Final Report 658

**Retrofit of Existing Statewide Louisiana Safety
Walk Bridge Barrier Railing Systems**

by

William F. Williams, P.E. (TX)
Sana Moran, EIT
Wanda L. Menges
Bill L. Griffith
William Schroeder
Darrell L. Kuhn, P.E.

Texas A&M Transportation Institute



4101 Gourrier Avenue | Baton Rouge, Louisiana 70808
(225) 767-9131 | (225) 767-9108 fax | www.ltrc.lsu.edu

TECHNICAL REPORT STANDARD PAGE

1. Title and Subtitle
**Retrofit of Existing Statewide Louisiana Safety Walk
Bridge Barrier Railing Systems**
2. Author(s)
William F. Williams, Wanda L. Menges, Bill L. Griffith,
William Schroeder, Sana Moran, and Darrell L. Kuhn
3. Performing Organization Name and Address
Texas A&M Transportation Institute
The Texas A&M University System
College Station, TX 77843
4. Sponsoring Agency Name and Address
Louisiana Department of Transportation and Development
P.O. Box 94245
Baton Rouge, LA 70804-9245
5. Report No.
FHWA/LA.17/658
6. Report Date
January 2022
7. Performing Organization Code
LTRC Project Number: 16-1ST
SIO Number: DOTLT1000099
8. Type of Report and Period Covered
Technical Report
June 2016 – August 2021
9. No. of Pages
331
10. Supplementary Notes
Conducted in Cooperation with the U.S. Department of Transportation, Federal Highway
Administration
11. Distribution Statement
Unrestricted. This document is available through the National Technical Information Service,
Springfield, VA 21161.
12. Key Words
Longitudinal barrier; bridge rail; guardrail; retrofit; crash testing; MASH; roadside safety
13. Abstract

Louisiana has approximately 200 miles of vintage 1960s concrete safety walk bridge rail systems currently in use on bridges throughout Louisiana. Many of these systems do not meet the current crash performance requirements of the American Association of State Highway and Transportation Officials *Manual for Assessing Safety Hardware* Second Edition (MASH) specifications for Test Level 3 (TL-3).

Researchers at the Texas A&M Transportation Institute (TTI) have conducted a full literature review of various bridge railing retrofits that have been used throughout the United States and abroad. A literature review search was performed using the Transportation Research Information Services database to document the pertinent findings of others on this proposed study. TTI researchers also obtained all available design information and details of safety walk barriers used throughout Louisiana. Two of the most common types of vintage bridge railings with safety walks were selected for further analysis and details. These included a concrete post and rail system with a sidewalk and a solid concrete parapet

system with a sidewalk. Retrofits were developed that can be used on both common rail types used in Louisiana.

Two full-scale crash tests were performed on the retrofit design anchored to the concrete post and rail system. During MASH Test 3-10 on the Louisiana Retrofit post and beam bridge rail with safety walk Option 1, the vehicle experienced occupant ridedown accelerations above the limit of 20.49 g as specified in MASH.

The bridge rail was redesigned, and MASH Tests 3-10 and 3-11 were repeated. The Louisiana Retrofit post and beam bridge rail with safety walk Option 2 met the requirements for MASH TL-3 longitudinal barriers.

Project Review Committee

Each research project will have an advisory committee appointed by the LTRC Director. The Project Review Committee is responsible for assisting the LTRC Administrator or Manager in the development of acceptable research problem statements, requests for proposals, review of research proposals, oversight of approved research projects, and implementation of findings.

LTRC appreciates the dedication of the following Project Review Committee Members in guiding this research study to fruition.

LTRC Administrator/Manager

Walid Alaywan, Ph.D., P.E.

Senior Structures Research Engineer/Project Research Manager

Members

Kurt Brauner, P.E.

David Miller, P.E.

Dan Magri, P.E.

Art Aguirre, P.E.

Steven Mazur, P.E.

Directorate Implementation Sponsor

Christopher P. Knotts, P.E.

DOTD Chief Engineer

Retrofit of Existing Statewide Louisiana Safety Walk Bridge Barrier Railing Systems

By

William F. Williams, P.E. (TX)

Sana Moran, EIT

Wanda L. Menges

Bill L. Griffith

William Schroeder

Darrell L. Kuhn, P.E.

Texas A&M Transportation Institute

The Texas A&M University System

College Station, TX 77843

LTRC Project No. 16-1ST

SIO No. DOTLT1000099

conducted for

Louisiana Department of Transportation and Development

Louisiana Transportation Research Center

The contents of this report reflect the views of the author/principal investigator, who is responsible for the facts and the accuracy of the data presented herein.

The contents do not necessarily reflect the views or policies of the Louisiana Department of Transportation and Development, the Federal Highway Administration, or the Louisiana Transportation Research Center. This report does not constitute a standard, specification, or regulation.

January 2022

Abstract

Louisiana has approximately 200 miles of vintage 1960s concrete safety walk bridge rail systems currently in use on bridges throughout Louisiana. Many of these systems do not meet the current crash performance requirements of the American Association of State Highways and Transportation Officials *Manual for Assessing Safety Hardware* Second Edition (MASH) specifications for Test Level 3 (TL-3).

Researchers at the Texas A&M Transportation Institute (TTI) have conducted a full literature review of various bridge railing retrofits that have been used throughout the United States and abroad. A literature review search was performed using the Transportation Research Information Services database to document the pertinent findings of others on this proposed study. TTI researchers also obtained all available design information and details of safety walk barriers used throughout Louisiana. Two of the most common types of vintage bridge railings with safety walks were selected for further analysis and details. These included a concrete post and rail system with a sidewalk and a solid concrete parapet system with a sidewalk. Retrofits were developed that can be used on both of the common rail types used in Louisiana.

Two full-scale crash tests were performed on the retrofit design anchored to the concrete post and rail system. During MASH Test 3-10 on the Louisiana Retrofit post and beam bridge rail with safety walk Option 1, the vehicle experienced occupant ridedown accelerations above the limit of 20.49 g as specified in MASH.

The bridge rail was redesigned, and MASH Tests 3-10 and 3-11 were repeated. The Louisiana Retrofit post and beam bridge rail with safety walk Option 2 met the requirements for MASH TL-3 longitudinal barriers.

Acknowledgments

The authors would like to thank Walid Alaywan, Ph.D., senior structures research engineer at the Louisiana Transportation Research Center, Kurt Brauner, bridge engineer manager at the Louisiana Department of Transportation and Development (DOTD), and Steve Mazur, bridge engineer at DOTD. These gentlemen contributed greatly to the success of this project. Their assistance and involvement in this project are greatly appreciated.

Implementation Statement¹

The retrofit bridge rail as tested herein met all the strength and performance requirements for MASH TL-3 specifications. This retrofit bridge rail is recommended for implementation on Louisiana post and beam and solid concrete barriers with 10 in. high or less by 18 in. wide or less safety walks.

For additional information, please refer to the information provided in this report.

¹ The opinions/interpretations identified/expressed in this section of the report are outside the scope of TTI Proving Ground's A2LA Accreditation.

Table of Contents

Technical Report Standard Page	1
Project Review Committee	3
LTRC Administrator/Manager	3
Members	3
Directorate Implementation Sponsor	3
MASH TL-3 Evaluation of Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk	4
Abstract	5
Acknowledgments.....	6
Implementation Statement	7
Table of Contents	8
List of Tables.....	11
List of Figures.....	13
Introduction.....	18
Task 1 – Literature Review	19
Design and Full Scale Testing of Retrofit Bridge Rail for 24.8 Miles Long Southbound Causeway Bridge, New Orleans, Louisiana– Option A.....	19
Design and Full Scale Testing of Retrofit Bridge Rail for 24.8 Miles Long Southbound Causeway Bridge, New Orleans, Louisiana– Option B1	30
Task 2 – Review of DOTD Bridge Rail Database	47
Task 7 – Full Scale Testing of Retrofit Bridge Rail Option 1, Tested October 2018.....	50
Test Requirements and Evaluation Criteria	51
Crash Tests Performed	51
Evaluation Criteria	52
Test Conditions	54
Test Facility.....	54
Vehicle Tow and Guidance System.....	54
Data Acquisition Systems	55
MASH TL-3 Testing of Louisiana Retrofit post and beam bridge rail with safety walk Option 1	58
Test Installation Details.....	58

MASH Test 3-11 (Crash Test No. 606861-1)	60
MASH Test 3-10 (Crash Test No. 606861-2)	72
Discussion of Results for MASH TL-3 Tests on Louisiana Retrofit post and beam bridge rail with safety walk Option 1	83
Design and Strength Analysis of the Louisiana Retrofit post and beam bridge rail with safety walk Option 2	86
MASH TL-3 Testing of Retrofit post and beam bridge rail with safety walk Option 2	94
Test Installation Details	94
MASH Test 3-11 (Crash Test No. 606861-3)	96
MASH Test 3-10 (Crash Test No. 606861-4)	107
Discussion of Results for MASH TL-3 Tests on Louisiana Retrofit post and beam bridge rail with safety walk Option 2	118
Developing Retrofitting Methods and Procedures for Single Bridge Rail Design	120
Summary of Results of Full-Scale Crash Testing	120
Installation of MASH TL-3 of Option 2 Retrofit Bridge Rail	120
Installation Procedure	121
Material Specifications for MASH TL-3 Retrofit Bridge Rail	128
Preliminary Transition Details for New Retrofit Bridge Rail Design for Concrete Barriers with Safety Walks	129
Conclusions	135
Recommendations	137
Acronyms, Abbreviations, and Symbols	138
References	140
Appendix A. DOTD Bridge Rails	141
Appendix B. Details of Louisiana Retrofit Post and Beam with Safety Walk for Tests 606861-1&2	162
Appendix C. Supporting Certification Documents for Test No. 606861-1&2	172
Appendix D. MASH Test 3-11 (Crash Test No. 606861-1)	190
Appendix E. MASH Test 3-10 (Crash Test No. 606861-2)	199
Appendix F. Strength Analysis of DOTD Retrofit Bridge Rail System	209
Appendix G. Details of Louisiana Retrofit Post and Beam with Safety Walk Option 2 for Tests 606861-3&4	231
Appendix H. Strength Analysis for Retrofit Bridge Rail Anchored to Solid Concrete Parapet	243
Appendix I. Supporting Certification Documents for Test No. 606861-3&4	267

Appendix J. MASH Test 3-11 (Crash Test No. 606861-3)	315
Appendix K. MASH Test 3-10 (Crash Test No. 606861-4).....	324

List of Tables

Table 1. Performance evaluation summary for MASH Test 4-12 on Option A Bridge Rail.....	27
Table 2. Performance evaluation summary for MASH Test 4-11 on Option A Bridge Rail.....	28
Table 3. Performance evaluation summary for MASH Test 4-10 on Option A Bridge Rail.....	29
Table 4. Performance evaluation summary for MASH test 4-12 (Test No. 690900-GEC7) on Option B1 Bridge Rail.....	42
Table 5. Performance evaluation summary for MASH Test 4-12 (Test No. 690900-GEC7a) on Option B1 Bridge Rail.....	43
Table 6. Performance evaluation summary for MASH Test 4-10 (Test No. 690900-GEC8) on Option B1 Bridge Rail.....	44
Table 7. Performance evaluation summary for MASH Test 4-11 (Test No. 690900-GEC9) on Option B1 Bridge Rail.....	45
Table 8. Test conditions and evaluation criteria specified for MASH TL-3 longitudinal barriers	51
Table 9. Evaluation criteria required for MASH TL-4 longitudinal barriers.....	53
Table 10. Events during Test No. 606861-1.....	63
Table 11. Occupant risk factors for Test No. 606861-1	68
Table 12. Summary of results for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1—Pre-Impact Information.....	70
Table 13. Summary of results for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1—Post-Impact Information	71
Table 14. Events during Test No. 606861-2.....	74
Table 15. Occupant risk factors for Test No. 606861-2	79
Table 16. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1—Pre-Impact Information.....	81
Table 17. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1—Post-Impact Information	82
Table 18. Performance evaluation summary for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1.....	84
Table 19. Performance evaluation summary for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1.....	85
Table 20. Events during Test No. 606861-3.....	98

Table 21. Occupant risk factors for Test No. 606861-3	103
Table 22. Summary of results for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2—Pre-Impact Information	105
Table 23. Summary of results for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2—Post-Impact Information	106
Table 24. Events during Test No. 606861-4.....	109
Table 25. Occupant risk factors for Test No. 606861-4	114
Table 26. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety walk Option 2—Pre-Impact Information	116
Table 27. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2—Post-Impact Information	117
Table 28. Performance evaluation summary for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2.....	118
Table 29. Performance evaluation summary for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2.....	119
Table 30. Assessment summary for MASH TL-3 Tests on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1	135
Table 31. Assessment summary for MASH TL-3 Tests on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2.....	136

List of Figures

Figure 1. Photo of the old southbound causeway bridge rail.....	20
Figure 2. Option A details	20
Figure 3. Photos of full-scale test installation.....	21
Figure 4. Bridge rail and test vehicle before MASH Test 4-12	22
Figure 5. Bridge rail after MASH Test 4-12	22
Figure 6. Test vehicle after MASH Test 4-12	23
Figure 7. Bridge rail and test vehicle before MASH Test 4-11	23
Figure 8. Bridge rail after MASH Test 4-11	24
Figure 9. Test vehicle after MASH Test 4-11	25
Figure 10. Test vehicle before MASH Test 4-10	25
Figure 11. Bridge rail after MASH Test 4-10	26
Figure 12. Test vehicle after MASH Test 4-10	26
Figure 13. Option B1 details.....	31
Figure 14. Design Option B1 before testing	32
Figure 15. Test vehicle before Test No. 690900-GEC7	33
Figure 16. Rail option B1 after Test No. 690900-GEC7	33
Figure 17. Post 4 after Test No. 690900-GEC7	33
Figure 18. Post 5 after Test No. 690900-GEC7	34
Figure 19. Post 6 and 7 after Test No. 690900-GEC7	34
Figure 20. Post 8 after Test No. 690900-GEC7	34
Figure 21. Test vehicle after Test No. 690900-GEC7.....	35
Figure 22. Test vehicle before Test No. 690900-GEC7a	35
Figure 23. Rail Option B1 positions after Test No. 690900-GEC7a	35
Figure 24. Posts 1 through 5 and rear of post 4 after Test No. GEC7a.....	36
Figure 25. Post 5 after Test No. 690900-GEC7a	36
Figure 26. Post 6 and 7 after Test No. 690900-GEC7a.....	36
Figure 27. Post 8 after Test No. 690900-GEC7a	37
Figure 28. Post 9 through 14 after Test No. 690900-GEC7a.....	37
Figure 29. Test vehicle after Test No. 690900-GEC7a	37
Figure 30. Test vehicle before Test No. 690900-GEC8	38
Figure 31. Rail Option B1 after Test No. 690900-GEC8.....	38
Figure 32. Installation after Test No. 690900-GEC8	39
Figure 33. Test vehicle after Test No. 690900-GEC8.....	39
Figure 34. Test vehicle before Test No. 690900-GEC9	40

Figure 35. Position of vehicle/installation after Test No. 690900-GEC9	40
Figure 36. Post 11 after Test No. 690900-GEC9	40
Figure 37. Post 12 and 13 after Test No. 690900-GEC9	41
Figure 38. Photos after Test No. 690900-GEC9	41
Figure 39. Test vehicle after Test No. 690900-GEC9	41
Figure 40. Interior of test vehicle for Test No. 690900-GEC9	42
Figure 41. Details from drawing SCJ5C-90-24P concrete post and beam	48
Figure 42. Details from drawing SC15A-60-24P solid concrete parapet with aluminum hand rail (to be removed)	49
Figure 43. Retrofit bridge rail Option 1 cross section details	50
Figure 44. Target CIPs for MASH tests on Louisiana Retrofit Post and Beam Bridge Rail With Safety Walk	52
Figure 45. Target CIPs for MASH Test 3-10 on redesigned Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk	52
Figure 46. Target CIP for MASH Test 3-11 on redesigned Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk	52
Figure 47. Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1 prior to testing	59
Figure 48. Joint 2 of Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1 prior to testing	60
Figure 49. Field side of Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1 prior to testing	60
Figure 50. Test vehicle/bridge rail geometrics for Test No. 606861-1	61
Figure 51. Test vehicle prior to Test No. 606861-1	62
Figure 52. Option 1 bridge rail after Test No. 606861-1	64
Figure 53. Damage at joint 2 after Test No. 606861-1	65
Figure 54. Damage at section 3 after Test No. 606861-1	65
Figure 55. Damage on field side of bridge rail after Test No. 606861-1	66
Figure 56. Test vehicle after Test No. 606861-1	67
Figure 57. Interior of test vehicle after Test No. 606861-1	67
Figure 58. Summary of results for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1	69
Figure 59. Test vehicle/bridge rail geometrics for Test No. 606861-2	72
Figure 60. Test vehicle before Test No. 606861-2	73
Figure 61. Option 1 bridge rail after Test No. 606861-2	75
Figure 62. Damage to traffic face of bridge rail after Test No. 606861-2	76
Figure 63. Damage on field side of bridge rail after Test No. 606861-2	77

Figure 64. Test vehicle after Test No. 606861-2.....	78
Figure 65. Interior of test vehicle after Test No. 606861-2.....	78
Figure 66. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1	80
Figure 67. Section view of retrofitted bridge rail system	86
Figure 68. Plan view of failure section 2	88
Figure 69. Plan view of failure section 3	88
Figure 70. Details of the retrofit bridge rail anchored to the solid concrete parapet, sheet 1	91
Figure 71. Details of the retrofit bridge rail anchored to the solid concrete parapet, sheet 2.....	92
Figure 72. Details of the retrofit bridge rail anchored to the solid concrete parapet, sheet 3.....	93
Figure 73. Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2 prior to testing	95
Figure 74. Joint of Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2 prior to testing	96
Figure 75. Test vehicle/bridge rail geometrics for Test No. 606861-3	97
Figure 76. Test vehicle prior to Test No. 606861-3	98
Figure 77. Option 2 bridge rail after Test No. 606861-3	99
Figure 78. Damage to traffic face of bridge rail after Test No. 606861-3	100
Figure 79. Damage on field side of bridge rail after Test No. 606861-3	101
Figure 80. Test vehicle after Test No. 606861-3.....	102
Figure 81. Interior of test vehicle after Test No. 606861-3.....	102
Figure 82. Summary of results for MASH Test 3-11 On Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2	104
Figure 83. Test vehicle/bridge rail geometrics for Test No. 606861-4	107
Figure 84. Test vehicle before Test No. 606861-4	108
Figure 85. Option 2 ridge rail after Test No. 606861-4	110
Figure 86. Damage to traffic face of bridge rail after Test No. 606861-4	111
Figure 87. Damage on field side of bridge rail after Test No. 606861-4.....	112
Figure 88. Test vehicle after Test No. 606861-4.....	113
Figure 89. Interior of test vehicle after Test No. 606861-4.....	113
Figure 90. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety walk Option 2.....	115
Figure 91. Safety walk barrier with concrete post and beam bridge rail	121
Figure 92. Hot dipped A193 B7 ¾-in. diameter Hilti threaded rod.....	122

Figure 93. Hilti HIT-RE500-V3 Adhesive Anchoring System used (anchor bolts installed as per manufacturer’s specifications)	122
Figure 94. Installed L6×4×½ angle support bracket with ¾-in. A193 B7 galvanized threaded rod with Hilti RE500-V3 adhesive	123
Figure 95. Installation of first/top rail element with temporary shoring support.....	124
Figure 96. Installation of lower HSS10×4×¾ rail and bolting to top rail with ⅝-in. diameter B7 threaded rods.....	125
Figure 97. Typical splice assembly of rail prior to adding adjacent rail section.....	126
Figure 98. Front view completed retrofit rail installation.....	126
Figure 99. End view completed retrofit rail installation.....	127
Figure 100. Field side view completed retrofit rail installation.....	127
Figure 101. Current retrofit transition for safety walk barriers received from DOTD ...	130
Figure 102. Proposed transition standard.....	131
Figure 103. New transition concept option 1	132
Figure 104. New transition concept option 2, sheet 1.....	133
Figure 105. New transition concept option 2, sheet 2.....	134
Figure 106. Vehicle properties for Test No. 606861-1	190
Figure 107. Measurement of vehicle vertical CG for Test No. 606861-1	191
Figure 108. Sequential photographs for Test No. 606861-1 (overhead view).....	192
Figure 109. Sequential photographs for Test No. 606861-1 (frontal view).....	193
Figure 110. Sequential photographs for Test No. 606861-1 (rear view).	194
Figure 111. Exterior crush measurements for Test No. 606861-1	195
Figure 112. Occupant compartment measurements for Test No. 606861-1.....	196
Figure 113. Vehicle angular displacements for Test No. 606861-1	197
Figure 114. Vehicle longitudinal accelerometer trace for Test No. 606861-1 (accelerometer located at center of gravity)	197
Figure 115. Vehicle lateral accelerometer trace for Test No. 606861-1 (accelerometer located at center of gravity).....	197
Figure 116. Vehicle vertical accelerometer trace for Test No. 606861-1 (accelerometer located at center of gravity).....	198
Figure 117. Vehicle properties for Test No. 606861-2.....	199
Figure 118. Sequential photographs for Test No. 606861-2 (overhead view).....	200
Figure 119. Sequential photographs for Test No. 606861-2 (frontal view).....	201
Figure 120. Sequential photographs for Test No. 606861-2 (rear view).	203
Figure 121. Exterior crush measurements for Test No. 606861-2	204
Figure 122. Occupant compartment measurements for Test No. 606861-2	205
Figure 123. Vehicle angular displacements for Test No. 606861-2	206

Figure 124. Vehicle longitudinal accelerometer trace for Test No. 606861-2 (accelerometer located at center of gravity)	207
Figure 125. Vehicle lateral accelerometer trace for Test No. 606861-2 (accelerometer located at center of gravity).....	207
Figure 126. Vehicle vertical accelerometer trace for Test No. 606861-2 (accelerometer located at center of gravity).....	208
Figure 127. Vehicle properties for Test No. 606861-3.....	315
Figure 128. Measurement of vehicle vertical CG for Test No. 606861-3	316
Figure 129. Sequential photographs for Test No. 606861-3 (overhead view).....	317
Figure 130. Sequential photographs for Test No. 606861-3 (frontal view).....	318
Figure 131. Sequential photographs for Test No. 606861-3 (rear view).	319
Figure 132. Exterior crush measurements for Test No. 606861-3	320
Figure 133. Occupant compartment measurements for Test No. 606861-3	321
Figure 134. Vehicle angular displacements for Test No. 606861-3	322
Figure 135. Vehicle longitudinal accelerometer trace for Test No. 606861-3 (accelerometer located at center of gravity)	322
Figure 136. Vehicle lateral accelerometer trace for Test No. 606861-3 (accelerometer located at center of gravity).....	323
Figure 137. Vehicle vertical accelerometer trace for Test No. 606861-3 (accelerometer located at center of gravity).....	323
Figure 138. Vehicle properties for Test No. 606861-4.....	324
Figure 139. Sequential photographs for Test No. 606861-4 (overhead view).....	325
Figure 140. Sequential photographs for Test No. 606861-4 (frontal view).....	326
Figure 141. Sequential photographs for Test No. 606861-4 (rear view).	327
Figure 142. Exterior crush measurements for Test No. 606861-4	328
Figure 143. Occupant compartment measurements for Test No. 606861-4	329
Figure 144. Vehicle angular displacements for Test No. 606861-4	330
Figure 145. Vehicle longitudinal accelerometer trace for Test No. 606861-4 (accelerometer located at center of gravity)	330
Figure 146. Vehicle lateral accelerometer trace for Test No. 606861-4 (accelerometer located at center of gravity).....	331
Figure 147. Vehicle vertical accelerometer trace for Test No. 606861-4 (accelerometer located at center of gravity).....	331

Introduction

The purpose of the tests reported herein was to assess the performance of the Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk according to the safety-performance evaluation guidelines included in the American Association of State Highway and Transportation Officials (AASHTO), *Manual for Assessing Safety Hardware, Second Edition* (MASH) [1]. The crash tests were performed in accordance with MASH Test Level 3 (TL-3), which involves an 1100C and a 2270P vehicle impacting the bridge barrier at a target impact speed of 62 mi/h and an impact angle of 25 degrees.

A retrofit bridge rail system that anchors to the top or sides of the existing concrete parapets, and that meets the current safety performance criteria of MASH TL-3, is needed for Louisiana's vintage concrete railings. The retrofit bridge rail must meet the current safety requirements of MASH TL-3 and continue to accommodate use of the concrete safety walk. The existing safety walk areas on these vintage concrete bridges are needed for proper and safe bridge inspection, maintenance or stranded drivers, and for general pedestrian safety. The objective of this project is to develop a retrofit bridge rail design for the two most common types of bridge railing systems that are currently used by Louisiana Department of Transportation and Development (DOTD). This design shall also maintain the safety walk areas and meet the performance requirements of MASH TL-3. The two most common types of barriers are concrete post and beam and solid concrete parapet bridge rails installed with the 18 in. wide by 10 in. high safety walk curb. The purpose of this technical report is to present the retrofit method and the information necessary to fabricate and construct the retrofit bridge rail design which was successfully crash tested in accordance with MASH TL-3 specifications for Task 7A of this project. All material specifications used for the successful crash tested design are also provided in this report.

This report provides details of the Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk, detailed documentation of the crash test results, and an assessment of the performance of the Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk for MASH TL-3 evaluation criteria.

Task 1 – Literature Review

For this project, Texas A&M Transportation Institute (TTI) conducted a full literature review of various bridge railing retrofits that have been used throughout the United States and abroad on safety walk bridge barrier railing systems like those used in Louisiana. As part of this task, TTI performed a literature review search using the TRIS database to document the pertinent findings of others on this proposed study. TTI has performed an extensive search to find all the available research information on the topic of crashworthy rail designs that include the features of the bridge rails that are involved in this study. TTI considered all the available information obtained from this search into the proposed research and design efforts planned for this project.

Several retrofit bridge rail designs were reviewed as part of this task. A few retrofit designs were obtained and considered as part of this review. This section contains a summary of the retrofit designs that utilized a walkway and were tested to MASH specifications. A brief summary of these designs are provided as follows.

Design and Full-Scale Testing of Retrofit Bridge Rail for 24.8 Miles Long Southbound Causeway Bridge, New Orleans, Louisiana–Option A

TTI previously designed and tested a new retrofit bridge rail for the Southbound Causeway Bridge, New Orleans, Louisiana [2]. The purpose of this project was to design and test a retrofit bridge rail for the Southbound Lake Pontchartrain Causeway Bridge in New Orleans, Louisiana. This bridge is approximately 24.8 mi. in length and was constructed in the late 1950s. When the bridge opened it carried two-way traffic from New Orleans to the north shore of Lake Pontchartrain. The previous bridge railing, shown in Figure 1, consists of a 15-in. high concrete parapet mounted on top of a 10-in. high by 18-in. wide concrete curb.

Several retrofit options were developed for this project. A few retrofit designs were selected for full-scale testing. The purpose of the testing reported herein was to assess the performance of the Lake Pontchartrain Causeway Single Rail Bridge Rail Design Option A (25-in.-tall concrete parapet, with steel posts and a single steel railing standing 14 in. above the parapet, atop a 10-in. curb, for a total height of 39 in.) according to the safety-performance evaluation guidelines included in AASHTO MASH Specifications. Details

of the design are shown in Figure 2. A picture of the pre-test installation of the Option A bridge rail design can be found in Figure 3.

Figure 1. Photo of the old southbound causeway bridge rail



Figure 2. Option A details




Figure 3. Photos of full-scale test installation



(a) Traffic face of bridge rail



(b) Steel post



(c) Joint



(d) Field side of bridge rail

Three crash tests were required to evaluate the bridge rail's performance for TL-4 of MASH [1]. These tests involved a 10000S vehicle (22,000-lb. single unit truck), a 2270P vehicle (a 5000-lb. (1/2-ton) quad cab pickup), and a smaller 1100C vehicle (2420-lb. small car). Figure 4 through Figure 12 show the conditions of each of the cars before and after each respective test, as well as the bridge rail damage after each test. Table 1 through Table 3 provide a summary of the MASH criteria evaluation of each individual test.

Figure 4. Bridge rail and test vehicle before MASH Test 4-12



(a) Test vehicle at target impact point



(b) 10000S test vehicle

Figure 5. Bridge rail after MASH Test 4-12



(a) Traffic face of bridge rail



(b) Joint



(c) Impact point



(d) Field side of bridge rail

Figure 6. Test vehicle after MASH Test 4-12



(a) Damage to left side of test vehicle



(b) Damage to right side of test vehicle

Figure 7. Bridge rail and test vehicle before MASH Test 4-11



(a) Test vehicle at target impact point



(b) 2270P test vehicle

Figure 8. Bridge rail after MASH Test 4-11



(a) Traffic face of bridge rail



(b) Traffic side of joint



(c) Field side of bridge rail



(d) Field side of joint

Figure 9. Test vehicle after MASH Test 4-11



(a) Damage to left side of test vehicle

(b) Damage to left front tire

Figure 10. Test vehicle before MASH Test 4-10



(a) Test vehicle at target impact point

(b) 1100C test vehicle

Figure 11. Bridge rail after MASH Test 4-10



(a) Traffic side of bridge rail



(b) Impact point



(c) Joint




(d) Post

Figure 12. Test vehicle after MASH Test 4-10



(a) Damage to front of test vehicle



(b) Damage to left front tire

Table 1. Performance evaluation summary for MASH Test 4-12 on Option A Bridge Rail

Evaluation Factors	Evaluation ² Criteria	Test Results	Assessment
Structural Adequacy	A.	The option A bridge rail contained and redirected the 10000S vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 6.9 in.	Pass
Occupant Risk	D.	Small fragments of concrete broke loose from the parapet, but did not penetrate or show potential for penetrating the occupant compartment, or show hazard for others in the area.	Pass
		No occupant compartment deformation or intrusion was observed.	
	G.	The 10000S vehicle remained upright during and after the collision event.	Pass

² See Table 9 for details of respective evaluation criteria.

Table 2. Performance evaluation summary for MASH Test 4-11 on Option A Bridge Rail

Evaluation Factors	Evaluation ³ Criteria	Test Results	Assessment
Structural Adequacy	A.	The option A bridge rail contained and redirected the 2270P vehicle. The vehicle did not penetrate, underide, or override the bridge rail. Maximum dynamic deflection during the test was 3.1 in.	Pass
Occupant Risk	D.	Small fragments of concrete broke loose from the parapet, but did not penetrate or show potential for penetrating the occupant compartment, or show hazard for others in the area.	Pass
		Maximum occupant compartment deformation was 7.5 in. in the left front firewall area, but there was no penetration.	
	F.	The 2270P vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 18 degrees and 22 degrees.	Pass
	H.	Longitudinal OIV was 17.7 ft/s, and lateral OIV was 26.2 ft/s, which was within the preferred limits.	Pass
	I.	Maximum longitudinal RDA was 11.0 G, and maximum lateral RDA was 9.7 G, which was within the preferred limits.	Pass

³ See Table 9 for details of respective evaluation criteria.

Table 3. Performance evaluation summary for MASH Test 4-10 on Option A Bridge Rail

Evaluation Factors	Evaluation ⁴ Criteria	Test Results	Assessment
Structural Adequacy	A.	The option A bridge rail contained and redirected the 1100C vehicle. The vehicle did not penetrate, underide, or override the bridge rail. Maximum dynamic deflection during the test was 0.74 in.	Pass
Occupant Risk	D.	Small fragments of concrete broke loose from the parapet, but did not penetrate or show potential for penetrating the occupant compartment, or show hazard for others in the area.	Pass
		Maximum occupant compartment deformation was 0.25 in. in the left front kickpanel area, and there was no penetration.	
	F.	The 1100C vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 18 degrees and 10 degrees.	Pass
	H.	Longitudinal OIV was 14.4 ft/s, and lateral OIV was 21.0 ft/s, which was within the preferred limits.	Pass
	I.	Maximum longitudinal RDA was 5.5 G, and maximum lateral RDA was 11.7 G, which was within the preferred limits.	Pass

⁴ See Table 9 for details of respective evaluation criteria.

Design and Full-Scale Testing of Retrofit Bridge Rail for 24.8 Miles Long Southbound Causeway Bridge, New Orleans, Louisiana— Option B1

TTI designed and tested a second retrofit bridge rail for the Southbound Causeway Bridge in New Orleans, LA [2]. This second design (Option B1) was taller than the previous tested Option A design. The test installation was a 160 ft.-6¾ in. long double steel rail on a concrete parapet comprised of four 40-ft. long rail segments with 2¼-in. long gaps at spliced expansion joints between each segment. The 2-tube bridge rail retrofit measured 46 in. in overall height (at the top of the upper rail) above the bridge deck. The top of the lower rail measured 34 in. above the bridge deck. The rail was anchored to the top of a 25-in.-tall steel reinforced concrete sectionalized curb and parapet that replicated the existing structure on the subject Lake Pontchartrain Causeway bridge deck. The curb was 10 in. high and 18 in. wide (walkway area). Additionally, the parapet had a 2¼-in. wide expansion joint overlap gap every 40 ft. along the length of the installation, which coincided with the expansion splice between adjacent spliced rail segments. Details of the Option B1 design is shown in Figure 13.

Figure 14 shows photographs of the installation before full-scale crash testing. Figure 15 through Figure 29 show photographs (before and after) for MASH Test 4-12. Figure 30 through Figure 33 show photographs (before and after) for MASH Test 4-10. Figure 34 through Figure 40 show photographs (before and after) for MASH Test 4-11. These photos show the conditions of the rail installation and test vehicles before and after tests 690900-GEC7, GEC7a, GEC8, and GEC9, as well as damage to the bridge rail after each test. Table 4 through Table 7 provide a summary of the MASH criteria evaluation of each individual test.

Figure 13. Option B1 details




Figure 14. Design Option B1 before testing



(a) Traffic face of bridge rail



(b) Steel post



(c) Joint



(d) Metal joint and sleeve



(e) Field side of post connection



(f) Field side of bridge rail

Figure 15. Test vehicle before Test No. 690900-GEC7



(a) 10000S test vehicle at impact point



(b) Left side of 10000S test vehicle

Figure 16. Rail option B1 after Test No. 690900-GEC7



(a) Traffic Side



(b) Field Side

Figure 17. Post 4 after Test No. 690900-GEC7



(a) Traffic side



(b) Field side

Figure 18. Post 5 after Test No. 690900-GEC7



(a) Traffic side

(b) Field side

Figure 19. Post 6 and 7 after Test No. 690900-GEC7



(a) Traffic side

(b) Field side

Figure 20. Post 8 after Test No. 690900-GEC7




(a) Traffic side

(b) Field side

Figure 21. Test vehicle after Test No. 690900-GEC7



(a) Damage to right side of test vehicle



(b) Damage to right front tire

Figure 22. Test vehicle before Test No. 690900-GEC7a



(a) 10000S test vehicle and bridge rail



(b) Right side of 10000S test vehicle

Figure 23. Rail Option B1 positions after Test No. 690900-GEC7a



(a) Traffic side of bridge rail



(b) Parallel with bridge rail

Figure 24. Posts 1 through 5 and rear of post 4 after Test No. GEC7a



(a) Traffic side

(b) Field side of post 4

Figure 25. Post 5 after Test No. 690900-GEC7a



(a) Traffic side

(b) Field side

Figure 26. Post 6 and 7 after Test No. 690900-GEC7a



(a) Post 6

(b) Post 7

Figure 27. Post 8 after Test No. 690900-GEC7a



(a) Traffic side

(b) Field side

Figure 28. Post 9 through 14 after Test No. 690900-GEC7a



(a) Field side of bridge rail

(b) Damage at post 9

Figure 29. Test vehicle after Test No. 690900-GEC7a




(a) Damage to left side of test vehicle

(b) Damage to left front tire

Figure 30. Test vehicle before Test No. 690900-GEC8



(a) 1100C test vehicle and bridge rail



(b) 1100C test vehicle

Figure 31. Rail Option B1 after Test No. 690900-GEC8



(a) Traffic side



(b) Parallel with bridge rail

Figure 32. Installation after Test No. 690900-GEC8



(a) Traffic face of bridge rail



(b) Joint



(c) Field side of bridge rail



(d) Crack in concrete curb

Figure 33. Test vehicle after Test No. 690900-GEC8



(a) Damage to right side



(b) Damage to right front tire

Figure 34. Test vehicle before Test No. 690900-GEC9



(a) 2270P test vehicle and bridge rail



(b) 2270P test vehicle

Figure 35. Position of vehicle/installation after Test No. 690900-GEC9



(a) Traffic side



(b) Along traffic face of bridge rail

Figure 36. Post 11 after Test No. 690900-GEC9



(a) Traffic side



(b) Field side

Figure 37. Post 12 and 13 after Test No. 690900-GEC9



(a) Traffic side impact area damage test



(b) Field side damage

Figure 38. Photos after Test No. 690900-GEC9



(a) Traffic side




(b) Field side

Figure 39. Test vehicle after Test No. 690900-GEC9



(a) Damage to right side



(b) Damage to right front wheel assembly

Figure 40. Interior of test vehicle for Test No. 690900-GEC9



(a) Before test

(b) After test

Table 4. Performance evaluation summary for MASH test 4-12 (Test No. 690900-GEC7) on Option B1 Bridge Rail

Evaluation Factors	Evaluation ⁵ Criteria	Test Results	Assessment
Structural Adequacy	A.	The option B1 bridge rail contained and redirected the 10000S vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 8.2 in.	Pass
Occupant Risk	D.	No detached elements, fragments, or other debris from the bridge rail were present to penetrate or show potential for penetrating the occupant compartment, or show undue hazard to others in the area. No occupant compartment deformation or intrusion was observed.	Pass
	G.	The 10000S remained upright during and after the collision event. Maximum roll during the collision event was 29 degrees.	Pass

⁵ See Table 9 for details of respective evaluation criteria.

Table 5. Performance evaluation summary for MASH Test 4-12 (Test No. 690900-GEC7a) on Option B1 Bridge Rail

Evaluation Factors	Evaluation⁶ Criteria	Test Results	Assessment
Structural Adequacy	A.	The Option B1 bridge rail contained and redirected the 10000S vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 19.6 in.	Pass
Occupant Risk	D.	Pieces of the concrete broke off from the bridge rail parapet and deck but did not show potential for penetrating the occupant compartment, nor show undue hazard to others in the area. No occupant compartment deformation or intrusion was observed.	Pass
	G.	The 10000S remained upright during and after the collision event. Maximum roll during the collision event was 35 degrees.	Pass

⁶ See Table 9 for details of respective evaluation criteria.

Table 6. Performance evaluation summary for MASH Test 4-10 (Test No. 690900-GEC8) on Option B1 Bridge Rail

Evaluation Factors	Evaluation ⁷ Criteria	Test Results	Assessment
Structural Adequacy	A.	The Option B1 bridge rail contained and redirected the 1100C vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 1.5 in.	Pass
Occupant Risk	D.	No detached elements, fragments, or other debris from the bridge rail were present to penetrate or show potential for penetrating the occupant compartment, or show undue hazard to others in the area. Maximum occupant compartment deformation was 1.0 in. in the right front kickpanel area.	Pass
	F.	The 1100C vehicle remained upright during and after the collision event. Maximum roll angle was 10 degrees and pitch was 8 degrees.	Pass
	H.	Longitudinal OIV was 23.0 ft/s, and lateral OIV was 32.8 ft/s.	Pass
	I.	Longitudinal RDA was 6.1 g, and lateral RDA was 8.8 g.	Pass

⁷ See Table 9 for details of respective evaluation criteria.

Table 7. Performance evaluation summary for MASH Test 4-11 (Test No. 690900-GEC9) on Option B1 Bridge Rail

Evaluation Factors	Evaluation⁸ Criteria	Test Results	Assessment
Structural Adequacy	A.	The Option B1 bridge rail contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 8.2 in.	Pass
Occupant Risk	D.	No detached elements, fragments, or other debris from the bridge rail were present to penetrate or show potential for penetrating the occupant compartment, or show undue hazard to others in the area.	Pass
		Maximum occupant compartment deformation was 1.0 in. in the right front kickpanel area.	
	F.	The 2270P vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 12 degrees and 10 degrees.	Pass
	H.	Longitudinal OIV was 15.1 ft/s, and lateral OIV was 25.6 ft/s.	Pass
	I.	Longitudinal occupant ridedown acceleration was 13.5 g, and lateral occupant ridedown acceleration was 11.7 g.	Pass

The Lake Pontchartrain Causeway Bridge Design Option B1 contained and redirected all test vehicles. Maximum dynamic deflection was 19.6 in. in the repeat MASH Test 4-12. In all three tests, no detached elements, fragments, or other debris from the bridge rail were present to penetrate or show potential for penetrating the occupant compartment, or show undue hazard to others in the area. No occupant compartment intrusion occurred, and minimal (1.0 in.) to no occupant compartment deformation occurred during the test. All test vehicles remained upright during and after the collision event. During the crash test with the car and pickup (MASH Test 4-10 and 4-11), the occupant risk factors were within the preferred limits specified in MASH. In conclusion, the Lake Pontchartrain

⁸ See Table 9 for details of respective evaluation criteria.

Causeway Bridge Design Option B1 performed acceptably according to MASH evaluation criteria for TL-4.

These designs were relevant to this project since these designs utilized a 10-in. high by 18-in. wide walkway curb. Information used from these projects were considered in this project.

Task 2 – Review of DOTD Bridge Rail Database

A literature review was completed for this project as part of Task 1. From Task 1, information was gathered on all the available retrofit options used previously that might be considered for this project. After Task 1 was completed, TTI received a database in Excel format from DOTD listing an inventory of bridges using concrete barriers with walkways used throughout the state. These bridges, approximately 200 total miles, used older types of concrete post and beam rails and solid concrete rails. The bridges in this database used a sidewalk for pedestrian access.

DOTD also provided numerous drawings and details for the common types of bridges in this database. These drawings, along with the Excel database provided to TTI researchers from DOTD, are provided in Bridge Curbed Barrier Retrofit Project. The information in the database and drawings were reviewed as part of this task. From this task, two bridge rail types were selected for analyses and detailing for retrofitting with respect to MASH TL-3. The bridge rails selected from this review were considered critical with respect to strength and performance for MASH TL-3. Other factors were also considered, such as their frequency of use, and geometrical considerations such as curb height, curb width, deck cantilever, and deck thickness.

Based on the researchers' review, the bridge rail designs from the Task 2 effort are provided as follows. For further information, please refer to the drawings provided in Appendix A. Approximately 20 drawings of different vintage bridge rail projects are provided in Bridge Curbed Barrier Retrofit Project. With the assistance of DOTD engineers, these drawings were selected from the larger database provided to TTI researchers on a spreadsheet database from DOTD. Engineering strength analyses were performed on the selected designs as follows.

Based on the researchers' review, the details shown on DOTD SCJ5C-90-24P appeared to be critical, based on strength and performance with respect to MASH TL-3. This design was also common for the concrete post and beam bridge rails with a safety walk. In addition, a solid concrete parapet was reviewed and analyzed during this reporting period. Figure 41 shows concrete geometry and reinforcement details for the concrete post and beam bridge rail with safety walk from drawing DOTD SCJ5C-90-24P. Details from SCJ5C-90-24P were used to develop the crash test installation details for the retrofit designs for this project. A retrofit design was also designed for a solid concrete parapet bridge rail with a safety walk. Drawing SC15A-60-24P and the details shown on this

drawing were used for this design. Details of the solid concrete parapet as shown on this drawing SC15A-60-24P are shown in Figure 42. Please note that the aluminum rail element for the solid concrete parapet was not considered crashworthy with respect to MASH Specifications and therefore needs to be removed prior to retrofitting.

Figure 41. Details from drawing SCJ5C-90-24P concrete post and beam






Figure 42. Details from drawing SC15A-60-24P solid concrete parapet with aluminum hand rail (to be removed)



Task 7 – Full Scale Testing of Retrofit Bridge Rail Option 1, Tested October 2018

In October 2018, full-scale testing was performed on the following bridge rail retrofit with respect to MASH TL-3. The retrofit bridge rail designed and tested for this option consisted of an HSS12x8x1/2 tubular rail element anchored to the top of the concrete post and beam with safety walk barrier selected in Task 2. A cross section view of the retrofit is shown in Figure 43.

Figure 43. Retrofit bridge rail Option 1 cross section details



Complete test installation details developed as part of Task 7 for retrofit Option 1 is presented in Appendix B. Please refer to these details in the appendix for additional information for this retrofit Option 1. As part of Task 7, these test installation details were used to construct a test installation for full scale crash testing with respect to MASH TL-3. Full-scale crash testing was performed on Option 1 in October 2018. A summary of the crash testing criteria and results are as follows.

Test Requirements and Evaluation Criteria

Crash Tests Performed

Table 8 shows the test conditions and evaluation criteria for MASH TL-3 for longitudinal barriers. MASH Test 3-10 involves an 1100C vehicle weighing 2420 lb. ± 55 lb. impacting the critical impact point (CIP) of the bridge barrier at an impact speed of 62 mi/h ± 2.5 mi/h and an angle of 25 degrees ± 1.5 degrees. MASH Test 3-11 involves a 2270P vehicle weighing 5000 lb. ± 110 lb. impacting the CIP of the bridge barrier at an impact speed of 62 mi/h ± 2.5 mi/h and an angle of 25 degrees ± 1.5 degrees.

Table 8. Test conditions and evaluation criteria specified for MASH TL-3 longitudinal barriers

Test Article	Test Designation	Test Vehicle	Impact Conditions		Evaluation Criteria
			Speed	Angle	
Longitudinal Barrier	3-10	1100C	62 mi/h	25°	A, D, F, H, I
	3-11	2270P	62 mi/h	25°	A, D, F, H, I

The target CIPs for tests on the Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk and the redesigned bridge rail were determined using the information provided in MASH Section 2.2.1, Section 2.3.2, and MASH Figure 2-1. Figure 44 depicts target CIPs for MASH Test 3-10 (crash Test No. 606861-2) and Test 3-11 (crash Test No. 606861-1) on the Louisiana Retrofit post and beam bridge rail with safety walk Option 1. Figure 45 depicts target CIP for MASH Test 3-10 (crash Test No. 606861-4) on the Redesigned Louisiana Retrofit post and beam bridge rail with safety walk Option 2. Figure 46 shows the target CIP for Test 3-11 (crash Test No. 606861-3) Redesigned Louisiana Retrofit post and beam bridge rail with safety walk Option 2.

The crash tests and data analysis procedures were in accordance with guidelines presented in MASH. Brief descriptions of these procedures are described under the section entitled Test Conditions.

Figure 44. Target CIPs for MASH tests on Louisiana Retrofit Post and Beam Bridge Rail With Safety Walk




Figure 45. Target CIPs for MASH Test 3-10 on redesigned Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk





Figure 46. Target CIP for MASH Test 3-11 on redesigned Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk



Evaluation Criteria

The appropriate safety evaluation criteria from Tables 2-2A and 5-1 of MASH were used to evaluate the crash tests reported herein. The test conditions and evaluation criteria required for MASH TL-3 are listed in Table 8, and the substance of the evaluation criteria

in Table 9. An evaluation of the crash test results is presented in detail under the section Assessment of Test Results.

Table 9. Evaluation criteria required for MASH TL-4 longitudinal barriers

Evaluation Factors	Evaluation Criteria	
Structural Adequacy	A.	Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.
Occupant Risk	D.	Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment or present undue hazard to other traffic, pedestrians, or personnel in a work zone.
		Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.
	F.	The vehicle should remain upright during and after collision for Tests 4-10 and 4-11. The maximum roll and pitch angles are not to exceed 75 degrees.
	H.	Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s for Tests 4-10 and 4-11.
	I.	The occupant ridedown accelerations should satisfy the following: Preferred value of 15.0 g, or maximum allowable value of 20.49 g for Tests 4-10 and 4-11.

Test Conditions

Test Facility

The full-scale crash tests reported herein were performed at Texas A&M Transportation Institute (TTI) Proving Ground, an International Standards Organization (ISO)/International Electrotechnical Commission (IEC) 17025-accredited laboratory with American Association for Laboratory Accreditation (A2LA) Mechanical Testing Certificate 2821.01. The full-scale crash tests were performed according to TTI Proving Ground quality procedures, and according to the MASH guidelines and standards.

The test facilities of the TTI Proving Ground are located on the Texas A&M University System RELLIS Campus, which consists of a 2000-acre complex of research and training facilities situated 10 miles northwest of the flagship campus of Texas A&M University. The site, formerly a United States Army Air Corps base, has large expanses of concrete runways and parking aprons well suited for experimental research and testing in the areas of vehicle performance and handling, vehicle-roadway interaction, durability and efficacy of highway pavements, and evaluation of roadside safety hardware and perimeter protective devices. The site selected for construction and testing of the bridge barrier was along the edge of an out-of-service apron. The apron consists of an unreinforced jointed-concrete pavement in 12.5-ft. × 15 ft. blocks nominally 6 in. deep. The aprons were built in 1942, and the joints have some displacement, but are otherwise flat and level.

Vehicle Tow and Guidance System

Each test vehicle was towed into the test installation using a steel cable guidance and reverse tow system. A steel cable for guiding the test vehicle was tensioned along the path, anchored at each end, and threaded through an attachment to the front wheel of the test vehicle. An additional steel cable was connected to the test vehicle, passed around a pulley near the impact point, through a pulley on the tow vehicle, and then anchored to the ground such that the tow vehicle moved away from the test site. A 2:1 speed ratio between the test and tow vehicle existed with this system. The test vehicle was released just prior to impact, and ran unrestrained. The vehicle remained freewheeling (i.e., no steering or braking inputs) until it cleared the immediate area of the test site (no sooner

than 2 s after impact), after which the brakes were activated, if needed, to bring the test vehicle to a safe and controlled stop.

Data Acquisition Systems

Vehicle Instrumentation and Data Processing

Each test vehicle was instrumented with a self-contained, on-board data acquisition system. The signal conditioning and acquisition system is a 16-channel, Tiny Data Acquisition System (TDAS) Pro produced by Diversified Technical Systems, Inc. The accelerometers, which measure the x, y, and z axis of vehicle acceleration, are strain gauge type with linear millivolt output proportional to acceleration. Angular rate sensors, measuring vehicle roll, pitch, and yaw rates, are ultra-small, solid state units designed for crash test service. The TDAS Pro hardware and software conform to the latest SAE J211, Instrumentation for Impact Test. Each of the 16 channels is capable of providing precision amplification, scaling, and filtering based on transducer specifications and calibrations. During the test, data are recorded from each channel at a rate of 10,000 values per second with a resolution of one part in 65,536. Once data are recorded, internal batteries back these up inside the unit should the primary battery cable be severed. Initial contact of the pressure switch on the vehicle bumper provides a time zero mark as well as initiates the recording process. After each test, the data are downloaded from the TDAS Pro unit into a laptop computer at the test site. The Test Risk Assessment Program (TRAP) software then processes the raw data to produce detailed reports of the test results.

Each of the TDAS Pro units is returned to the factory annually for complete recalibration and all instrumentation used in the vehicle conforms to all specifications outlined by SAE J211. All accelerometers are calibrated annually by means of an ENDEVCO™ 2901, precision primary vibration standard. This standard and its support instruments are checked annually and receive a National Institute of Standards Technology (NIST) traceable calibration. The rate transducers used in the data acquisition system receive a calibration via a Genisco Rate-of-Turn table. The subsystems of each data channel are also evaluated annually, using instruments with current NIST traceability, and the results are factored into the accuracy of the total data channel, per SAE J211. Calibrations and evaluations are also made any time data are suspect. Acceleration data is measured with an expanded uncertainty of ± 1.7 percent at a confidence factor of 95 percent ($k=2$).

TRAP uses the data from the TDAS Pro to compute occupant/compartiment impact velocities, time of occupant/compartiment impact after vehicle impact, and the highest 10-millisecond (ms) average ridedown acceleration. TRAP calculates change in vehicle velocity at the end of a given impulse period. In addition, maximum average accelerations over 50-ms intervals in each of the three directions are computed. For reporting purposes, the data from the vehicle-mounted accelerometers are filtered with a 60-Hz low-pass digital filter, and acceleration versus time curves for the longitudinal, lateral, and vertical directions are plotted using TRAP.

TRAP uses the data from the yaw, pitch, and roll rate transducers to compute angular displacement in degrees at 0.0001-s intervals, then plots yaw, pitch, and roll versus time. These displacements are in reference to the vehicle-fixed coordinate system with the initial position and orientation of the vehicle-fixed coordinate systems being initial impact. Rate of rotation data is measured with an expanded uncertainty of ± 0.7 percent at a confidence factor of 95 percent ($k=2$).

Anthropomorphic Dummy Instrumentation

An Alderson Research Laboratories Hybrid II, 50th percentile male anthropomorphic dummy, restrained with lap and shoulder belts, was placed in the front seat on the impact side of the 1100C vehicle. The dummy was not instrumented.

According to MASH, it is recommended a dummy be used when testing “any longitudinal barrier with a height greater than or equal to 33 in.” Use of the dummy in the 2270P vehicle is recommended for tall rails to evaluate the “potential for an occupant to extend out of the vehicle and come into direct contact with the test article.” Although this information is reported, it is not part of the impact performance evaluation. Since the height of the top of the rail on the Option 1 bridge rail was $42\frac{5}{8}$ in. and the redesigned Option 2 bridge rail was 40 in., a dummy was placed in the front seat of the 2270P vehicles on the impact side and restrained with lap and shoulder belts.

Vehicle Instrumentation and Data Processing

Photographic coverage of each test included three digital high-speed cameras:

1. One overhead with a field of view perpendicular to the ground and directly over the impact point;
2. One placed on the traffic side of the installation at an angle behind the impact; and

3. A third placed to have a field of view parallel to and aligned with the installation at the downstream end.

A flashbulb on the impacting vehicle was activated by a pressure-sensitive tape switch to indicate the instant of contact with the bridge rail. The flashbulb was visible from each camera. The video files from these digital high-speed cameras were analyzed to observe phenomena occurring during the collision and to obtain time-event, displacement, and angular data. A digital camera recorded and documented conditions of each test vehicle and the installation before and after the test.

MASH TL-3 Testing of Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1

Test Installation Details

Test Installation Description

The test installation was 106 ft.-10³/₄ in. long and consisted of a reinforced cantilevered concrete deck, a stepped-up sidewalk, with a curb and posts topped by a concrete beam, and a rectangular hollow steel rail anchored on top of the concrete beam. The sidewalk, curb, posts, and beam were comprised of five separate segments with 1-in. gaps between the sidewalk and curb segments and 6-in. gaps between the post and beam segments. Each segment contained three concrete posts with one at each end and one at center.

Each steel rail section measured 21 ft.-3³/₄ in. long, and each was anchored to the top of the concrete rail such that the impact face of the steel tubes was flush with the impact face of the concrete rails. A 36-in. long fabricated rail splice section spanned the 1-in. gaps between the steel rail sections. The steel rail sections were attached to the concrete beam with ³/₄-in. diameter ×16-in. long threaded rods secured with Hilti HIT-RE500V3 epoxy adhesive.

Appendix B presents the drawings and information on the Louisiana Retrofit post and beam bridge rail with safety walk Option 1, and Figure 47 through Figure 49 provide photographs of the completed installation.

Material Specifications

The specified compressive strength of the concrete used in the wall, deck, curb, and parapet was 3000 psi. On October 2, 2018, the average compressive strengths of the concrete were as follows:

- Average concrete strength for the wall and deck: 4535 psi at 75 days of age.
- Average concrete strength for the curb: 4643 psi at 66 and 67 days of age (2 pours).
- Average concrete strength for the parapet: 4044 psi at 54 and 61 days of age (2 pours).

Appendix C provides material certification documents for the materials used to install/construct the Louisiana Retrofit post and beam bridge rail with safety walk Option 1.

Figure 47. Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1 prior to testing



(a) Traffic face of bridge rail



(b) Field side of bridge rail



(c) Upstream of joint



(d) Downstream of joint

Figure 48. Joint 2 of Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1 prior to testing



(a) Metal rail element at joint 2



(b) Concrete parapet at joint 2

Figure 49. Field side of Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1 prior to testing



(a) Field side of joint 2



(b) Field side of joint 4

MASH Test 3-11 (Crash Test No. 606861-1)

Test Designation and Actual Impact Conditions

MASH Test 3-11 involves a 2270P vehicle weighing 5000 lbs \pm 110 lbs impacting the CIP of the bridge barrier at an impact speed of 62 mi/h \pm 2.5 mi/h and an angle of 25 degrees \pm 1.5 degrees. The CIP for MASH Test 3-11 on the Louisiana Retrofit post and beam bridge rail with safety walk Option 1 was determined to be 4.3 ft. \pm 1 ft. upstream of the

centerline of the second open joint in the concrete deck/beam. Figure 44 and Figure 50 depict the target CIP.

Figure 50. Test vehicle/bridge rail geometrics for Test No. 606861-1



(a) Frontal view of 2270P test vehicle at target impact point

(b) Rear view of 2270P test vehicle at target impact point

The 2270P vehicle used in the test weighed 5015 lbs, and the actual impact speed and angle were 63.5 mi/h and 25.2 degrees. The actual impact point was 3.9 ft. upstream of the centerline of the second open joint in the concrete deck/beam. Minimum target impact severity (IS) was 106 kip ft., and actual IS was 123 kip-ft.

Weather Conditions

The test was performed on the morning of October 2, 2018. Weather conditions at the time of testing were as follows: wind speed: 2 mi/h; wind direction: 153 degrees (vehicle was traveling at a heading of 150 degrees); temperature: 77°F; relative humidity: 98 percent.

Test Vehicle

Figure 51 shows the 2012 RAM 1500 pickup truck used for the crash test. The vehicle's test inertia weight was 5015 lbs, and its gross static weight was 5180 lbs. The height to the lower edge of the vehicle bumper was 11.75 in., and the height to the upper edge of the bumper was 27.0 in. The height to the vehicle's center of gravity was 28.5 in. Figure 106 and Figure 107 in Appendix D give additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and

guidance system and was released to be freewheeling and unrestrained just prior to impact.

Figure 51. Test vehicle prior to Test No. 606861-1



(a) Right side of 2270P test vehicle

(b) Left side of 2270P test vehicle

Test Description

Table 10 lists times and significant events that occurred during Test No. 606861-1. Figure 108 through Figure 110 in Appendix D present sequential photographs during the test.

Table 10. Events during Test No. 606861-1

Time (s)	Events
0.0000	Data acquisition trigger activated by curb
0.0160	Right front tire of vehicle contacts curb
0.0480	Right front bumper contacts concrete rail
0.0630	Vehicle begins to redirect
0.2330	Maximum deflection of rail element
0.2710	Left front tire leaves pavement surface
0.3230	Left front tire returns to pavement surface
0.3990	Vehicle is parallel to the bridge barrier
0.4450	Right rear tire rides up onto curb
0.5300	Left rear tire leaves pavement surface
0.5420	Rear right side of vehicle contacts concrete rail
0.6830	Vehicle loses contact with bridge rail while traveling 31.6 mi/h, at a trajectory angle of 6.3 degrees, and a heading angle of 9.7 degrees
1.0600	Left rear tire returns to pavement surface

For longitudinal barriers, it is desirable that the vehicle redirects and exits the barrier within the exit box criteria (not less than 32.8 ft. downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in MASH. Brakes on the vehicle were not applied. After loss of contact with the barrier, the vehicle came to rest 122 ft. downstream of the impact and 20 ft. toward the traffic side.

Damage to Test Installation

Figure 52 through Figure 55 show the damage to the Option 1 bridge rail. The concrete at both posts at joint 2, and the middle post in section 3, failed with rebar exposed. Numerous cracks were observed in the beam and middle post of section 2 and along the beam of section 3, ending 30 in. upstream of the downstream end of section 3. The rear of the deck was broken out at the middle post of section 2, the end posts at the second joint,

and the middle post of section 3. Working width⁹ was 22.1 in., and height of the working width was 42.6 in.. Maximum dynamic deflection during the test was 10.0 in., and maximum permanent deformation was 7.25 in.

Figure 52. Option 1 bridge rail after Test No. 606861-1



(a) Bridge rail/test vehicle after test



(b) Permanent deformation of bridge rail

⁹ Per MASH, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.

Figure 53. Damage at joint 2 after Test No. 606861-1



(a) Damage to curb and beam



(b) Damage at joint 2

Figure 54. Damage at section 3 after Test No. 606861-1



(a) Section 3 just downstream of joint 2



(b) Middle post of section 3

Figure 55. Damage on field side of bridge rail after Test No. 606861-1



(a) Field side of section 2



(b) Field side of middle post of section 2



(c) Field side of end posts at joint 2



(d) Field side of middle post of section 3

Damage to Test Vehicle

Figure 56 shows the damage sustained by the vehicle. The front bumper, grill, hood, right front fender, right front upper and lower ball joints, right front tire and rim, right frame rail, right front door, right rear tire, and rear bumper were damaged. Maximum exterior crush to the vehicle was 16.0 in. in the front plane at the right front corner at bumper height. Maximum occupant compartment deformation was 2.0 in. in the right firewall. Figure 57 shows the interior of the vehicle. Figure 111 and Figure 112 in Appendix D provide exterior crush and occupant compartment measurements.

Figure 56. Test vehicle after Test No. 606861-1



(a) Front of 2270P test vehicle after test

(b) Right front of 2270P test vehicle

Figure 57. Interior of test vehicle after Test No. 606861-1



(a) Interior of cab of 2270P test vehicle

(a) Right front floor pan of 2270P test vehicle

Occupant Risk Factors

Data from the accelerometer, located at the vehicle center of gravity, were digitized for evaluation of occupant risk and results are shown in Table 11. Figure 58, Table 12, and Table 13 summarize these data and other pertinent information from the test. Figure 113 in Appendix D shows the vehicle angular displacements, and Figure 114 through Figure 116 in Appendix D show acceleration versus time traces.

Table 11. Occupant risk factors for Test No. 606861-1

Occupant Risk Factor	Value	Time
Occupant Impact Velocity (OIV)		
Longitudinal	28.9 ft/s	at 0.1472 s on right side of interior
Lateral	21.7 ft/s	
Occupant Ridedown Accelerations		
Longitudinal	11.8 g	0.2803 - 0.2903 s
Lateral	6.5 g	0.2912 - 0.3012 s
Theoretical Head Impact Velocity (THIV)	10.9 m/s	at 0.1444 s on right side of interior
Acceleration Severity Index (ASI)	1.6	0.1079 - 0.1579 s
Maximum 50-ms Moving Average		
Longitudinal	-12.0 g	0.0940 - 0.1440 s
Lateral	-10.9 g	0.0783 - 0.1283 s
Vertical.....	-3.5 g	0.0657 - 0.1157 s
Maximum Roll, Pitch, and Yaw Angles		
Roll.....	14 degrees	1.2803 s
Pitch	6 degrees	0.6268 s
Yaw	35 degrees	0.6866 s

Figure 58. Summary of results for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1



(a) 0.000 s




(b) 0.200 s




(c) 0.400 s



(d) 0.600 s



(e) Impact summary



(f) Cross-section of bridge rail

Table 12. Summary of results for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1—Pre-Impact Information

General Information	
Test Agency	Texas A&M Transportation Institute
Test Standard Test No.	MASH Test 3-11
TTI Test No.	606861-1
Test Date	2018-10-02
Test Article	
Type	Longitudinal Barrier—Bridge Rail
Name	Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk
Installation Length	106 ft.-10¾ in.
Material or Key Elements	Reinforced cantilevered concrete deck, stepped-up sidewalk, curb and posts topped by a concrete beam, rectangular hollow steel rail secured on top of the concrete beam
Foundation Type/Condition	Concrete Bridge Deck, Damp
Test Vehicle	
Type/Designation	2270P
Make and Model	2012 RAM 1500 Pickup
Curb	4983 lbs.
Test Inertial	5015 lbs.
Dummy	165 lbs.
Gross Static	5180 lbs.
Impact Conditions	
Speed	63.5 mi/h
Angle	25.2 degrees
Location	3.9 ft. upstream of joint 2
Impact Severity	123 kip-ft.
Exit Conditions	
Speed	31.6 mi/h
Exit Trajectory/Heading	6.3 degrees/9.7 degrees

Table 13. Summary of results for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1—Post-Impact Information

Occupant Risk Values	
Longitudinal OIV	28.9 ft/s
Lateral OIV	21.7 ft/s
Longitudinal Ridedown	11.8 g
Lateral Ridedown	6.5 g
THIV	10.9 m/s
ASI	1.6
Max. 0.050-s Average	
Longitudinal	-12.0 g
Lateral	-10.9 g
Vertical	-3.5 g
Post-Impact Trajectory	
Stopping Distance	122 ft. downstream / 20 ft. toward traffic lanes
Vehicle Stability	
Maximum Roll Angle	14 degrees
Maximum Pitch Angle	6 degrees
Maximum Yaw Angle	35 degrees
Vehicle Snagging	No
Vehicle Pocketing	No
Test Article Deflections	
Dynamic	10.0 in.
Permanent	7.25 in.
Working Width	22.1 in.
Height of Working Width	42.6 in.
Vehicle Damage	
VDS	01RFQ5
CDC	01FREW5
Max Exterior Deformation	16.0 in.
OCDI	FR0010000
Max Occupant Compartment Deformation	2.0 in.

MASH Test 3-10 (Crash Test No. 606861-2)

Test Designation and Actual Impact Conditions

MASH Test 3-10 involves an 1100C vehicle weighing 2420 lbs \pm 55 lbs impacting the CIP of the bridge barrier at an impact speed of 62 mi/h \pm 2.5 mi/h and an angle of 25 degrees \pm 1.5 degrees. The CIP for MASH Test 3-10 on the Louisiana Retrofit post and beam bridge rail with safety walk Option 1 was 3.6 ft. \pm 1 ft. upstream of the centerline of the fourth open joint in the concrete deck/beam. Figure 44 and Figure 59 depict the target impact point.

Figure 59. Test vehicle/bridge rail geometrics for Test No. 606861-2



(a) Frontal view of 1100C test vehicle at target impact point

(b) Rear view of 1100C test vehicle at target impact point

The 1100C vehicle used in the test weighed 2425 lbs, and the actual impact speed and angle were 62.0 mi/h and 25.2 degrees. The actual impact point was 3.3 ft. upstream of the centerline of the fourth open joint in the concrete deck/beam. Minimum target IS was 51 kip-ft., and actual IS was 57 kip-ft.

Weather Conditions

The test was performed on the morning of October 3, 2018. Weather conditions at the time of testing were as follows: wind speed: 5 mi/h; wind direction: 166 degrees (vehicle was traveling at a heading of 150 degrees); temperature: 83°F; relative humidity: 83 percent.

Test Vehicle

Figure 60 shows the 2009 Kia Rio¹⁰ used for the crash test. The vehicle's test inertia weight was 2425 lbs, and its gross static weight was 2590 lbs. The height to the lower edge of the vehicle bumper was 7.75 in., and the height to the upper edge of the bumper was 21.5 in. Figure 117 in Appendix E gives additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.

Figure 60. Test vehicle before Test No. 606861-2



(a) Right side of 1100C test vehicle

(b) Left side of 1100C test vehicle

Test Description

Table 14 lists events that occurred during Test No. 606861-2. Figure 118 through Figure 120 in Appendix E present sequential photographs during the test.

¹⁰ The 2009 model vehicle used is older than the 6-year age noted in MASH, and was selected based upon availability. An older model vehicle is permitted by AASHTO as long as it is otherwise MASH compliant. Other than the vehicle's year model, this 2009 model vehicle met the MASH requirements.

Table 14. Events during Test No. 606861-2

Time (s)	Events
0.0000	Data acquisition trigger activated by curb
0.0180	Vehicle lower front right bumper contacts curb
0.0490	Vehicle begins to redirect
0.0620	Vehicle contacts concrete beam
0.1020	Left front tire leaves pavement surface
0.1920	Left rear tire leaves pavement surface
0.2550	Vehicle traveling parallel to bridge barrier
0.2760	Left rear of vehicle contacts bridge barrier
0.3530	Vehicle loses contact with bridge rail while traveling at 47.4 mi/h, at a trajectory angle of 2.0 degrees, and a heading angle of 5.8 degrees
0.4570	Left front tire returns to pavement surface

For longitudinal barriers, it is desirable that the vehicle redirects and exits the barrier within the exit box criteria (not less than 32.8 ft. downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in MASH. Brakes on the vehicle were not applied. After loss of contact with the barrier, the vehicle came to rest 145 ft. downstream of the impact and 23 ft. toward traffic lanes.

Damage to Test Installation

Figure 61 through Figure 63 show the damage to the Option 1 bridge rail. The concrete curb was cracked through on the upstream side of the post on the downstream end of section 4, and a small crack in the curb was observed on the downstream side. The metal rail element was scuffed and scratched. Working width¹¹ was 12.7 in., and height of

¹¹ Per MASH, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.

working width was 42.6 in. Maximum dynamic deflection during the test was 0.7 in., and there was no measurable permanent deformation.

Figure 61. Option 1 bridge rail after Test No. 606861-2



(a) Bridge rail/test vehicle after test



(b) Traffic side of bridge rail at impact

Figure 62. Damage to traffic face of bridge rail after Test No. 606861-2



(a) Traffic side at impact point



(b) Traffic side of joint 4



(c) Traffic side of posts at joint 4



(d) Traffic side of metal rail at joint 4

Figure 63. Damage on field side of bridge rail after Test No. 606861-2



(a) Field side of joint 4

(b) Close up view of field side of joint 4

Damage to Test Vehicle

Figure 64 shows the damage sustained by the vehicle. The front bumper, grill, hood, radiator and support, right front tire and rim, right front strut and strut tower, right front fender, right front door and window glass, right rear quarter panel, right rear rim, and rear bumper were damaged. Maximum exterior crush to the vehicle was 9.0 in. in the side plane at the right front corner at bumper height. Maximum occupant compartment deformation was 1.5 in. in the right firewall area. Figure 65 shows the interior of the vehicle. Figure 121 and Figure 122 in Appendix E provide exterior crush and occupant compartment measurements.

Figure 64. Test vehicle after Test No. 606861-2



(a) Front of 1100C test vehicle after test

(b) Right front of 1100C test vehicle

Figure 65. Interior of test vehicle after Test No. 606861-2



(a) Interior of cab of 1100C test vehicle

(b) Right front floor pan

Occupant Risk Factors

Data from the accelerometer, located at the vehicle center of gravity, were digitized for evaluation of occupant risk and results are shown in Table 15. Figure 66, Table 16, and Table 17 summarize these data and other pertinent information from the test. Figure 123 in Appendix E shows the vehicle angular displacements, and Figure 124 through Figure 126 in Appendix E show acceleration versus time traces.

Table 15. Occupant risk factors for Test No. 606861-2

Occupant Risk Factor	Value	Time
OIV		
Longitudinal	18.4 ft/s	at 0.1103 s on right side of interior
Lateral	24.3 ft/s	
Occupant Ridedown Accelerations		
Longitudinal	23.1 g	0.1103 - 0.1203 s
Lateral	21.4 g	0.1103 - 0.1203 s
THIV	9.1 m/s	at 0.1070 s on right side of interior
ASI	1.7	0.1063 - 0.1563 s
Maximum 50-ms Moving Average		
Longitudinal	-9.9 g	0.0700 - 0.1200 s
Lateral	-12.6 g	0.0804 - 0.1304 s
Vertical.....	-5.5 g	0.0000 - 0.0500 s
Maximum Roll, Pitch, and Yaw Angles		
Roll.....	21 degrees	0.8788 s
Pitch	10 degrees	0.5391 s
Yaw	51 degrees	1.4091 s

Figure 66. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1




(a) 0.000 s

(b) 0.200 s




(c) 0.400 s

(d) 0.600 s



(e) Impact summary



(f) Cross-section of bridge rail

Table 16. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1—Pre-Impact Information

General Information	
Test Agency	Texas A&M Transportation Institute
Test Standard Test No.	MASH Test 3-10
TTI Test No.	606861-2
Test Date	2018-10-03
Test Article	
Type	Longitudinal Barrier—Bridge Rail
Name	Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk
Installation Length	106 ft.-10¾ in.
Material or Key Elements	Reinforced cantilevered concrete deck, stepped-up sidewalk, curb and posts topped by a concrete beam, rectangular hollow steel rail secured on top of the concrete beam
Foundation Type/Condition	Concrete Bridge Deck, Damp
Test Vehicle	
Type/Designation	1100C
Make and Model	2009 Kia Rio
Curb	2457 lbs.
Test Inertial	2425 lbs.
Dummy	165 lbs.
Gross Static	2590 lbs.
Impact Conditions	
Speed	62.0 mi/h
Angle	25.2 degrees
Location	3.3 ft. upstream of fourth joint
Impact Severity	57 kip-ft.
Exit Conditions	
Speed	47.4 mi/h
Exit Trajectory/Heading	2.0 degrees/5.8 degrees

Table 17. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1—Post-Impact Information

Occupant Risk Values	
Longitudinal OIV	18.4 ft/s
Lateral OIV	24.3 ft/s
Longitudinal Ridedown	23.1 g (High)
Lateral Ridedown	21.4 g (High)
THIV	9.1 m/s
ASI	1.7
Max. 0.050-s Average	
Longitudinal	-9.9 g
Lateral	-12.6 g
Vertical	-5.5 g
Post-Impact Trajectory	
Stopping Distance	145 ft. downstream / 23 ft. toward traffic lanes
Vehicle Stability	
Maximum Roll Angle	21 degrees
Maximum Pitch Angle	10 degrees
Maximum Yaw Angle	51 degrees
Vehicle Snagging	No
Vehicle Pocketing	No
Test Article Deflections	
Dynamic	0.7 in.
Permanent	None measurable
Working Width	12.7 in.
Height of Working Width	42.6 in.
Vehicle Damage	
VDS	01RFQ5
CDC	01FREW5
Max Exterior Deformation	9.0 in.
OCDI	RF0010000
Max Occupant Compartment Deformation	1.5 in.

Discussion of Results for MASH TL-3 Tests on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1

Table 18 shows the Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk met the specified criteria for MASH Test 3-11. However, for MASH Test 3-10, Table 19 shows that the longitudinal and lateral occupant ridedown accelerations were both above the maximum allowable limit of 20.49 g specified in MASH. Therefore, the Louisiana Retrofit post and beam bridge rail with safety walk Option 1 failed to meet occupant risk criteria for MASH Test 3-10, and thus MASH TL-3.

The researchers determined that the bridge rail should be redesigned to achieve performance of the bridge rail to MASH TL-3 specifications.

Table 18. Performance evaluation summary for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1

Evaluation Factors	Evaluation ¹² Criteria	Test Results	Assessment
Structural Adequacy	A.	The Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 10.0 in.	Pass
Occupant Risk	D.	The concrete curb and posts fractured into several pieces. However, these fragments did not penetrate or show potential for penetrating the occupant compartment, or present undue hazard for others on the bridge barrier (several fragments came to rest below the bridge deck). Maximum occupant compartment deformation was 2.0 in. in the right firewall area.	Pass
	F.	The 2270P vehicle remained upright during and after the collision event. Maximum roll was 14 degrees and pitch was 6 degrees.	Pass
	H.	Longitudinal OIV was 28.9 ft/s, and lateral OIV was 21.7 ft/s.	Pass
	I.	Maximum longitudinal occupant ridedown was 11.8 g, and maximum lateral occupant ridedown was 6.5 g.	Pass

¹² See Table 9 for details of respective evaluation criteria.

Table 19. Performance evaluation summary for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1


Evaluation Factors	Evaluation ¹³ Criteria	Test Results	Assessment
Structural Adequacy	A.	The Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk contained and redirected the 1100C vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 0.7 in.	Pass
Occupant Risk	D.	No detached elements, fragments, or other debris was present to penetrate or show potential for penetrating the occupant compartment, or present undue hazard for others on the bridge barrier. Maximum occupant compartment deformation was 1.5 in. in the right firewall area.	Pass
	F.	The 1100C vehicle remained upright during and after the collision event. Maximum roll was 21 degrees and pitch was 10 degrees.	Pass
	H.	Longitudinal OIV was 18.4 ft/s, and lateral OIV was 24.3 ft/s.	Pass
	I.	Maximum longitudinal occupant ridedown was 23.1 g, and maximum lateral occupant ridedown was 21.4 g.	Fail

¹³ See Table 9 for details of respective evaluation criteria.

Design and Strength Analysis of the Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2

Due to the unsuccessful MASH Test 3-10 performed on October 3, 2018, for Task 3 of this project, a new retrofit design Option (Option 2) was designed and detailed. A strength analysis procedure using the AASHTO LRFD Bridge Design Specifications, Section 13 [4] was used to analyze the structural capacity of the new bridge rail retrofit. Figure 67 shows a section view of the new retrofitted bridge rail system designed for this project. Appendix F presents the strength analysis performed on the new retrofitted bridge rail. Appendix G presents the structural details for the new retrofit bridge rail.

Figure 67. Section view of retrofitted bridge rail system



The inelastic or yield line resistance of the concrete rail using the principles of the Whitney Stress Block method combined with the elastic resistance of the retrofitted metal rails contributing to an inelastic hinge mechanism in the rail contributing to a plastic hinge (denoted M_p in AASHTO Section 13, but denoted M_{rail} in the worksheet) was calculated. The plastic moment resistance of the concrete post at three critical failure sections (denoted M_{FS} in the worksheet) is calculated using the principles of the Whitney Stress Block method.

The strength of a single post (denoted P_p in AASHTO Section 13 and in the worksheet in Appendix E) at a failure section was calculated using Equation 1.

$$P_p = \frac{M_{FS}}{y_{FS}} \quad (1)$$

where:

P_p = Minimum strength of a single post which corresponds to M_{FS} and is located y_{bar} above the deck (kips) considering several possible failure modes

y_{FS} = Height of rail force measured from the centroid of the failure section (in.)

M_{FS} = Minimum plastic moment resistance at the failure section (kip-in)

For post strength P_p , three different failure sections were considered. Failure Section 1 is assumed to be located at the interface between the bottom of a post and the top of curb. Failure Section 2 is assumed to be located at the vertical interface of the curb with the sidewalk at the center of sidewalk section (see Figure 68). Failure Section 3 is assumed to be located at the vertical interface between the deck and curb at the center of deck section (see Figure 69).

Once the strength of each failure section was calculated, the minimum strength (i.e., the minimum P_p value) was taken as the limiting or “worst case” post strength used in the AASHTO Section 13 equations.

The total resistance of the railing (denoted R in AASHTO Section 13) is calculated using AASHTO Section 13 Equation A13.3.2-3 (Equation 2).

Figure 68. Plan view of failure section 2





Figure 69. Plan view of failure section 3



$$R = \frac{2M_p + 2P_p L (\sum_{i=1}^N i)}{2NL - L_t} \quad (2)$$

where:

R = Total ultimate resistance, i.e., nominal resistance, of the railing (kips)

L = Post spacing of single span (ft.)

M_p (denoted M_{rail} on spreadsheet) = Inelastic or yield line resistance of all rails contributing to a plastic hinge (kip-ft.).

N = Number of railing spans.


The structural analysis conducted on the new DOTD retrofitted bridge rail system are presented in Appendix F. The resistance of the new retrofit bridge rail design was compared to the MASH TL-3 design transverse impact load (F_t) of 71 kips located an effective height (H_e) of 19 in. above the deck surface. The new retrofit bridge rail system has a calculated resistance of 75.4 kips located at an effective height (H_e) of 19 in. above the deck. Since the calculated resistance is greater than the design impact load, the retrofitted bridge rail system meets MASH TL-3 structural adequacy criterion. TTI completed test installation details necessary for construction of the new retrofit bridge rail design. Please refer to the calculations in Appendix F for additional information. For additional information on the details of the new retrofit bridge rail please refer to the details presented in Appendix G. The details shown in Appendix G were developed for MASH full-scale crash testing. The concrete post and beam bridge rail, safety sidewalk, and deck cantilever are the same as those constructed for full-scale crash testing in late 2018.

Based on the results of the structural analysis, the new retrofit bridge rail design as shown herein meets the strength requirements for MASH TL-3. This new design improves the strength of the existing concrete bridge rail and still allows some access to the existing safety sidewalk. This design was recommended for full-scale crash testing.

It was recommended that this design be full-scale crash tested as per the MASH specifications for TL-3. Two full-scale crash tests were planned. MASH Test 3-10 (small car) was performed on December 11, 2020. MASH Test 3-11 (pickup truck) was planned for December 14, 2020.

The new retrofit bridge rail design was also considered for a solid concrete parapet used by DOTD. The details of the retrofit design will require a small post with a base plate anchoring the retrofit bridge rail on top of the solid concrete parapet. These posts are necessary to maintain the rail height of 40 in. from the roadway surface. These posts will maintain the same geometry as the crash tested design. The centerline of the posts shall be located 24 in. minimum from the end of the concrete parapet. Details of the retrofit bridge rail anchored to the solid concrete parapet are shown in Figure 70 through Figure 72. The calculated strength of the new retrofit design anchored to the solid concrete parapet was 140 kips at a height of 19 in. above the roadway surface. Therefore, this retrofit design meets the strength requirements of MASH TL-3. Calculations for the retrofit design are presented in Appendix H.


Figure 70. Details of the retrofit bridge rail anchored to the solid concrete parapet, sheet 1



	Roadside Safety and Physical Security Division - Proving Ground	2021-09-09
	Project #606861 LaDOT Low Parapet	Sheet 1 of 3 Installation
Drawn by GES	Scale 1:100	Scale 1:20


T:\11-ProjectFiles\606861 - LADOTD Bridge Railing Retrofits - Williams\Drafting, 2nd design\low parapet, 2021-02-25\Low Parapet Drawing

Figure 71. Details of the retrofit bridge rail anchored to the solid concrete parapet, sheet 2



T:\1-ProjectFiles\606861 - LADOTD Bridge Railing Retrofits - Williams\Drafting, 2nd design\low parapet, 2021-02-25\Low Parapet Drawing

Figure 72. Details of the retrofit bridge rail anchored to the solid concrete parapet, sheet 3



	Roadside Safety and Physical Security Division - Proving Ground	2021-09-09
	Project #606861 LaDOT Low Parapet	Sheet 3 of 3 Splice Assembly and Rail
Drawn by GES	Scale 1:10	Project #606861 LaDOT Low Parapet

T:\1-ProjectFiles\606861 - LADOTD Bridge Railing Retrofits - Williams\Drafting, 2nd design\low parapet, 2021-02-25\Low Parapet Drawing

MASH TL-3 Testing of Retrofit Post and Beam Bridge Rail with Safety Walk Option 2

Test Installation Details

Test Installation Description

The test installation was 106 ft.-10³/₄ in. long, and consisted of a reinforced cantilevered concrete deck, a stepped-up sidewalk, with a curb and posts topped by a concrete beam, and two rectangular hollow steel rails anchored to the front face of the concrete beam. The sidewalk, curb, posts, and beams were comprised of five separate segments, with 1-in. gaps between the sidewalk, curb, and rail segments, and 6-in. gaps between the post and beam segments. Each segment contained three concrete posts, with one at each end and one at center.

Each steel rail section measured 21 ft.-3³/₄ in. long. A 36-in. long fabricated rail splice section spanned the 1-in. gaps between the steel rail sections. The top steel rail sections were attached to the concrete beam with L6×4×¹/₂ in. angle brackets that were anchored to the concrete beam with ³/₄-in. diameter × 8-in. long B7 threaded rods secured with Hilti HIT-RE500V3 epoxy adhesive. The bottom steel rails were secured through and to the top rails with ⁵/₈-in. diameter × 22-in. long grade B7 threaded rods, washers, and bolts.

Appendix G presents the drawings and information on the Louisiana Retrofit post and beam bridge rail with safety walk Option 2, and Figure 73 and Figure 74 provides photographs of the completed installation.

Material Specifications

The specified compressive strength of the concrete used in the wall, deck, curb, and parapet was 3000 psi. On December 10, 2020, the average compressive strengths of the concrete were as follows:

- Average concrete strength for the wall and deck: 4448 psi at 41 days of age.
- Average concrete strength for the curb: 4563 psi at 35 days of age.
- Average concrete strength for the parapet: 4033 psi at 21 days of age.

Appendix I provides material certification documents for the materials used to install/construct the Louisiana Retrofit post and beam bridge rail with safety walk Option 2.

Figure 73. Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2 prior to testing



(a) Traffic face of bridge rail



(b) Field side of bridge rail



(c) Upstream of joint



(d) Downstream of joint

Figure 74. Joint of Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2 prior to testing



(a) Traffic face at joint



(b) Field side at joint

MASH Test 3-11 (Crash Test No. 606861-3)

Test Designation and Actual Impact Conditions

MASH Test 3-11 involved a 2270P vehicle weighing 5000 lbs \pm 110 lbs impacting the CIP of the bridge barrier at an impact speed of 62 mi/h \pm 2.5 mi/h and an angle of 25 degrees \pm 1.5 degrees. The CIP for MASH Test 3-11 on the Louisiana Retrofit post and beam bridge rail with safety walk Option 2 was determined to be 4.3 ft. upstream of the centerline of the second open joint in the deck/beam. Figure 46 and Figure 75 depict the target CIP.

Figure 75. Test vehicle/bridge rail geometrics for Test No. 606861-3



(a) Frontal view of 2270P test vehicle at target impact point

(b) Rear view of 2270P test vehicle at target impact point

The 2270P vehicle used in the test weighed 5056 lbs, and the actual impact speed and angle were 62.7 mi/h and 25.0 degrees. The actual impact point was 4.8 ft. upstream of the centerline of the second open joint in the concrete deck/beam. Minimum target IS was 106 kip-ft., and actual IS was 119 kip-ft.

Weather Conditions

The test was performed on the morning of December 14, 2020. Weather conditions at the time of testing were as follows: wind speed: 6 mi/h; wind direction: 4 degrees (vehicle was travelling at a heading of 150 degrees); temperature: 42°F; relative humidity: 83 percent

Test Vehicle

Figure 76 shows the 2014 RAM 1500 pickup truck used for the crash test. The vehicle's test inertia weight was 5056 lbs, and its gross static weight was 5221 lbs. The height to the lower edge of the vehicle bumper was 11.75 in., and the height to the upper edge of the bumper was 27.0 in. The height to the vehicle's center of gravity was 28.5 in. Figure 127 and Figure 128 in Appendix J give additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.

Figure 76. Test vehicle prior to Test No. 606861-3



(a) Right side of 2270P test vehicle

(b) Left side of 2270P test vehicle

Test Description

Table 20 lists times and significant events that occurred during Test No. 606861-3. Figure 129 through Figure 131 in Appendix J present sequential photographs during the test.

Table 20. Events during Test No. 606861-3

Time (s)	Events
0.0000	Data acquisition trigger activated by curb
0.0220	Vehicle impacted the bridge rail
0.0410	Vehicle begins to redirect
0.1380	Left front tire lifts off pavement
0.2130	Vehicle travelling parallel to bridge rail
0.2600	Left front tire contacts pavement
0.2700	Left rear tire lifts off pavement
0.3700	Right front tire contacts pavement
0.4540	Vehicle loses contact with installation while traveling at 50.2 mi/h, at a trajectory angle of 4.2 degrees, and a heading angle of 7.8 degrees

For longitudinal barriers, it is desirable that the vehicle redirects and exits the barrier within the exit box criteria (not less than 32.8 ft. downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in MASH.

Brakes on the vehicle were applied at 3.0 s after impact, and the vehicle subsequently came to rest 221 ft. downstream of the impact 40 ft. toward traffic lanes.

Damage to Test Installation

Figure 77 through Figure 79 show the damage to the Option 2 bridge rail. There was some gouging and scuffing of the sidewalk at impact. The concrete deck and posts had significant damage at posts 5, 6, 7, and 8, with exposed rebar at posts 6, 7, and 8. There were several large cracks at the top of posts 6 and 7. There was also some scuffing on the metal rail element. Working width¹⁴ was 38.7 in., and height of the working width was 28.0 in. Maximum dynamic deflection during the test was 6.8 in., and maximum permanent deformation was 3.4 in.

Figure 77. Option 2 bridge rail after Test No. 606861-3



(a) Bridge rail/test vehicle after test

(b) Traffic side of bridge rail at impact

¹⁴ Per MASH, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.

Figure 78. Damage to traffic face of bridge rail after Test No. 606861-3



(a) Traffic side at impact point



(b) Traffic side of joint



(c) Traffic side of posts at joint



(d) Traffic side loss of contact

Figure 79. Damage on field side of bridge rail after Test No. 606861-3



(a) Field side of joint

(b) Field side of middle post

Damage to Test Vehicle

Figure 80 shows the damage sustained by the vehicle. The front bumper, grill, hood, radiator and support, right front fender, right front tire and rim, right front and rear doors, right rear cab corner, right rear exterior bed, right rear tire, and rear bumper were damaged. Maximum exterior crush to the vehicle was 11.0 in. in the front plane at the right front corner at bumper height. No occupant compartment deformation was observed. Figure 81 shows the interior of the vehicle. Figure 132 and Figure 133 in Appendix J provide exterior crush and occupant compartment measurements.

Figure 80. Test vehicle after Test No. 606861-3



(a) Front of 2270P test vehicle after test

(b) Right front of 2270P test vehicle

Figure 81. Interior of test vehicle after Test No. 606861-3



(b) Interior of cab of 2270P test vehicle

(a) Right front floor pan of 2270P test vehicle

Occupant Risk Factors

Data from the accelerometer, located at the vehicle center of gravity, were digitized for evaluation of occupant risk and results are shown in Table 21. Figure 82, Table 22, and Table 23 summarize these data and other pertinent information from the test. Figure 134 in Appendix J shows the vehicle angular displacements, and Figure 135 through Figure 137 in Appendix J show acceleration versus time traces.

Table 21. Occupant risk factors for Test No. 606861-3

Occupant Risk Factor	Value	Time
OIV		
Longitudinal	13.1 ft/s	at 0.1207 s on right side of interior
Lateral	24.6 ft/s	
Occupant Ridedown Accelerations		
Longitudinal	6.1 g	0.1215 - 0.1315 s
Lateral	8.2 g	0.2089 - 0.2189 s
THIV	8.7 m/s	at 0.1183 s on right side of interior
ASI	1.8	0.0851 - 0.1351 s
Maximum 50-ms Moving Average		
Longitudinal	-5.4 g	0.0746 - 0.1246 s
Lateral	-14.0 g	0.0565 - 0.1065 s
Vertical.....	1.8 g	0.2949 - 0.3449 s
Maximum Roll, Pitch, and Yaw Angles		
Roll.....	7 degrees	0.6206 s
Pitch	9 degrees	0.5326 s
Yaw	34 degrees	0.7969 s

Figure 82. Summary of results for MASH Test 3-11 On Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2



(a) 0.000 s




(b) 0.200 s




(c) 0.400 s



(d) 0.600 s



(e) Impact summary



(f) Cross-section of bridge rail

Table 22. Summary of results for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2—Pre-Impact Information

General Information	
Test Agency	Texas A&M Transportation Institute
Test Standard Test No.	MASH Test 3-11
TTI Test No.	606861-3
Test Date	2020-12-14
Test Article	
Type	Longitudinal Barrier—Bridge Rail
Name	Louisiana Retrofit post and beam bridge rail with safety walk Option 2
Installation Length	106 ft.-10¾ in.
Material or Key Elements	Reinforced cantilevered concrete deck, with 10-in. high sidewalk, curb and posts topped by a concrete beam, 2 rectangular hollow steel rails secured to concrete beam
Foundation Type/Condition	Concrete Bridge Deck, Damp
Test Vehicle	
Type/Designation	2270P
Make and Model	2014 RAM 1500
Curb	5056 lbs.
Test Inertial	5056 lbs.
Dummy	165 lbs.
Gross Static	5221 lbs.
Impact Conditions	
Speed	62.7 mi./h
Angle	25.0 degrees
Location	4.8 ft. upstream of second joint
Impact Severity	119 kip-ft.
Exit Conditions	
Speed	50.2 mi./h
Exit Trajectory/Heading	4.2 degrees/7.8 degrees

Table 23. Summary of results for MASH Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2—Post-Impact Information

Occupant Risk Values	
Longitudinal OIV	13.1 ft/s
Lateral OIV	24.6 ft/s
Longitudinal Ridedown	6.1 g
Lateral Ridedown	8.2 g
THIV	8.7 m/s
ASI	1.8
Max. 0.050-s Average	
Longitudinal	-5.4 g
Lateral	-14.0 g
Vertical	1.8 g
Post-Impact Trajectory	
Stopping Distance	221 ft. downstream / 40 ft. toward traffic lanes
Vehicle Stability	
Maximum Roll Angle	7 degrees
Maximum Pitch Angle	9 degrees
Maximum Yaw Angle	34 degrees
Vehicle Snagging	No
Vehicle Pocketing	No
Test Article Deflections	
Dynamic	6.8 in.
Permanent	3.4 in.
Working Width	38.7 in.
Height of Working Width	28.0 in.
Vehicle Damage	
VDS	01RFQ5
CDC	01FREW4
Max Exterior Deformation	11.0 in.
OCDI	RF0000000
Max Occupant Compartment Deformation	None

MASH Test 3-10 (Crash Test No. 606861-4)

Test Designation and Actual Impact Conditions

MASH Test 3-10 involves an 1100C vehicle weighing 2420 lbs \pm 55 lbs impacting the CIP of the bridge barrier at an impact speed of 62 mi/h \pm 2.5 mi/h and an angle of 25 degrees \pm 1.5 degrees. The CIP for MASH Test 3-10 on the Louisiana Retrofit post and beam bridge rail with safety walk Option 2 was 3.6 ft. \pm 1 ft. upstream of the centerline of the fourth open joint in the deck/beam. Figure 45 and Figure 83 depict the target impact point.

Figure 83. Test vehicle/bridge rail geometries for Test No. 606861-4



(a) Frontal view of 1100C test vehicle at target impact point

(b) Field side view of 1100C test vehicle at target impact point

The 1100C vehicle used in the test weighed 2404 lbs, and the actual impact speed and angle were 61.5 mi/h and 25.7 degrees. The actual impact point was 3.7 ft. upstream of the centerline of the fourth open joint in the deck/beam. Minimum target IS was 51 kip-ft., and actual IS was 57 kip-ft.

Weather Conditions

The test was performed on the morning of December 11, 2020. Weather conditions at the time of testing were as follows: wind speed: 5 mi/h; wind direction: 215 degrees (vehicle was travelling at a heading of 150 degrees); temperature: 64°F; relative humidity: 100 percent.

Test Vehicle

Figure 84 shows the 2014 Nissan Versa used for the crash test. The vehicle's test inertia weight was 2404 lbs, and its gross static weight was 2569 lbs. The height to the lower edge of the vehicle bumper was 7.0 in., and the height to the upper edge of the bumper was 22.25 in. Figure 138 in Appendix K gives additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.

Figure 84. Test vehicle before Test No. 606861-4



(a) Right side of 1100C test vehicle

(b) Left side of 1100C test vehicle

Test Description

Table 24 lists events that occurred during Test No. 606861-4. Figure 139 through Figure 141 in Appendix K present sequential photographs during the test.

Table 24. Events during Test No. 606861-4

Time (s)	Events
0.0000	Vehicle impacts curb
0.0160	Right front tire lifts off of the pavement
0.0310	Vehicle begins to redirect
0.0330	Right front bumper contacts bridge rail
0.0990	Left front tire lifts off of the pavement
0.1570	Left rear tire lifts off of pavement
0.1990	Vehicle travelling parallel to bridge rail
0.2130	Right rear bumper contacts bridge rail
0.4160	Vehicle loses contact with bridge rail while traveling at 53.2 mi/h, trajectory angle of 5.5 degrees, and heading angle of 10.7 degrees

For longitudinal barriers, it is desirable that the vehicle redirects and exits the barrier within the exit box criteria (not less than 32.8 ft. downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in MASH. Brakes on the vehicle were applied at 2.75 s, and the vehicle subsequently came to rest 175 ft. downstream of the impact and 11 ft. toward traffic lanes.

Damage to Test Installation

Figure 85 through Figure 87 show the damage to the Option 2 bridge rail. There was some gouging and scuffing of the sidewalk at the point of impact, and the curb cracked at posts 12, 13, and 14. The cracks at posts 12 and 13 extended from the traffic side of the curb to the field side, and under the deck 11 in. at post 12 and 9 in. at post 13. The posts were also cracked at posts 12 and 13. At post 14, the curb and post were cracked on the field side. There was also some scuffing on the rail. Working width¹⁵ was 33.0 in., and

¹⁵ Per MASH, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.

height of working width was 4.6 in. Maximum dynamic deflection during the test was 1.8 in., and maximum permanent deformation was 0.6 in.

Figure 85. Option 2 ridge rail after Test No. 606861-4



(a) Bridge rail/test vehicle after test



(b) Traffic side of bridge rail at impact

Figure 86. Damage to traffic face of bridge rail after Test No. 606861-4



(a) Traffic side at impact point



(b) Traffic side of joint



(c) Traffic side of posts at joint



(d) Traffic side loss of contact

Figure 87. Damage on field side of bridge rail after Test No. 606861-4



(a) Field side upstream of joint

(b) Field side downstream of joint

Damage to Test Vehicle

Figure 88 shows the damage sustained by the vehicle. The front bumper, grill, hood, radiator and support, right front fender, right front tire and rim, right strut and tower, right front and rear doors, right rear quarter panel, right rear tire and rim, and rear bumper were damaged. Maximum exterior crush to the vehicle was 9.0 in. in the front plane at the right front corner at bumper height. Maximum occupant compartment deformation was 0.5 in. in the right front floor pan and right front kick panel area. Figure 89 shows the interior of the vehicle. Figure 142 and Figure 143 in Appendix K provide exterior crush and occupant compartment measurements.

Figure 88. Test vehicle after Test No. 606861-4



(a) Front of 1100C test vehicle after test

(b) Right front of 1100C test vehicle

Figure 89. Interior of test vehicle after Test No. 606861-4



(c) Interior of cab of 1100C

(a) Right front floor pan of 1100C test vehicle

Occupant Risk Factors

Data from the accelerometer, located at the vehicle center of gravity, were digitized for evaluation of occupant risk and results are shown in Table 25. Figure 90, Table 26, and Table 27 summarize these data and other pertinent information from the test. Figure 144 in Appendix K shows the vehicle angular displacements, and Figure 145 through Figure 147 in Appendix K show acceleration versus time traces.

Table 25. Occupant risk factors for Test No. 606861-4

Occupant Risk Factor	Value	Time
OIV		
Longitudinal	19.7 ft/s	at 0.1069 s on right side of interior
Lateral	31.2 ft/s	
Occupant Ridedown Accelerations		
Longitudinal	4.0 g	0.1383 - 0.1483 s
Lateral	8.6 g	0.2297 - 0.2397 s
THIV	11.0 m/s	at 0.1049 s on right side of interior
ASI	2.1	0.0830 - 0.1330 s
Maximum 50-ms Moving Average		
Longitudinal	-8.8 g	0.0509 - 0.1009 s
Lateral	-16.0 g	0.0561 - 0.1061 s
Vertical	-3.6 g	0.0224 - 0.0724 s
Maximum Roll, Pitch, and Yaw Angles		
Roll.....	12 degrees	2.5000 s
Pitch.....	16 degrees	0.5178 s
Yaw	46 degrees	0.9913 s

Figure 90. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety walk Option 2



(a) 0.000 s




(b) 0.200 s




(c) 0.400 s



(d) 0.600 s



(e) Impact summary



(f) Cross-section of bridge rail

Table 26. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety walk Option 2—Pre-Impact Information

General Information	
Test Agency	Texas A&M Transportation Institute
Test Standard Test No.	MASH Test 3-10
TTI Test No.	606861-4
Test Date	2020-12-11
Test Article	
Type	Longitudinal Barrier—Bridge Rail
Name	Louisiana Retrofit post and beam bridge rail with safety walk Option 2
Installation Length	106 ft.-10¾ in.
Material or Key Elements	Reinforced cantilevered concrete deck, with 10-in. high sidewalk with curb and posts topped by a concrete beam, with two retrofit rectangular hollow steel rails secured to concrete beam
Foundation Type/Condition	Concrete Bridge Deck, Damp
Test Vehicle	
Type/Designation	1100C
Make and Model	2014 Nissan Versa
Curb	2343 lbs.
Test Inertial	2404 lbs.
Dummy	165 lbs.
Gross Static	2569 lbs.
Impact Conditions	
Speed	61.5 mi/h
Angle	25.7 degrees
Location	3.7 ft. upstream of fourth joint
Impact Severity	57 kip-ft.
Exit Conditions	
Speed	53.2 mi/h
Exit Trajectory/Heading	5.5 degrees/10.7 degrees

Table 27. Summary of results for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2—Post-Impact Information

Occupant Risk Values	
Longitudinal OIV	19.7 ft/s
Lateral OIV	31.2 ft/s
Longitudinal Ridedown	4.0 g
Lateral Ridedown	8.6 g
THIV	11.0 m/s
ASI	2.1
Max. 0.050-s Average	
Longitudinal	-8.8 g
Lateral	-16.0 g
Vertical	-3.6 g
Post-Impact Trajectory	
Stopping Distance	175 ft. downstream 11 ft. toward traffic lanes
Vehicle Stability	
Maximum Roll Angle	12 degrees
Maximum Pitch Angle	16 degrees
Maximum Yaw Angle	46 degrees
Vehicle Snagging	No
Vehicle Pocketing	No
Test Article Deflections	
Dynamic	1.8 in.
Permanent	0.6 in.
Working Width	33.0 in.
Height of Working Width	4.6 in.
Vehicle Damage	
VDS	01RFQ5
CDC	01FREW4
Max Exterior Deformation	9.0 in.
OCDI	RF0000000
Max Occupant Compartment Deformation	0.5 in.

Discussion of Results for MASH TL-3 Tests on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2

Table 28 and Table 29 show that the Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk performed acceptably and met the specifications for MASH TL-3 longitudinal barriers.

Table 28. Performance evaluation summary for Test 3-11 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2

Evaluation Factors	Evaluation ¹⁶ Criteria	Test Results	Assessment
Structural Adequacy	A.	The Louisiana Retrofit post and beam bridge rail with safety walk Option 2 contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 6.8 in.	Pass
Occupant Risk	D.	The concrete curb and posts fractured into several pieces. However, these fragments did not penetrate or show potential for penetrating the occupant compartment, or present undue hazard for others on the bridge barrier (several fragments came to rest below the bridge deck). No occupant compartment deformation was observed.	Pass
	F.	The 2270P vehicle remained upright during and after the collision event. Maximum roll was 7 degrees and pitch was 9 degrees.	Pass
	H.	Longitudinal OIV was 13.1 ft/s, and lateral OIV was 24.6 ft/s.	Pass
	I.	Maximum longitudinal occupant ridedown was 6.1 g, and maximum lateral occupant ridedown was 8.2 g.	Pass

¹⁶ See Table 9 for details of respective evaluation criteria.

Table 29. Performance evaluation summary for MASH Test 3-10 on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2

Evaluation Factors	Evaluation ¹⁷ Criteria	Test Results	Assessment
Structural Adequacy	A.	The Louisiana Retrofit post and beam bridge rail with safety walk Option 2 contained and redirected the 1100C vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 1.8 in.	Pass
Occupant Risk	D.	No detached elements, fragments, or other debris was present to penetrate or show potential for penetrating the occupant compartment, or present undue hazard for others on the bridge barrier. Maximum occupant compartment deformation was 0.5 in. in the right floor pan/kick panel area.	Pass
	F.	The 1100C vehicle remained upright during and after the collision event. Maximum roll was 12 degrees and pitch was 16 degrees.	Pass
	H.	Longitudinal OIV was 19.7 ft/s, and lateral OIV was 31.2 ft/s.	Pass
	I.	Maximum longitudinal occupant ridedown was 4.0 g, and maximum lateral occupant ridedown was 8.6 g.	Pass

¹⁷ See Table 9 for details of respective evaluation criteria.

Developing Retrofitting Methods and Procedures for Single Bridge Rail Design

Summary of Results of Full-Scale Crash Testing

For this project, a new retrofit bridge rail was designed and successfully crash tested with respect to MASH Test Level 3. The retrofit bridge rail design was developed from typical details used on existing safety walk bridge barrier railing systems used on vintage Louisiana bridges. Details of the bridge rail retrofit constructed and tested for this project are shown in Figure 91 through Figure 100. In December, 2020, two crash tests, MASH Test 3-10 and 3-11, were performed on the new retrofit design shown in Appendix F. Both crash tests were successful with respect to MASH TL-3 specifications.

Installation of MASH TL-3 of Option 2 Retrofit Bridge Rail

The retrofit bridge rail presented on the drawings in this report has been successfully crash tested to MASH TL-3 Specifications. The following installation procedure can be used to assist in installing the retrofit bridge rail on existing DOTD bridges with vintage concrete post and beam or solid concrete parapet bridge rails with safety walks. This retrofit bridge rail attaches to the top of a concrete post and rail or solid concrete parapet as shown in the previous figures. The retrofit bridge rail is located in front of the concrete bridge rail and still preserves much of the walkway area. In some cases, any existing attachments on top of the existing concrete barriers in the field should be removed to provide the necessary clearance for the new retrofit bridge rail as presented herein. In no way shall existing hardware remain in place, or be added other than what is shown on the “as-tested” test installation drawings as presented in Appendix F. Please refer to the section below for all material specifications required for the retrofit bridge rail to be used on all MASH TL-3 retrofit applications using this design.

Installation Procedure

1. Figure 91 shows a view of the simulated Louisiana safety walk bridge barrier railing system with concrete deck cantilever (TTI simulated crash test installation) without the retrofit bridge rail.

Figure 91. Safety walk barrier with concrete post and beam bridge rail



2. Drill and install adhesive anchors for L6×4×½ angle support brackets on top of concrete bridge rail. These holes shall be drilled and the anchors installed as per the manufacturer's specifications. Hilti RE500-V3 adhesive shall be used for these ¾-in. diameter by 8 in. long anchors. The anchors shall be embedded 6 in. minimum. These anchors shall be A193-B7 galvanized threaded rods installed typically using 52 in. maximum spacing on the top of the barrier as shown in the drawings provided herein. For the solid concrete parapet design Option shown in Figures 70 to 72, the anchors shall be embedded 10 in. minimum. Photographs of the adhesive anchoring system used for this project and recommended for use for this retrofit design are provided in Figure 92 and Figure 93.

Figure 92. Hot dipped A193 B7 ¾-in. diameter Hilti threaded rod



Figure 93. Hilti HIT-RE500-V3 Adhesive Anchoing System used (anchor bolts installed as per manufacturer's specifications)



3. Install L6×4×½ angle brackets and allow complete cure time as per Hilti HIT-RE500-V3 specifications. Figure 94 shows the bracket installed. The bracket shall be installed with the 4-in. angle face flush (even) with the face of the existing concrete barrier as shown in the photos and drawings. Please note, the concrete bridge rail is flush with the face of the support angle to provide a good uniform bearing surface for the new retrofit bridge rail. Also note, two additional holes

were provided in the L6×4×½ angle. These holes can be used if rebar is encountered in the drilling operation using the center hole in the angle.

Figure 94. Installed L6×4×½ angle support bracket with ¾-in. A193 B7 galvanized threaded rod with Hilti RE500-V3 adhesive



4. Install/connect the top HSS10×4×¾ rail to the L6×4×½ angle support brackets. At each bracket location, the top rail element is attached to the bracket using a single round head 5/8-in. diameter x 5 ½ in. long bolt. Some temporary shoring support might be required to bolt this top rail element to the L6×4×½ angle support bracket. Figure 95 shows the top rail installed with the temporary shoring. Installation of the top rail should progress from one end of the bridge installation to the other adding bridge rail splices and additional rail elements as you proceed toward the opposite end of the bridge.

Figure 95. Installation of first/top rail element with temporary shoring support



5. Install lower HSS10×4× $\frac{3}{8}$ rail element by connecting lower element to top rail element using $\frac{5}{8}$ -in. × 22 in. long B7 threaded rods with F436 washers and two hex nuts. Figure 96 shows the lower rail installation.

Figure 96. Installation of lower HSS10×4× $\frac{3}{8}$ rail and bolting to top rail with $\frac{5}{8}$ -in. diameter B7 threaded rods



Figure 97 shows the installation of a typical splice joint assembly as installation of the rail progresses from one end of the installation (bridge) to the other. Photos of the completed rail section are shown in Figure 98 through Figure 100. From start to finish (after curing of the adhesive anchors), installation of the bridge rail installation was completed within 3 hours.

Figure 97. Typical splice assembly of rail prior to adding adjacent rail section



Figure 98. Front view completed retrofit rail installation



Figure 99. End view completed retrofit rail installation



Figure 100. Field side view completed retrofit rail installation



Material Specifications for MASH TL-3 Retrofit Bridge Rail

The retrofit bridge rail design tested for this project met all the safety and performance criteria for MASH TL-3. To meet the requirements for MASH TL-3, the following material specifications shall be used for the retrofit bridge design for implementation in the field on DOTD bridges. A list of the material specifications for this retrofit bridge rail design are provided as follows. Please refer to the drawings provided in this report for further information.

- Anchor bolts – $\frac{3}{4}$ -in. diameter, 8 in. long A193 B7 hot-dipped galvanized threaded rods, embedded 6 in. minimum.
- Anchor bolt epoxy – Hilti HIT-RE500 V3 Epoxy. Anchor bolts shall be installed as per the manufacturer's specifications.
- HSS10×4× $\frac{3}{8}$ Steel Tube – ASTM A500 grade B material, hot dipped galvanized. The maximum distance of 60 ft. is recommended between splice. It is recommended that 60 ft. maximum section lengths be used.
- Joint assembly, HSS5×3× $\frac{3}{8}$ and HSS4×3× $\frac{3}{8}$ – ASTM A500 grade B material, hot dipped galvanized.
- Rail attachment bolts, round head bolt, $\frac{5}{8}$ -in. diameter × 5½ in. long attaching rail to L6×4×½ bracket angles – ASTM A449 with F436 washer and heavy hex nut, hot dipped galvanized.
- Rail connecting bolts, $\frac{5}{8}$ -in. diameter × 22 in. long bolts connecting HSS10×4× $\frac{3}{8}$ tubes – A193 B7 threaded rods, with F436 washers (2) and heavy hex nuts (2), hot-dipped galvanized.
- L6×4×½ attachment bracket – ASTM A36 material, hot-dipped galvanized.
- Splice connection bolts, ½-in. diameter × 1½-in. long – ASTM A307 material, hot-dipped galvanized.


Preliminary Transition Details for New Retrofit Bridge Rail Design for Concrete Barriers with Safety Walks

TTI received current details used for safety walk barriers from Kurt Brauner, with DOTD. Figure 101 shows the current details used for safety walk barriers. In addition, TTI has received details for the DOTD proposed transition standard. Figure 102 shows the DOTD proposed transition standard details.

TTI has developed preliminary details for two approach guardrail transitions for the retrofit bridge rail designed and successfully crash tested with respect to MASH TL-3 specifications for this project. Two concepts have been developed for this project. Option 1, as shown in Figure 103 below, utilizes similar details to the one shown in Figure 101. The transition connects directly to the steel retrofit bridge rail and concrete post and rail. The transition rail laps over the new retrofit bridge rail over a distance of approximately 20 ft. and is blocked out over this distance as shown in Figure 103. After further analyses and detailing of this transition concept, full scale crash testing will be necessary to meet the requirements of MASH TL-3 specifications.

Option 2, as shown in Figure 104 and Figure 105, connects directly to the end of the retrofit bridge rail. The retrofit bridge rails extend off the ends of the existing concrete bridge rail a sufficient length to make the connection to the steel retrofit tubular rail elements. A new tapered curb section is constructed off the bridge end and tapers the curb back and down beneath the guardrail as shown in Figure 104 and Figure 105. Some additional connection hardware will likely be necessary to connect the transition end shoe to the retrofit tubular rail elements. After further analyses and detailing of this transition concept, full scale crash testing will be necessary to meet the requirements of MASH TL-3 specifications.


Figure 103. New transition concept option 1



	Roadside Safety and Physical Security Division - Proving Ground	
	Project #606861 La DoT Bridge Retrofit	2021-02-23
Drawn by GES	Scale 1:60	Sheet 1 of 1 Transition


Q:\Accreditation-17025-2017\EIR-000 Project Files\606861-03 - LaDoT - Williams\Drafting_post test\transition2021-02-22\606861-3 Transition Drawing


Figure 104. New transition concept option 2, sheet 1



C:\accreditation-17025-2017\ER-000 Project Files\606861-03 - LaDoT - Williams\Drafting, post test\transition\2021-02-19\606861-3 Transition Drawing

Figure 105. New transition concept option 2, sheet 2



	Roadside Safety and Physical Security Division - Proving Ground		2021-08-13
	Project #606861 La DoT Bridge Retrofit	Scale 1:20	Sheet 2 of 2 Section Views

Q:\Accreditation-17025-2017\EIR-000 Project Files\606861-03 - LaDoT - Williams\Drafting_posttest\transition\2021-02-19\606861-3 Transition Drawing

Conclusions

The purpose of the tests reported herein was to assess the performance of the Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk according to the safety-performance evaluation guidelines included in MASH. The crash tests were performed in accordance with MASH TL-3, which involves an 1100C and a 2270P vehicle impacting the bridge barrier at a target impact speed of 62 mi/h and an impact angle of 25 degrees.

During MASH Test 3-10 on the Louisiana Retrofit post and beam bridge rail with safety walk Option 1, the vehicle experienced occupant ridedown accelerations above the limit of 20.49 g as specified in MASH. Table 30 shows that the bridge rail did not meet the specifications for MASH longitudinal barriers.

Table 30. Assessment summary for MASH TL-3 Tests on Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 1

Evaluation Factors	Evaluation Criteria	Test No. 606861-1	Test No. 606861-2
Structural Adequacy	A.	S	S
Occupant Risk	D.	S	S
	F.	S	S
	H.	S	S
	I.	S	U
Test No.		MASH Test 3-11	MASH Test 3-10
Pass/Fail		Pass	Fail

S = Satisfactory

U = Unsatisfactory

The bridge rail was redesigned and MASH Tests 3-10 and 3-11 were repeated. Table 31 shows the Retrofit post and beam bridge rail with safety walk Option 2 met the requirements for MASH TL-3 longitudinal barriers.

**Table 31. Assessment summary for MASH TL-3 Tests on
Louisiana Retrofit Post and Beam Bridge Rail with Safety Walk Option 2**

Evaluation Factors	Evaluation Criteria	Test No. 606861-3	Test No. 606861-4
Structural Adequacy	A.	S	S
Occupant Risk	D.	S	S
	F.	S	S
	H.	S	S
	I.	S	S
Test No.		MASH Test 3-11	MASH Test 3-10
Pass/Fail		Pass	Pass

S = Satisfactory
U = Unsatisfactory

Recommendations¹⁸

The retrofit bridge rail Option 2 as tested herein, and anchored to a safety walk concrete post and beam bridge rail as shown herein, met all the safety and performance requirements of MASH TL-3 specifications. This retrofit bridge rail is recommended for use on all concrete post and beam and solid concrete barriers with safety walks 10 in. high or less and 18 in. wide or less. The retrofit bridge rail should be installed as per the recommendations provided in this report. Please refer to the section entitled “Developing Retrofitting Methods and Procedures for Single Bridge Rail Design.” The height of the retrofit bridge rail should always be 40 in. from the roadway surface as successfully tested herein. The retrofit bridge rail shall be installed as per the specifications and procedures provided in the referenced section. In cases where the retrofit bridge using the L6×4×½ angle brackets is lower than the as tested height of 40 in., short steel baseplated posts shall be used instead of the L6×4×½ angle brackets. These short posts shall be W6×15 baseplated posts spaced on 6.0 ft. on centers (maximum) as shown on the solid concrete parapet design and presented herein, and shall be used to achieve the required height of 40 in. above the roadway surface. For the solid concrete parapet, the L6x4x1/2 angle bracket can be used if this bracket results in the steel tubes being mounted at the correct height (as-tested height of 40 in.). Otherwise, the W6x15 baseplated post is recommend to achieve this correct height. Please refer to the drawings and material specifications contained in this report for additional information.

¹⁸ The opinions/interpretations identified/expressed in this section of the report are outside the scope of TTI Proving Ground’s A2LA Accreditation.

Acronyms, Abbreviations, and Symbols


Term	Description
1100C	small (compact) test vehicle
2270P	pickup truck test vehicle
A2LA	American Association for Laboratory Accreditation
AASHTO	American Association of State Highway and Transportation Officials
ASI	Acceleration Severity Index
CDC	SAE Collision Damage Classification
CG	center of gravity
cm	centimeter(s)
FHWA	Federal Highway Administration
ft.	foot (feet)
ft./s	foot (feet)/second
g	unit of gravity
h	hour(s)
in.	inch(es)
IEC	International Electrotechnical Commission
IS	impact severity
ISO	International Standards Organization
kip-ft.	kilopound [kip] which is one thousand pounds [lbf], a unit of force, with feet [ft.], which is a unit of length
DOTD	Louisiana Department of Transportation and Development
LTRC	Louisiana Transportation Research Center
lb.	pound(s)
m	meter(s)
m/s	meters/second
MASH	<i>AASHTO Manual for Assessing Roadside Safety Hardware, Second Edition</i>
mi.	mile(s)
ms	millisecond


Term	Description
NCHRP	National Cooperative Highway Research Program
NIST	National Institute of Standards Technology
OCDI	<i>NCHRP Report 350</i> Appendix E: Occupant Compartment Deformation Index
OIV	Occupant Impact Velocity
psi	pound(s) per square inch
s	second(s)
SAE	Society of Automotive Engineers
TDAS	Tiny Data Acquisition System
THIV	Theoretical Head Impact Velocity
TRAP	Test Risk Assessment Program
TTI	Texas A&M Transportation Institute
VDS	National Safety Council Vehicle Damage Scale for Traffic Accident Investigators

References

1. AASHTO. *Manual for Assessing Roadside Safety Hardware, Second Edition*. American Association of State Highway and Transportation Officials, Washington, DC, 2016.
2. W. F. Williams, "4.3. Design & Full Scale Testing of Retrofit Bridge Rail for 24.8 Miles Long Southbound Causeway Bridge, New Orleans, Louisiana," Texas Transportation Institute, College Station, 2015


Appendix A. DOTD Bridge Rails





SITE OF ORIGINAL DEPARTMENT OF HIGHWAYS
NEW ORLEANS-PARIS ROAD HIGHWAY
FRANKLIN AVENUE - LOUISA STREET
INTERSTATE ROUTE 9 OVER REPUBLICS AVE. CANAL
DECK SLAB DETAILS


SCALE: AS NOTED
 DRAWING NO. 7-39754
 SHEET NO. 250
 DESIGNED BY: R. C. [Name obscured]



STANDARD PLAN
 CONCRETE ROAD BRIDGES AND SIDE WALKS
 APPROXIMATE ROADWAY AND SIDEWALKS
 70' AT 600' SPAN, 80' AT 60' SPAN, 55' AT 40' SPAN
 STATE OF LOUISIANA
 DEPARTMENT OF HIGHWAYS
 DIVISION OF BRIDGE ENGINEERING
 DIVISION OF ROAD ENGINEERING
 DIVISION OF TRUCK ENGINEERING
 DIVISION OF WATER ENGINEERING
 DIVISION OF AIRPORT ENGINEERING
 DIVISION OF CANAL ENGINEERING
 DIVISION OF COAST AND WATER ENGINEERING
 DIVISION OF EARTH ENGINEERING
 DIVISION OF ELECTRICAL ENGINEERING
 DIVISION OF ENVIRONMENTAL ENGINEERING
 DIVISION OF GEOTECHNICAL ENGINEERING
 DIVISION OF INDUSTRIAL ENGINEERING
 DIVISION OF MATERIALS ENGINEERING
 DIVISION OF MECHANICAL ENGINEERING
 DIVISION OF METALLURGICAL ENGINEERING
 DIVISION OF NUCLEAR ENGINEERING
 DIVISION OF OPTICAL ENGINEERING
 DIVISION OF POLYMER ENGINEERING
 DIVISION OF SAFETY ENGINEERING
 DIVISION OF STRUCTURAL ENGINEERING
 DIVISION OF THERMAL ENGINEERING
 DIVISION OF TRANSPORTATION ENGINEERING
 DIVISION OF WIND ENGINEERING

NO.	DESCRIPTION	CUBIC YARDS		LINEAL FEET		REMARKS
		CONCRETE	STEEL	CONCRETE	STEEL	
1	ABUTMENT	100	100	100	100	
2	PIER	200	200	200	200	
3	DECK	300	300	300	300	
4	WALKWAY	50	50	50	50	
5	RAILROAD	100	100	100	100	
6	PIER	200	200	200	200	
7	DECK	300	300	300	300	
8	WALKWAY	50	50	50	50	
9	RAILROAD	100	100	100	100	
10	PIER	200	200	200	200	
11	DECK	300	300	300	300	
12	WALKWAY	50	50	50	50	
13	RAILROAD	100	100	100	100	
14	PIER	200	200	200	200	
15	DECK	300	300	300	300	
16	WALKWAY	50	50	50	50	
17	RAILROAD	100	100	100	100	
18	PIER	200	200	200	200	
19	DECK	300	300	300	300	
20	WALKWAY	50	50	50	50	
21	RAILROAD	100	100	100	100	
22	PIER	200	200	200	200	
23	DECK	300	300	300	300	
24	WALKWAY	50	50	50	50	
25	RAILROAD	100	100	100	100	
26	PIER	200	200	200	200	
27	DECK	300	300	300	300	
28	WALKWAY	50	50	50	50	
29	RAILROAD	100	100	100	100	
30	PIER	200	200	200	200	
31	DECK	300	300	300	300	
32	WALKWAY	50	50	50	50	
33	RAILROAD	100	100	100	100	
34	PIER	200	200	200	200	
35	DECK	300	300	300	300	
36	WALKWAY	50	50	50	50	
37	RAILROAD	100	100	100	100	
38	PIER	200	200	200	200	
39	DECK	300	300	300	300	
40	WALKWAY	50	50	50	50	
41	RAILROAD	100	100	100	100	
42	PIER	200	200	200	200	
43	DECK	300	300	300	300	
44	WALKWAY	50	50	50	50	
45	RAILROAD	100	100	100	100	
46	PIER	200	200	200	200	
47	DECK	300	300	300	300	
48	WALKWAY	50	50	50	50	
49	RAILROAD	100	100	100	100	
50	PIER	200	200	200	200	
51	DECK	300	300	300	300	
52	WALKWAY	50	50	50	50	
53	RAILROAD	100	100	100	100	
54	PIER	200	200	200	200	
55	DECK	300	300	300	300	
56	WALKWAY	50	50	50	50	
57	RAILROAD	100	100	100	100	
58	PIER	200	200	200	200	
59	DECK	300	300	300	300	
60	WALKWAY	50	50	50	50	
61	RAILROAD	100	100	100	100	
62	PIER	200	200	200	200	
63	DECK	300	300	300	300	
64	WALKWAY	50	50	50	50	
65	RAILROAD	100	100	100	100	
66	PIER	200	200	200	200	
67	DECK	300	300	300	300	
68	WALKWAY	50	50	50	50	
69	RAILROAD	100	100	100	100	
70	PIER	200	200	200	200	
71	DECK	300	300	300	300	
72	WALKWAY	50	50	50	50	
73	RAILROAD	100	100	100	100	
74	PIER	200	200	200	200	
75	DECK	300	300	300	300	
76	WALKWAY	50	50	50	50	
77	RAILROAD	100	100	100	100	
78	PIER	200	200	200	200	
79	DECK	300	300	300	300	
80	WALKWAY	50	50	50	50	
81	RAILROAD	100	100	100	100	
82	PIER	200	200	200	200	
83	DECK	300	300	300	300	
84	WALKWAY	50	50	50	50	
85	RAILROAD	100	100	100	100	
86	PIER	200	200	200	200	
87	DECK	300	300	300	300	
88	WALKWAY	50	50	50	50	
89	RAILROAD	100	100	100	100	
90	PIER	200	200	200	200	
91	DECK	300	300	300	300	
92	WALKWAY	50	50	50	50	
93	RAILROAD	100	100	100	100	
94	PIER	200	200	200	200	
95	DECK	300	300	300	300	
96	WALKWAY	50	50	50	50	
97	RAILROAD	100	100	100	100	
98	PIER	200	200	200	200	
99	DECK	300	300	300	300	
100	WALKWAY	50	50	50	50	

C.P. 3 1-20




BILL OF MATERIAL

BAR	NO.	SIZE	LENGTH	WEIGHT	LOCATION
1	10	#4	100'-0"	1000.0	Deck
2	10	#4	100'-0"	1000.0	Deck
3	10	#4	100'-0"	1000.0	Deck
4	10	#4	100'-0"	1000.0	Deck
5	10	#4	100'-0"	1000.0	Deck
6	10	#4	100'-0"	1000.0	Deck
7	10	#4	100'-0"	1000.0	Deck
8	10	#4	100'-0"	1000.0	Deck
9	10	#4	100'-0"	1000.0	Deck
10	10	#4	100'-0"	1000.0	Deck
11	10	#4	100'-0"	1000.0	Deck
12	10	#4	100'-0"	1000.0	Deck
13	10	#4	100'-0"	1000.0	Deck
14	10	#4	100'-0"	1000.0	Deck
15	10	#4	100'-0"	1000.0	Deck
16	10	#4	100'-0"	1000.0	Deck
17	10	#4	100'-0"	1000.0	Deck
18	10	#4	100'-0"	1000.0	Deck
19	10	#4	100'-0"	1000.0	Deck
20	10	#4	100'-0"	1000.0	Deck
21	10	#4	100'-0"	1000.0	Deck
22	10	#4	100'-0"	1000.0	Deck
23	10	#4	100'-0"	1000.0	Deck
24	10	#4	100'-0"	1000.0	Deck
25	10	#4	100'-0"	1000.0	Deck
26	10	#4	100'-0"	1000.0	Deck
27	10	#4	100'-0"	1000.0	Deck
28	10	#4	100'-0"	1000.0	Deck
29	10	#4	100'-0"	1000.0	Deck
30	10	#4	100'-0"	1000.0	Deck
31	10	#4	100'-0"	1000.0	Deck
32	10	#4	100'-0"	1000.0	Deck
33	10	#4	100'-0"	1000.0	Deck
34	10	#4	100'-0"	1000.0	Deck
35	10	#4	100'-0"	1000.0	Deck
36	10	#4	100'-0"	1000.0	Deck
37	10	#4	100'-0"	1000.0	Deck
38	10	#4	100'-0"	1000.0	Deck
39	10	#4	100'-0"	1000.0	Deck
40	10	#4	100'-0"	1000.0	Deck
41	10	#4	100'-0"	1000.0	Deck
42	10	#4	100'-0"	1000.0	Deck
43	10	#4	100'-0"	1000.0	Deck
44	10	#4	100'-0"	1000.0	Deck
45	10	#4	100'-0"	1000.0	Deck
46	10	#4	100'-0"	1000.0	Deck
47	10	#4	100'-0"	1000.0	Deck
48	10	#4	100'-0"	1000.0	Deck
49	10	#4	100'-0"	1000.0	Deck
50	10	#4	100'-0"	1000.0	Deck
51	10	#4	100'-0"	1000.0	Deck
52	10	#4	100'-0"	1000.0	Deck
53	10	#4	100'-0"	1000.0	Deck
54	10	#4	100'-0"	1000.0	Deck
55	10	#4	100'-0"	1000.0	Deck
56	10	#4	100'-0"	1000.0	Deck
57	10	#4	100'-0"	1000.0	Deck
58	10	#4	100'-0"	1000.0	Deck
59	10	#4	100'-0"	1000.0	Deck
60	10	#4	100'-0"	1000.0	Deck
61	10	#4	100'-0"	1000.0	Deck
62	10	#4	100'-0"	1000.0	Deck
63	10	#4	100'-0"	1000.0	Deck
64	10	#4	100'-0"	1000.0	Deck
65	10	#4	100'-0"	1000.0	Deck
66	10	#4	100'-0"	1000.0	Deck
67	10	#4	100'-0"	1000.0	Deck
68	10	#4	100'-0"	1000.0	Deck
69	10	#4	100'-0"	1000.0	Deck
70	10	#4	100'-0"	1000.0	Deck
71	10	#4	100'-0"	1000.0	Deck
72	10	#4	100'-0"	1000.0	Deck
73	10	#4	100'-0"	1000.0	Deck
74	10	#4	100'-0"	1000.0	Deck
75	10	#4	100'-0"	1000.0	Deck
76	10	#4	100'-0"	1000.0	Deck
77	10	#4	100'-0"	1000.0	Deck
78	10	#4	100'-0"	1000.0	Deck
79	10	#4	100'-0"	1000.0	Deck
80	10	#4	100'-0"	1000.0	Deck
81	10	#4	100'-0"	1000.0	Deck
82	10	#4	100'-0"	1000.0	Deck
83	10	#4	100'-0"	1000.0	Deck
84	10	#4	100'-0"	1000.0	Deck
85	10	#4	100'-0"	1000.0	Deck
86	10	#4	100'-0"	1000.0	Deck
87	10	#4	100'-0"	1000.0	Deck
88	10	#4	100'-0"	1000.0	Deck
89	10	#4	100'-0"	1000.0	Deck
90	10	#4	100'-0"	1000.0	Deck
91	10	#4	100'-0"	1000.0	Deck
92	10	#4	100'-0"	1000.0	Deck
93	10	#4	100'-0"	1000.0	Deck
94	10	#4	100'-0"	1000.0	Deck
95	10	#4	100'-0"	1000.0	Deck
96	10	#4	100'-0"	1000.0	Deck
97	10	#4	100'-0"	1000.0	Deck
98	10	#4	100'-0"	1000.0	Deck
99	10	#4	100'-0"	1000.0	Deck
100	10	#4	100'-0"	1000.0	Deck


STANDARD PLAN
 20'-0" CONCRETE SLAB SPAN - 45° SKEW
 24'-0" CLEAR ROADWAY & 1'-6" SIDEWALKS
 To be used WITH STD. PLAN C.S. 202-15

STATE OF LOUISIANA
 DEPARTMENT OF HIGHWAYS



STANDARD PLAN
CONCRETE
STATE OF LOUISIANA
DEPARTMENT OF HIGHWAYS

BILL OF MATERIAL		LOCATION
NO.	QUANTITY	DESCRIPTION
1	1.00	CONCRETE
2	1.00	STEEL
3	1.00	WOOD
4	1.00	PAINT
5	1.00	REINFORCEMENT
6	1.00	DRAINAGE
7	1.00	ABUTMENT
8	1.00	PIERS
9	1.00	SPILLWAYS
10	1.00	WALKWAYS
11	1.00	LANDINGS
12	1.00	RAILINGS
13	1.00	GRADING
14	1.00	PAVING
15	1.00	LANDSCAPING
16	1.00	UTILITIES
17	1.00	CONCRETE
18	1.00	STEEL
19	1.00	WOOD
20	1.00	PAINT
21	1.00	REINFORCEMENT
22	1.00	DRAINAGE
23	1.00	ABUTMENT
24	1.00	PIERS
25	1.00	SPILLWAYS
26	1.00	WALKWAYS
27	1.00	LANDINGS
28	1.00	RAILINGS
29	1.00	GRADING
30	1.00	PAVING
31	1.00	LANDSCAPING
32	1.00	UTILITIES




NO.	DESCRIPTION	QUANTITY	UNIT	AMOUNT
1	CONCRETE	1000	CU YD	1000
2	STEEL	1000	LBS	1000
3	WOOD	1000	CU YD	1000
4	PAINT	1000	GALES	1000
5	LABOR	1000	HRS	1000
6	TRUCKS	1000	HRS	1000
7	CRANE	1000	HRS	1000
8	WATER	1000	CU YD	1000
9	CEMENT	1000	CU YD	1000
10	AGGREGATE	1000	CU YD	1000
11	REINFORCEMENT	1000	LBS	1000
12	FORMS	1000	SQ YD	1000
13	BRICKS	1000	1000	1000
14	ROOFING	1000	SQ YD	1000
15	GLASS	1000	SQ YD	1000
16	MECHANICAL	1000	1000	1000
17	ELECTRICAL	1000	1000	1000
18	LANDSCAPE	1000	1000	1000
19	UTILITIES	1000	1000	1000
20	CONCRETE	1000	CU YD	1000
21	STEEL	1000	LBS	1000
22	WOOD	1000	CU YD	1000
23	PAINT	1000	GALES	1000
24	LABOR	1000	HRS	1000
25	TRUCKS	1000	HRS	1000
26	CRANE	1000	HRS	1000
27	WATER	1000	CU YD	1000
28	CEMENT	1000	CU YD	1000
29	AGGREGATE	1000	CU YD	1000
30	REINFORCEMENT	1000	LBS	1000
31	FORMS	1000	SQ YD	1000
32	BRICKS	1000	1000	1000
33	ROOFING	1000	SQ YD	1000
34	GLASS	1000	SQ YD	1000
35	MECHANICAL	1000	1000	1000
36	ELECTRICAL	1000	1000	1000
37	LANDSCAPE	1000	1000	1000
38	UTILITIES	1000	1000	1000
39	CONCRETE	1000	CU YD	1000
40	STEEL	1000	LBS	1000
41	WOOD	1000	CU YD	1000
42	PAINT	1000	GALES	1000
43	LABOR	1000	HRS	1000
44	TRUCKS	1000	HRS	1000
45	CRANE	1000	HRS	1000
46	WATER	1000	CU YD	1000
47	CEMENT	1000	CU YD	1000
48	AGGREGATE	1000	CU YD	1000
49	REINFORCEMENT	1000	LBS	1000
50	FORMS	1000	SQ YD	1000
51	BRICKS	1000	1000	1000
52	ROOFING	1000	SQ YD	1000
53	GLASS	1000	SQ YD	1000
54	MECHANICAL	1000	1000	1000
55	ELECTRICAL	1000	1000	1000
56	LANDSCAPE	1000	1000	1000
57	UTILITIES	1000	1000	1000
58	CONCRETE	1000	CU YD	1000
59	STEEL	1000	LBS	1000
60	WOOD	1000	CU YD	1000
61	PAINT	1000	GALES	1000
62	LABOR	1000	HRS	1000
63	TRUCKS	1000	HRS	1000
64	CRANE	1000	HRS	1000
65	WATER	1000	CU YD	1000
66	CEMENT	1000	CU YD	1000
67	AGGREGATE	1000	CU YD	1000
68	REINFORCEMENT	1000	LBS	1000
69	FORMS	1000	SQ YD	1000
70	BRICKS	1000	1000	1000
71	ROOFING	1000	SQ YD	1000
72	GLASS	1000	SQ YD	1000
73	MECHANICAL	1000	1000	1000
74	ELECTRICAL	1000	1000	1000
75	LANDSCAPE	1000	1000	1000
76	UTILITIES	1000	1000	1000
77	CONCRETE	1000	CU YD	1000
78	STEEL	1000	LBS	1000
79	WOOD	1000	CU YD	1000
80	PAINT	1000	GALES	1000
81	LABOR	1000	HRS	1000
82	TRUCKS	1000	HRS	1000
83	CRANE	1000	HRS	1000
84	WATER	1000	CU YD	1000
85	CEMENT	1000	CU YD	1000
86	AGGREGATE	1000	CU YD	1000
87	REINFORCEMENT	1000	LBS	1000
88	FORMS	1000	SQ YD	1000
89	BRICKS	1000	1000	1000
90	ROOFING	1000	SQ YD	1000
91	GLASS	1000	SQ YD	1000
92	MECHANICAL	1000	1000	1000
93	ELECTRICAL	1000	1000	1000
94	LANDSCAPE	1000	1000	1000
95	UTILITIES	1000	1000	1000
96	CONCRETE	1000	CU YD	1000
97	STEEL	1000	LBS	1000
98	WOOD	1000	CU YD	1000
99	PAINT	1000	GALES	1000
100	LABOR	1000	HRS	1000

STANDARD PLAN
 FOR CONCRETE SLAB BRIDGE
 10-0 ROADWAY FOR SIDEWALKS
 TO BE USED WITH THE PLAN C.S. 57-20

STATE OF LOUISIANA
 DEPARTMENT OF HIGHWAYS

PROJECT NO. 1000
 CONTRACT NO. 1000
 DRAWING NO. 1000


C.S. 57-20



C-6-34

LOUISIANA HIGHWAY COMMISSION
 PROJECT: ...
 SHEET: ...

1/1 Scale: ...
 Date: ...
 No. Sheets: ...




BILL OF MATERIALS

DESCRIPTION	QUANTITY	UNIT	REMARKS
1. Steel Deck	1000	SQ. FT.	
2. Steel Girders	100	LINEAL FT.	
3. Steel Bracing	50	LINEAL FT.	
4. Steel Bolts	10000	NO.	
5. Steel Plates	500	SQ. FT.	
6. Cast Iron Drain	10	NO.	
7. Expansion Plates	10	NO.	
8. Steel Bars	100	NO.	
9. Steel Nuts	10000	NO.	
10. Steel Washers	10000	NO.	
11. Steel Angles	100	LINEAL FT.	
12. Steel Channels	100	LINEAL FT.	
13. Steel I-Beams	100	LINEAL FT.	
14. Steel Joists	100	LINEAL FT.	
15. Steel Decking	1000	SQ. FT.	
16. Steel Scaffolding	100	LINEAL FT.	
17. Steel Formwork	1000	SQ. FT.	
18. Steel Reinforcement	100	LINEAL FT.	
19. Steel Brackets	100	NO.	
20. Steel Connectors	100	NO.	
21. Steel Spacers	100	NO.	
22. Steel Clips	100	NO.	
23. Steel Lacing	100	LINEAL FT.	
24. Steel Diaphragms	100	NO.	
25. Steel Stiffeners	100	NO.	
26. Steel Girders	100	LINEAL FT.	
27. Steel Bracing	100	LINEAL FT.	
28. Steel Bolts	10000	NO.	
29. Steel Plates	500	SQ. FT.	
30. Cast Iron Drain	10	NO.	
31. Expansion Plates	10	NO.	
32. Steel Bars	100	NO.	
33. Steel Nuts	10000	NO.	
34. Steel Washers	10000	NO.	
35. Steel Angles	100	LINEAL FT.	
36. Steel Channels	100	LINEAL FT.	
37. Steel I-Beams	100	LINEAL FT.	
38. Steel Joists	100	LINEAL FT.	
39. Steel Decking	1000	SQ. FT.	
40. Steel Scaffolding	100	LINEAL FT.	
41. Steel Formwork	1000	SQ. FT.	
42. Steel Reinforcement	100	LINEAL FT.	
43. Steel Brackets	100	NO.	
44. Steel Connectors	100	NO.	
45. Steel Spacers	100	NO.	
46. Steel Clips	100	NO.	
47. Steel Lacing	100	LINEAL FT.	
48. Steel Diaphragms	100	NO.	
49. Steel Stiffeners	100	NO.	
50. Steel Girders	100	LINEAL FT.	
51. Steel Bracing	100	LINEAL FT.	
52. Steel Bolts	10000	NO.	
53. Steel Plates	500	SQ. FT.	
54. Cast Iron Drain	10	NO.	
55. Expansion Plates	10	NO.	
56. Steel Bars	100	NO.	
57. Steel Nuts	10000	NO.	
58. Steel Washers	10000	NO.	
59. Steel Angles	100	LINEAL FT.	
60. Steel Channels	100	LINEAL FT.	
61. Steel I-Beams	100	LINEAL FT.	
62. Steel Joists	100	LINEAL FT.	
63. Steel Decking	1000	SQ. FT.	
64. Steel Scaffolding	100	LINEAL FT.	
65. Steel Formwork	1000	SQ. FT.	
66. Steel Reinforcement	100	LINEAL FT.	
67. Steel Brackets	100	NO.	
68. Steel Connectors	100	NO.	
69. Steel Spacers	100	NO.	
70. Steel Clips	100	NO.	
71. Steel Lacing	100	LINEAL FT.	
72. Steel Diaphragms	100	NO.	
73. Steel Stiffeners	100	NO.	
74. Steel Girders	100	LINEAL FT.	
75. Steel Bracing	100	LINEAL FT.	
76. Steel Bolts	10000	NO.	
77. Steel Plates	500	SQ. FT.	
78. Cast Iron Drain	10	NO.	
79. Expansion Plates	10	NO.	
80. Steel Bars	100	NO.	
81. Steel Nuts	10000	NO.	
82. Steel Washers	10000	NO.	
83. Steel Angles	100	LINEAL FT.	
84. Steel Channels	100	LINEAL FT.	
85. Steel I-Beams	100	LINEAL FT.	
86. Steel Joists	100	LINEAL FT.	
87. Steel Decking	1000	SQ. FT.	
88. Steel Scaffolding	100	LINEAL FT.	
89. Steel Formwork	1000	SQ. FT.	
90. Steel Reinforcement	100	LINEAL FT.	
91. Steel Brackets	100	NO.	
92. Steel Connectors	100	NO.	
93. Steel Spacers	100	NO.	
94. Steel Clips	100	NO.	
95. Steel Lacing	100	LINEAL FT.	
96. Steel Diaphragms	100	NO.	
97. Steel Stiffeners	100	NO.	
98. Steel Girders	100	LINEAL FT.	
99. Steel Bracing	100	LINEAL FT.	
100. Steel Bolts	10000	NO.	

GENERAL NOTES

1. All work to be in accordance with the specifications for Highway Bridges, 1931 Edition, as amended.
2. The contractor shall be responsible for the design of the bridge and for the selection of materials.
3. The contractor shall be responsible for the construction of the bridge and for the maintenance of the bridge during construction.
4. The contractor shall be responsible for the safety of the bridge during construction.
5. The contractor shall be responsible for the removal of the bridge after construction.
6. The contractor shall be responsible for the cost of the bridge.
7. The contractor shall be responsible for the time of the bridge.
8. The contractor shall be responsible for the quality of the bridge.
9. The contractor shall be responsible for the quantity of the bridge.
10. The contractor shall be responsible for the location of the bridge.
11. The contractor shall be responsible for the orientation of the bridge.
12. The contractor shall be responsible for the elevation of the bridge.
13. The contractor shall be responsible for the width of the bridge.
14. The contractor shall be responsible for the depth of the bridge.
15. The contractor shall be responsible for the height of the bridge.
16. The contractor shall be responsible for the length of the bridge.
17. The contractor shall be responsible for the area of the bridge.
18. The contractor shall be responsible for the volume of the bridge.
19. The contractor shall be responsible for the weight of the bridge.
20. The contractor shall be responsible for the mass of the bridge.
21. The contractor shall be responsible for the density of the bridge.
22. The contractor shall be responsible for the specific gravity of the bridge.
23. The contractor shall be responsible for the relative density of the bridge.
24. The contractor shall be responsible for the specific weight of the bridge.
25. The contractor shall be responsible for the relative weight of the bridge.
26. The contractor shall be responsible for the specific mass of the bridge.
27. The contractor shall be responsible for the relative mass of the bridge.
28. The contractor shall be responsible for the specific volume of the bridge.
29. The contractor shall be responsible for the relative volume of the bridge.
30. The contractor shall be responsible for the specific area of the bridge.
31. The contractor shall be responsible for the relative area of the bridge.
32. The contractor shall be responsible for the specific depth of the bridge.
33. The contractor shall be responsible for the relative depth of the bridge.
34. The contractor shall be responsible for the specific height of the bridge.
35. The contractor shall be responsible for the relative height of the bridge.
36. The contractor shall be responsible for the specific length of the bridge.
37. The contractor shall be responsible for the relative length of the bridge.
38. The contractor shall be responsible for the specific width of the bridge.
39. The contractor shall be responsible for the relative width of the bridge.
40. The contractor shall be responsible for the specific depth of the bridge.
41. The contractor shall be responsible for the relative depth of the bridge.
42. The contractor shall be responsible for the specific height of the bridge.
43. The contractor shall be responsible for the relative height of the bridge.
44. The contractor shall be responsible for the specific length of the bridge.
45. The contractor shall be responsible for the relative length of the bridge.
46. The contractor shall be responsible for the specific width of the bridge.
47. The contractor shall be responsible for the relative width of the bridge.
48. The contractor shall be responsible for the specific depth of the bridge.
49. The contractor shall be responsible for the relative depth of the bridge.
50. The contractor shall be responsible for the specific height of the bridge.
51. The contractor shall be responsible for the relative height of the bridge.
52. The contractor shall be responsible for the specific length of the bridge.
53. The contractor shall be responsible for the relative length of the bridge.
54. The contractor shall be responsible for the specific width of the bridge.
55. The contractor shall be responsible for the relative width of the bridge.
56. The contractor shall be responsible for the specific depth of the bridge.
57. The contractor shall be responsible for the relative depth of the bridge.
58. The contractor shall be responsible for the specific height of the bridge.
59. The contractor shall be responsible for the relative height of the bridge.
60. The contractor shall be responsible for the specific length of the bridge.
61. The contractor shall be responsible for the relative length of the bridge.
62. The contractor shall be responsible for the specific width of the bridge.
63. The contractor shall be responsible for the relative width of the bridge.
64. The contractor shall be responsible for the specific depth of the bridge.
65. The contractor shall be responsible for the relative depth of the bridge.
66. The contractor shall be responsible for the specific height of the bridge.
67. The contractor shall be responsible for the relative height of the bridge.
68. The contractor shall be responsible for the specific length of the bridge.
69. The contractor shall be responsible for the relative length of the bridge.
70. The contractor shall be responsible for the specific width of the bridge.
71. The contractor shall be responsible for the relative width of the bridge.
72. The contractor shall be responsible for the specific depth of the bridge.
73. The contractor shall be responsible for the relative depth of the bridge.
74. The contractor shall be responsible for the specific height of the bridge.
75. The contractor shall be responsible for the relative height of the bridge.
76. The contractor shall be responsible for the specific length of the bridge.
77. The contractor shall be responsible for the relative length of the bridge.
78. The contractor shall be responsible for the specific width of the bridge.
79. The contractor shall be responsible for the relative width of the bridge.
80. The contractor shall be responsible for the specific depth of the bridge.
81. The contractor shall be responsible for the relative depth of the bridge.
82. The contractor shall be responsible for the specific height of the bridge.
83. The contractor shall be responsible for the relative height of the bridge.
84. The contractor shall be responsible for the specific length of the bridge.
85. The contractor shall be responsible for the relative length of the bridge.
86. The contractor shall be responsible for the specific width of the bridge.
87. The contractor shall be responsible for the relative width of the bridge.
88. The contractor shall be responsible for the specific depth of the bridge.
89. The contractor shall be responsible for the relative depth of the bridge.
90. The contractor shall be responsible for the specific height of the bridge.
91. The contractor shall be responsible for the relative height of the bridge.
92. The contractor shall be responsible for the specific length of the bridge.
93. The contractor shall be responsible for the relative length of the bridge.
94. The contractor shall be responsible for the specific width of the bridge.
95. The contractor shall be responsible for the relative width of the bridge.
96. The contractor shall be responsible for the specific depth of the bridge.
97. The contractor shall be responsible for the relative depth of the bridge.
98. The contractor shall be responsible for the specific height of the bridge.
99. The contractor shall be responsible for the relative height of the bridge.
100. The contractor shall be responsible for the specific length of the bridge.




LIST OF MATERIAL




NO.	DESCRIPTION	QUANTITY	UNIT	REMARKS
1	Steel Deck	1000	Sq. Ft.	
2	Steel Girders	100	Lbs.	
3	Steel Bolts	1000	Each	
4	Steel Nuts	1000	Each	
5	Steel Washers	1000	Each	
6	Steel Plates	100	Sq. Ft.	
7	Steel Channels	100	Lbs.	
8	Steel Angles	100	Lbs.	
9	Steel Bars	100	Lbs.	
10	Steel Pipes	100	Lbs.	
11	Steel Castings	100	Lbs.	
12	Steel Rivets	1000	Each	
13	Steel Screws	1000	Each	
14	Steel Brackets	100	Each	
15	Steel Connectors	100	Each	
16	Steel Spacers	100	Each	
17	Steel Straps	100	Each	
18	Steel Clips	100	Each	
19	Steel Pins	100	Each	
20	Steel Keys	100	Each	
21	Steel Cotter Pins	100	Each	
22	Steel Lock Washers	100	Each	
23	Steel Split Lock Washers	100	Each	
24	Steel Flat Washers	100	Each	
25	Steel Round Washers	100	Each	
26	Steel Square Washers	100	Each	
27	Steel Hex Washers	100	Each	
28	Steel Oval Washers	100	Each	
29	Steel Triangular Washers	100	Each	
30	Steel Circular Washers	100	Each	
31	Steel Rectangular Washers	100	Each	
32	Steel Elliptical Washers	100	Each	
33	Steel Diamond Washers	100	Each	
34	Steel Square Washers	100	Each	
35	Steel Round Washers	100	Each	
36	Steel Square Washers	100	Each	
37	Steel Round Washers	100	Each	
38	Steel Square Washers	100	Each	
39	Steel Round Washers	100	Each	
40	Steel Square Washers	100	Each	

STANDARD PLAN
A.C. DEER GARDEN - HIS BRIDGES
 HIS BRIDGES - HIS BRIDGES
 HIS BRIDGES - HIS BRIDGES

STATE OF LOUISIANA
 DEPARTMENT OF HIGHWAYS





3 - 1/2" DIA. BARS
 391(0) ST-100 IN. QUANTITY 105



ESTIMATED QUANTITIES (ONE YEAR)
 BAR SIZE #1 QUANTITY 391(0) LOCATION










BAR SIZE #1	QUANTITY	LOCATION
1	391(0)	SECTION 1-1
2	391(0)	SECTION 2-2
3	391(0)	SECTION 3-3
4	391(0)	SECTION 4-4
5	391(0)	SECTION 5-5
6	391(0)	SECTION 6-6
7	391(0)	SECTION 7-7
8	391(0)	SECTION 8-8
9	391(0)	SECTION 9-9
10	391(0)	SECTION 10-10
TOTAL	391(0)	TOTAL QUANTITY



GENERAL NOTE: REINFORCEMENT SHALL BE PLACED AS SHOWN UNLESS OTHERWISE NOTED.
 ALL REINFORCEMENT SHALL BE 1/2" DIA. BARS UNLESS OTHERWISE NOTED.
 ALL REINFORCEMENT SHALL BE PLACED AS SHOWN UNLESS OTHERWISE NOTED.

STATE OF LOUISIANA
 DEPARTMENT OF HIGHWAYS
 BRIDGE DESIGN SECTION
 PROJECT NO. 90-28PA(MOD)66

ESTIMATED QUANTITIES (ONE SPAN)				LOCATION
BAR SIZE	NO.	UNIT	LENGTH	
A # 8	52	20'-0"	1085.2'	BOTTOM OF SLAB
B # 6	40	19'-7"	891.5'	BOTTOM OF SLAB
TOTAL # 6 BARS			1965.7'	728.7' BOTTOM OF SLAB
TOTAL # 8 BARS			1085.2'	1095.3' TOP OF SLAB
C # 4	50	19'-7"	985.0'	TOP OF SLAB WALKERS
D # 4	48	6'-9"	524.0'	RAILING PARAPET
TOTAL # 4 BARS			1754.0'	1172.3' LBS
TOTAL REINFORCING STEEL				415.3 LBS
CLASS. 2 CONCRETE FOR SUBSTRUCTURES				0.15 CUBIC YDS
CONCRETE RAILING (INTERMEDIATE SPAN)				36.23 CUBIC YDS
TOTAL # 4 BARS				42.33 LINEAL FT.



GENERAL NOTES:
 1. ALL REINFORCING STEEL SHALL BE ASTM A615, GRADE 60.
 2. ALL CONCRETE SHALL BE CLASS 2, 4000 PSI.
 3. ALL DIMENSIONS SHALL BE IN FEET AND INCHES UNLESS OTHERWISE NOTED.
 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS.
 5. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES.
 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES.
 7. THE CONTRACTOR SHALL MAINTAIN ADEQUATE DRAINAGE THROUGHOUT THE PROJECT.
 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING STRUCTURES.
 9. THE CONTRACTOR SHALL MAINTAIN ADEQUATE SAFETY THROUGHOUT THE PROJECT.
 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL ENVIRONMENTAL RESOURCES.

STANDARD PLAN
 20'-0" CONCRETE SLAB SPAN
 40'-0" ROADWAY
 90° CROSSING
 PARABOLIC CROWN
 STATE OF LOUISIANA
 DEPARTMENT OF HIGHWAYS
 DIVISION OF BRIDGE DESIGN
 DATE: JAN. 29, '71
 PROJECT NO. 200-200-001
 DRAWING NO. 200-200-001-1
 SHEET NO. 1 OF 2


REVISIONS:

REVISIONS:

REVISIONS:

REVISIONS:

REVISIONS:



MOMENTS AND REACTIONS

SPAN	TYPE	REACT. AT SUPPORTS	MOMENT AT SUPPORTS	MOMENT AT MIDSPAN
1	1	1000	1000	1000
2	2	2000	2000	2000
3	3	3000	3000	3000
4	4	4000	4000	4000
5	5	5000	5000	5000
6	6	6000	6000	6000
7	7	7000	7000	7000
8	8	8000	8000	8000
9	9	9000	9000	9000
10	10	10000	10000	10000

BEAM SIZES AND DIMENSIONS

SPAN	TYPE	BEAM SIZE	DIMENSIONS
1	1	12" x 12"	12" x 12" x 12"
2	2	14" x 14"	14" x 14" x 14"
3	3	16" x 16"	16" x 16" x 16"
4	4	18" x 18"	18" x 18" x 18"
5	5	20" x 20"	20" x 20" x 20"
6	6	22" x 22"	22" x 22" x 22"
7	7	24" x 24"	24" x 24" x 24"
8	8	26" x 26"	26" x 26" x 26"
9	9	28" x 28"	28" x 28" x 28"
10	10	30" x 30"	30" x 30" x 30"

QUANTITIES

ITEM	DESCRIPTION	QUANTITY
1	STEEL JOIST	1000
2	STEEL JOIST	2000
3	STEEL JOIST	3000
4	STEEL JOIST	4000
5	STEEL JOIST	5000
6	STEEL JOIST	6000
7	STEEL JOIST	7000
8	STEEL JOIST	8000
9	STEEL JOIST	9000
10	STEEL JOIST	10000


ORDER OF AWARDING CHECK
 PARISH ROAD OVERPASS (STA. 701+13.55)
 100' O. SPAN (20' x 20' SPANS)
 24'-0" ROADWAY
 1'-6" SIDEWALKS
 90'-CRISIS
 PARABOLIC CROWN

STATE OF LOUISIANA
 DEPARTMENT OF HIGHWAYS

SCIRC-90-94P

Appendix B. Details of Louisiana Retrofit Post and Beam with Safety Walk for Tests 606861-1&2


C:\Accreditation-17025-2017\FIR-000 Project Files\606861-03 - Lab 01 - Williams\Drawing, 606861-1-2\606861-1-2 Drawing



Texas A&M Transportation Institute
Roadside Safety and Physical Security Division - Proving Ground




Project #606861-1-2 LADOT Bridge Rail Retrofit 2018-08-02

Drawn by SM/GS Scale 1:10 Sheet 8 of 10 Rebar Placement 3



	Roadside Safety and Physical Security Division - Proving Ground	2018-08-02
	Project #606861 1-2 LADOTD Bridge Rail Retrofit	Sheet 2 of 10 Rail Details
Drawn by SM/GS	Scale 1:30	

Rail Splice



- 3a. Galvanize after all fabrication is complete.
- 3b. Contractor shall provide material certs for all steel components.




Roadside Safety and
Physical Security Division -
Proving Ground

Project #606861 1-2 LADOT Bridge Rail Retrofit

2018-08-02

Drawn by SM/GS Scale 1:5

Sheet 3 of 10 Rail Splice



**Texas A&M
Transportation
Institute**

Roadside Safety and
Physical Security Division -
Proving Ground

Project #606861 1-2 LADOTD Bridge Rail Retrofit

Drawn by SM/GS


Scale 1:150

Sheet 4 of 10

Concrete Details


2018-08-02

Concrete Section




- 5a.** R1/2" this edge. Drip Stop and other exposed concrete edges as shown 3/4" each way.
- 5b.** Wall is 12" for 75', then 32" thick to end of installation. The Existing Working Slab is also 75' long. Incorporate additional length in New Working Slab, with same rebar.
- 5c.** Concrete strength is 3,000 psi.
- 5d.** A cold joint in the concrete is permissible here, with minimum 3 days cure time between pours (or when the first pour has reached 1500 psi compressive strength).

	Roadside Safety and Physical Security Division - Proving Ground	2018-08-02
	Project #606861 1-2 LADOT Bridge Rail Retrofit Drawn by SM/GS Scale 1:15	Sheet 5 of 10 Concrete Section




	Roadside Safety and Physical Security Division - Proving Ground	2018-08-02
	Project #606861 1-2 LADOT Bridge Rail Retrofit	Sheet 6 of 10 Rebar Placement 1
Drawn by SM/GS	Scale 1:15	

Rebar Placement 2




Elevation View



	Roadside Safety and Physical Security Division - Proving Ground	2018-08-02
	Project #606861 1-2 LADOT Bridge Rail Retrofit Drawn by SM/GS Scale 1:30	Sheet 7 of 10 Rebar Placement 2



	Roadside Safety and Physical Security Division - Proving Ground
	Project #606861 1-2 LADOT Bridge Rail Retrofit 2018-08-02 Drawn by SM/GS Scale 1:10 Sheet 9 of 10 Rebar Detail 1



	Roadside Safety and Physical Security Division - Proving Ground	2018-08-02
	Project #606861 1-2 LADOT Bridge Rail Retrofit	Sheet 8 of 10 Rebar Placement 3
Drawn by SM/GS Scale 1:10		



	Roadside Safety and Physical Security Division - Proving Ground		2018-08-02
	Project #608861 1-2 LADOT Bridge Rail Retrofit	Scale 1:10	Sheet 10 of 10 Rebar Detail 2

Appendix C. Supporting Certification Documents for Test No. 606861-1&2

Page: 2

CERTIFIED MILL TEST REPORT

NUCOR
NUCOR CORPORATION
NUCOR STEEL TEXAS

SOLD TO: KATY STEEL
PO BOX 735
KATY, TX 77492-

SHIP TO: KATY STEEL-CUSTOMER PU
N/A
KATY, TX 77492-

Ship from:
MTR #: 0000335081
Nucor Steel - Texas
8812 Hwy 79 W
JEWETT, TX 75846
800-527-6445

Date: 11-May-2018
B.L. Number: 820362
Load Number: 410652

Material Safety Data Sheets are available at www.nucorbar.com or by contacting your inside sales representative. NBMG-08 January 1, 2012

LOT # HEAT #	DESCRIPTION	PHYSICAL TESTS				CHEMICAL TESTS												
		YIELD P.S.I.	TENSILE P.S.I.	ELONG % IN 8"	BEND	WT% DEF	C	Ni	Mn	Cr	P	Mo	S	V	Si	Cb	Cu	Sh
PO# => JW181039401 JW18103944	322637-4 Nucor Steel - Texas 10/#3 Rebar 20' A615M GR280 (Gr40) ASTM A615/A615M-14 GR 40[Z80] AASHTO M31-07	59,400 410MPa	84,200 581MPa	20.0%	OK	.23 .25	.87 .23	.014 .047	.016 .003	.20 .003	.25							

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.

- 1.) Weld repair was not performed on this material.
- 2.) Melted and Manufactured in the United States.
- 3.) Mercury, Barium, or other source materials in any form.

Rafa R. Vanturi

QUALITY

150

MILL TEST CERTIFICATE
MANUFACTURER: VINTON STEEL LLC

SOLD TO: KATY STEEL COMPANY, INC.
P. O. BOX 735
KATY TX 77492

SHIP TO: KATY STEEL COMPANY
28011 HW 90
KATY TX 77494

MATERIAL: RV13040B13PA #4 X 20' GRADE 40 (ASTM A615) (ASTM A615/A615M)
DELIVERY LIST NUMBER:
P.O. CUSTOMER NUMBER: 417207

PROGRAM NUMBER: 0080665407

ISSUING DATE: 25.06.2018
CERTIFICATE NUMBER: 55757
PAGE: 1/1

MECHANICAL PROPERTIES

HEAT NUMBER	YIELD STRENGTH psi	TENSILE STRENGTH psi	PERCENT ELONGATION %	BEND	ACTUAL W. PER FOOT lb/ft
1811351	52483	81011	19	ACCEPTABLE	0.642

CHEMICAL COMPOSITION

HEAT NUMBER	C %	Mn %	P %	S %	Si %	Ni %	Cr %	Mo %	Cu %	V %	Ca %	CE %
1811351	0.3000	0.5454	0.0294	0.0325	0.1930	0.1423	0.1535	0.0199	0.2396	0.0000	0.0000	0.4180

WE HEREBY CERTIFY THAT THE ABOVE FIGURES ARE CORRECT AS CONTAINED IN THE RECORDS OF THE COMPANY.
MELTED AND MANUFACTURED IN THE U.S.A.

This reinforcing steel meets all the requirements of the Buy America Act requirements of 23 CFR 635.410
Approved by BSGV Quality Assurance
Manual REV-20 10/09/2014

Harold Du Gano

CERTIFIED BY THE QUALITY DEPARTMENT - SIGNATURE ON FILE

MAILING ADDRESS
VINTON STEEL LLC VINTON P.O. BOX 12843
EL PASO, TEXAS 79913-0843 915 886-2000

STREET ADDRESS
1-10 & VINTON ROAD
VINTON, TEXAS 79835-9998

AL

MILL TEST CERTIFICATE
 MANUFACTURER: VINTON STEEL LLC

SOLD TO: KATY STEEL COMPANY, INC.
 P. O. BOX 735
 KATY TX 77492

SHIP TO: KATY STEEL COMPANY
 28011 HW 90
 KATY TX 77494

MATERIAL: RV16040B17PA #5 X 20' GRADE 40 (ASTM A615) (ASTM A615/A615M)
 DELIVERY LIST NUMBER:
 P.O. CUSTOMER NUMBER: 417207

PROGRAM NUMBER: 0080665407

ISSUING DATE: 25.06.2018
 CERTIFICATE NUMBER: 55756
 PAGE: 1/1

MECHANICAL PROPERTIES

HEAT NUMBER	YIELD STRENGTH psi	TENSILE STRENGTH psi	PERCENT ELONGATION %	BEND	ACTUAL W. PER FOOT lb/ft
1820222	48000	76669	21	ACCEPTABLE	0.987

CHEMICAL COMPOSITION

HEAT NUMBER	C	Mn	P	S	Si	Ni	Cr	Mo	Cu	V	Cb	CE
1820222	0.2775	0.5971	0.0145	0.0393	0.1457	0.0700	0.0995	0.0112	0.2497	-0.003	-0.001	0.3972

WE HEREBY CERTIFY THAT THE ABOVE FIGURES ARE CORRECT AS CONTAINED IN THE RECORDS OF THE COMPANY.
 MELTED AND MANUFACTURED IN THE U.S.A.

This reinforcing steel meets all the requirements of the Buy America Act requirements of 23 CFR 635.410
 Approved by BSGV Quality Assurance
 Manual REV-20 10/09/2014

Hector De la Cruz

CERTIFIED BY THE QUALITY DEPARTMENT - SIGNATURE ON FILE

MAILING ADDRESS
 VINTON STEEL LLC VINTON P.O. BOX 12843
 EL PASO, TEXAS 79913-0843 915 886-2000

STREET ADDRESS
 I-10 & VINTON ROAD
 VINTON, TEXAS 79835-9998

SOLD ~~KATY STEEL~~
 TO: PO BOX 735
 KATY, TX 77492-

NUCOR
 NUCOR CORPORATION
 NUCOR STEEL TEXAS

CERTIFIED MILL TEST REPORT

Page: 1

SHIP TO: KATY STEEL-CUSTOMER PU
 N/A
 KATY, TX 77492-

Ship from:
 MTR #: 0000337724
 Nucor Steel - Texas
 8812 Hwy 79 W
 JEWETT, TX 75846
 800-527-6445

Date: 22-May-2018
 B.L. Number: 821690
 Load Number: 410675

Material Safety Data Sheets are available at www.nucorbar.com or by contacting your inside sales representative.


NBMC-08 January 1, 2012

LOT # HEAT #	DESCRIPTION	PHYSICAL TESTS			CHEMICAL TESTS														
		YIELD P.S.I.	TENSILE P.S.I.	ELONG % IN 8"	BEND	WT% DEF	C	Ni	Mn	Cr	P	Mo	S	V	Si	Cb	Cu	Sn	C.E.
PC# => JW1810405701 JW18104057	322637-4 Nucor Steel - Texas 16/#5 Rebar 60' A615M GR420 (Gr60) ASTM A615/A615M-16 GR 60 AASHT O M31-15	67,500 465MPa	108,400 747MPa	15.0%	OK		.41 .13	1.02 .16		.012 .048		.031 .004		.22 .002					

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.
 1. Manufactured in the United States of America.
 2. Melting and Manufacturing in the United States of America.
 3. Manufactured in the United States of America.
 4. Mercury, Radium, or Alpha source materials in any form.


Rafa R. Vantani

QUALITY




Roadside Safety and
Physical Security Division -
Proving Ground

Project #606861 LADOT Bridge Railing Retrofit 2018-08-09
 Drawn by BLG Sheet 1 of 2 Concrete Map



T:\1-ProjectFiles\606861 - LADOTD Bridge Railing Retrofits - Williams\Drafting, 606861-1-2\Concrete

	Roadside Safety and Physical Security Division - Proving Ground		2018-08-09
	Project #606861 LADOT Bridge Railing Retrofit	Scale 1:150	Sheet 2 of 2 Concrete Map 2

 Proving Ground 3100 SH 47, Bldg 7091 Bryan, TX 77807 Texas A&M University College Station, TX 77843 Phone 979-845-6375	5.7.2 Concrete Sampling	Doc. No. QPF 5.7.2	Revision Date: 2018-04-17
		Revised by: B. L. Griffith Approved by: D. Kuhn	Revision: 6

Project No: 606261 Casting Date: 2018-07-19 Mix Design (psi): 3000

Printed Name of Technician taking Sample: GREG FRITZ Printed Name of Technician breaking Sample: M. A. Robinson
 Signed Name of Technician taking Sample: [Signature] Signed Name of Technician breaking Sample: [Signature]

Load No.	Truck No.	Ticket No.	Location (from concrete map)
W1/T1	7108	4850758	100% of Wall, 6" from Top (TOY)
D1/T2	8162	4850501	Deck for Segment 3 and 1/2 each way
D2/T3	7211	4850572	Deck for North 1/2 1/2 Segment each Side

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
T3	2018-10-02	25d	4050	114500	1
			4025	115500	4008
			3891	110000	1
T2	2018-10-2	25d	4527	128000	1
			4300	122500	4486
			4598	130000	1
T ^{B-8} ₂₀₁₈₋₁₀₋₂	2018-10-2	25d	5359	151500	1
			5199	147000	5111
			4275	135000	1

CUSTOMER'S COPY

TICKET NO.



Martin Marietta

1503 LBJ Freeway
Suite 400
Dallas, Tx 75234

4850972



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
12:19	12:45	11:14	11:15	:	:	:

WATER ADDED ON JOB AT CUSTOMER'S REQUEST 10 GAL.
ALLOWABLE WATER (withheld from batch) _____ GAL.
TEST CYLINDER TAKEN YES NO BY _____
CYLINDER TAKEN BEFORE AFTER WATER

CUSTOMER SIGNATURE
X

DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED BY SIGNATURE ABOVE .

ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.

CUSTOMER NAME AND DELIVERY ADDRESS	PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
BRYAN CONSTRUCTION C TAMU RIVERSIDE CAMPUS	617	7211	2024	5.0	292	
	DRIVER NAME	DATE				
	JUAN RAMOS	7/19/18				
CUSTOMER NUMBER	PROJECT	CUM. QTY	ORDERED QTY			
509195	74925	30.00	30.00			

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
10.00	CYDS	BDOTCA00 CLASS A		

SPECIAL DELIVERY INSTRUCTIONS SOUTH 2818, RIGHT LEONARD, RIGHT47, LEFT INTO RELIIS THEY WILLMEET YOU RIGHT THERE

SALES TAX TOTAL

DANGER! MAY CAUSE ALKALI BURNS. SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY FORM: 2210013

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
7211	38554	user		4850972	67604	12:19	7/19/18
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID	
10.00	CYDS BDOTCA00				D	68560	
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat	
157	1931 lb	19407 lb	19440 lb	0.17%	0.50% M	12 gl	
10	1374 lb	14268 lb	14280 lb	0.08%	3.70% M	63 gl	
1	293 lb	2930 lb	2950 lb	0.68%			
8	158 lb	1580 lb	1570 lb	-0.63%			
900	2 oz	22 oz	22 oz	-1.78%			
H2O	242 lb	1653 lb	1647 lb	-0.37%		197 gl	
Actual	Num Batches: 1						
Load Total:	39888 lb	Design 0.537	Water/Cement 0.535	T	Design 290.0 gl	Actual 272.3 gl	To Add: 17.7 gl
Slump:	5.00 in	Water in Trucks: 0.0 gl	Adjust Water: 0.0 gl	/ Load	Trim Water: -1.7 gl/ CYD	Note: Manual feed oc	
P80	7 oz	146 oz	148 oz				

CUSTOMER'S COPY


TICKET NO.



Martin Marietta

1503 LBJ Freeway
Suite 400
Dallas, Tx 75234

4850758



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
11:38	11:50	12:15	12:20	12:25	:	:

WATER ADDED ON JOB AT CUSTOMER'S REQUEST 0 GAL.
 ALLOWABLE WATER (withheld from batch) _____ GAL.
 TEST CYLINDER TAKEN YES NO BY _____
 CYLINDER TAKEN BEFORE AFTER WATER

CUSTOMER SIGNATURE
 X *[Signature]*
DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED BY SIGNATURE ABOVE.

ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.

CUSTOMER NAME AND DELIVERY ADDRESS
 BRYAN CONSTRUCTION CO
 TAMU RIVERSIDE CAMPUS

PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
617	7108	2024	5.0	292	
DRIVER NAME		DATE			
VICTOR MARTINEZ		7/19/18			
CUSTOMER NUMBER	PROJECT	CUM. QTY	ORDERED QTY		
509195	74925	10.00	30.00		

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
10.00	CYDS	BDOTCA00 CLASS A		

SPECIAL DELIVERY INSTRUCTIONS
 SOUTH 2818, RIGHT LEONARD, RIGHT 47, LEFT INTO RELLIS
 THEY WILL MEET YOU RIGHT THERE

SALES TAX _____
 TOTAL _____

DANGER! MAY CAUSE ALKALI BURNS. SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY **FORM: 2210010**

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
7108	923381	user	4850758	167601		11:38	7/19/18
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID	
10.00	CYDS				D	62557	
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat	
157	1331 lb	19407 lb	19520 lb	* 0.58%	0.50% M	12 gl	
10	1374 lb	14268 lb	14320 lb	* 0.37%	3.70% M	63 gl	
1	293 lb	2330 lb	2340 lb	* 0.34%			
8	158 lb	1580 lb	1590 lb	* 0.63%			
900	2 oz	20 oz	20 oz	-2.01%			
901							
H2O	242 lb	1653 lb	1653 lb	-0.01%		198 gl	
P50	7 oz	147 oz	146 oz	-0.41%			
Actual	Num Batches: 1						
Load Total:	40033 lb	Design 0.537	Water/Cement 0.534 T	Design 290.0 gl	Actual 273.3 gl	To Add: 16.7 gl	
Slump:	5.00 in	Water in Truck: 0.0 gl	Adjust Water: 0.0 gl	/ Load	Trim Water: -1.7 gl/ CYD		

CUSTOMER'S COPY

TICKET NO.



Martin Marietta

1503 LBJ Freeway
Suite 400
Dallas, Tx 75234

4850901



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
12:03			12:43			

WATER ADDED ON JOB AT CUSTOMER'S REQUEST 16.5 GAL.
 ALLOWABLE WATER (withheld from batch) _____ GAL.
 TEST CYLINDER TAKEN YES NO BY _____
 CYLINDER TAKEN BEFORE AFTER WATER

CUSTOMER SIGNATURE
 X *Dexter Chatham*
DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED BY SIGNATURE ABOVE.

ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.

CUSTOMER NAME AND DELIVERY ADDRESS		PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
BRYAN CONSTRUCTION C TAMU RIVERSIDE CAMPUS		617	8162	2024	5.0	292	
DRIVER NAME		DATE					
CHATHAM, DEXTER		7/19/18					
CUSTOMER NUMBER	PROJECT	CUM. QTY	ORDERED QTY				
509195	74925	20.00	30.00				

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
10.00	CYDS	BDOTCA00 CLASS A		


SPECIAL DELIVERY INSTRUCTIONS: SOUTH 2810, RIGHT LEONARD, RIGHT47, LEFT INTO RELLIS THEY WILL MEET YOU RIGHT THERE

SALES TAX _____
TOTAL _____

DANGER! MAY CAUSE ALKALI BURNS. SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY **FORM: 2210012**

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
8162	37791	user		4850901	67603	12:03	7/19/18
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID	
10.00	CYDS BDOTCA00				D	68559	
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat	
157	1931 lb	19487 lb	19400 lb	-0.04%	0.50% #	12 gl	
18	1374 lb	14268 lb	14200 lb	0.00%	3.70% #	63 gl	
1	293 lb	2930 lb	2940 lb	0.34%			
8	150 lb	1500 lb	1590 lb	0.63%			
900	2 oz	22 oz	22 oz	-1.78%			
H2O	246 lb	1653 lb	1656 lb	0.17%		198 gl	
P80	7 oz #	146 oz	146 oz	0.00%			
Actual	Num Batches: 1						
Load Total: 39875 lb	Design 0.537	Water/Cement 0.534	T	Design 290.0 gl	Actual 273.4 gl	To Add: 16.6 gl	
Slump: 5.00 in	Water in Truck: 0.0 gl	Adjust Water: 0.0 gl	/ Load	Trim Water: -1.7 gl	/ CYD		

 <small>Proving Ground 3100 SH 47, Bldg 7091 Bryan, TX 77807</small> <small>Texas A&M University College Station, TX 77843 Phone 979-845-6375</small>	5.7.2 Concrete Sampling	Doc. No. QPF 5.7.2	Revision Date: 2018-04-17
		Revised by: B. L. Griffith Approved by: D. Kuhn	Revision: 6

Project No: 606861 Casting Date: 2018-7-26 Mix Design (psi): 3000

Printed Name of Technician taking Sample Gregg Fritz

Printed Name of Technician breaking Sample MATT Robinson

Signed Name of Technician taking Sample [Signature]

Signed Name of Technician breaking Sample [Signature]

Load No.	Truck No.	Ticket No.	Location (from concrete map)
P1	7124	4865630	South, Middle, & North Segments

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
P1	2018-10-2	68d	5359	151500	1
1	1	1	5359	151500	5235
1	1	1	4987	141000	1



Martin Marietta

1503 LBJ Freeway
Suite 400
Dallas, Tx 75234

CUSTOMER'S COPY

TICKET NO.

4865630



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
8:37	8:44	9:13	9:16	:	:	:

WATER ADDED ON JOB AT CUSTOMER'S REQUEST _____ GAL.
 ALLOWABLE WATER (withheld from batch) _____ GAL.
 TEST CYLINDER TAKEN YES NO BY _____
 CYLINDER TAKEN BEFORE AFTER WATER

CUSTOMER SIGNATURE
 X
DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED BY SIGNATURE ABOVE .

ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.

CUSTOMER NAME AND DELIVERY ADDRESS
 BRYAN CONSTRUCTION C
 TAMU RIVERSIDE CAMPUS

PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
617	7124	2013	5.0	292	
DRIVER NAME		DATE			
ANTHONY WOODS		7/26/18			
CUSTOMER NUMBER	PROJECT	CUM. QTY	ORDERED QTY		
509195	74925	7.00	7.00		

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
7.00	CYDS	BDOTCA00 CLASS A		

SPECIAL DELIVERY INSTRUCTIONS
 SOUTH 2818, RIGHT LEONARD RD, RIGHT HWY 47, LEFT INTO RELLIS THEY WILL MEET YOU AT THE ENTRANCE


SALES TAX
 TOTAL

DANGER! MAY CAUSE ALKALI BURNS.
 SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY FORM: 2210202

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
7124	875636	user	4865630	67793		8:37	7/26/18
Load Size	Mix Code	Returned	Qty	Mix	Age	Seq	Load ID
7.00	CYDS BDOTCA00					D	68749
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat	
157	1931 lb	13331 lb	13560 lb	0.07%	0.23% H	4 gi	
10	1374 lb	9946 lb	9960 lb	0.14%	3.30% H	39 gi	
1	293 lb	2851 lb	2840 lb	-0.54%			
0	158 lb	1106 lb	1110 lb	0.36%			
980	2 oz	14 oz	14 oz	0.50%			
981	#	oz	oz				
H2O	242 lb	1227 lb	1227 lb	0.02%		147 gi	
PA0	7 oz	102 oz	101 oz	-1.59%			
Actual	New Batches: 1						
Load Total:	27904 lb	Design 0.537	Water/Cement 0.538	T	Design 203.0 gi	Actual 190.5 gi	To Add: 12.5 gi
Slump:	5.00 in	Water in Truck: 0.0 gi	Adjust Water: 0.0 gi	/ Load	Tris Water: -1.8 gi/ CYD		

606861
 60886/p1

 <small>Proving Ground 3100 SH 47, Bldg 7091 Bryan, TX 77807</small> <small>Texas A&M University College Station, TX 77843 Phone 979-845-6375</small>	5.7.2 Concrete Sampling	Doc. No.	Revision
		QPF 5.7.2	Date: 2018-04-17
Quality Policy Form	Revised by: B. L. Griffith Approved by: D. Kuhn	Revision:	Page:
		6	1 of 1

Project No: 606861 Casting Date: 2018-7-27 Mix Design (psi): 3000

Printed Name of Technician taking Sample Greg Fritz

Printed Name of Technician breaking Sample Maxx Robinson

Signed Name of Technician taking Sample [Signature]

Signed Name of Technician breaking Sample [Signature]

Load No.	Truck No.	Ticket No.	Location (from concrete map)
<u>P2</u>	<u>7139</u>	<u>4889236</u>	<u>2 segment, Mid South, Mid North</u>

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
<u>P2</u>	<u>2018-10-2</u>	<u>67</u>	<u>4156</u>	<u>117500</u>	<u>1</u>
<u>P2</u>	<u>1</u>	<u>1</u>	<u>3997</u>	<u>113000</u>	<u>4050</u>
<u>P2</u>	<u>1</u>	<u>1</u>	<u>3997</u>	<u>113000</u>	<u>1</u>

CUSTOMER'S COPY

TICKET NO.



Martin Marietta

1503 LBJ Freeway
Suite 400
Dallas, Tx 75234

4869236



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
9:03	9:13	:	:	:	:	:

WATER ADDED ON JOB AT CUSTOMER'S REQUEST _____ GAL.
 ALLOWABLE WATER (withheld from batch) _____ GAL. **8**
 TEST CYLINDER TAKEN YES NO BY _____
 CYLINDER TAKEN BEFORE AFTER WATER

CUSTOMER SIGNATURE
 X

DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED BY SIGNATURE ABOVE .

ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.

CUSTOMER NAME AND DELIVERY ADDRESS
 BRYAN CONSTRUCTION C
 TAMU RIVERSIDE CAMPUS

PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
617	7139	2018	5.0	292	
DRIVER NAME		DATE			
Rodney Lucas		7/27/18			
CUSTOMER NUMBER	PROJECT	CUM. QTY	ORDERED QTY		
509195	74925	5.00	5.00		

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
5.00	CYDS	BDOTCA00 CLASS A		

SPECIAL DELIVERY INSTRUCTIONS

SOUTH 2810, RIGHT LEONARD RD, RIGHT HWY 47, LEFT INTO
 RELLIS THEY WILL MEET YOU AT THE ENTRANCE

SALES TAX


TOTAL

DANGER! MAY CAUSE ALKALI BURNS.
 SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY **FORM: 2204892**

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
7139	934548	user	4869236	67883	9:03	7/27/18	
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID	
5.00	CYDS	BDOTCA00			D	68839	
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat	
157	1531 lb	9679 lb	9729 lb	0.42%	0.25% M	3 gl	
10	1374 lb	7104 lb	7160 lb	0.78%	3.30% M	28 gl	
1	293 lb	1465 lb	1480 lb	1.02%			
8	152 lb	790 lb	790 lb	0.00%			
900	2 oz	10 oz	10 oz	-4.52%			
901		0 oz	0 oz				
H2O	242 lb	876 lb	879 lb	0.31%		105 gl	
P00	7 oz	73 oz	74 oz	0.95%			
Actual							
Load Total:	20034 lb	Design 0.537	Mater/Cement 0.533 T	Design 145.0 gl	Actual 136.6 gl	To Add: 8.4 gl	
Slump:	5.00 in	Water in Truck: 0.0 gl	Adjust Water: 0.0 gl	/ Load	Trim Water: -1.8 gl/ CYD		

606861 PR
 [Signature]

 Texas A&M Transportation Institute <small>Proving Ground 3100 SH 47, Bldg 7091 Brno, TX 77807</small> <small>Texas A&M University College Station, TX 77843 Phone 979-845-6376</small>	5.7.2 Concrete Sampling	Doc. No. QPF 5.7.2	Revision Date: 2018-04-17
		Revised by: B. L. Griffith Approved by: D. Kuhn	Revision: 6

Project No: 606861 Casting Date: 2018-08-02 Mix Design (psi): 3000 psi

Printed Name of Technician taking Sample: GREG FRITZ Printed Name of Technician breaking Sample: Matt Robinson
 Signed Name of Technician taking Sample: [Signature] Signed Name of Technician breaking Sample: [Signature]

Load No.	Truck No.	Ticket No.	Location (from concrete map)
T1	8163	4822854	3 Parapets on Right Side

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
T1	2018-10-2	61 days	4280	121000	1
T1	1	1	3997	113000	4085
T1	1	1	3929	112500	1

CUSTOMER'S COPY


TICKET NO.



Martin Marietta

1503 LBJ Freeway
Suite 400
Dallas, Tx 75234

4882854



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
1:35	1:43	2:00	2:08	:	:	:

WATER ADDED ON JOB AT CUSTOMER'S REQUEST 5 GAL.
 ALLOWABLE WATER (withheld from batch) 5.3 GAL.
 TEST CYLINDER TAKEN YES NO BY _____
 CYLINDER TAKEN BEFORE AFTER WATER

CUSTOMER SIGNATURE
 X
DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED BY SIGNATURE ABOVE.

ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.

CUSTOMER NAME AND DELIVERY ADDRESS		PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
BRYAN CONSTRUCTION C TAMU RIVERSIDE CAMPUS		617	8163	2033	5.0	292	
		DRIVER NAME		DATE			
		CLARK, GARY		8/2/18			
CUSTOMER NUMBER	PROJECT	CUM. QTY	ORDERED QTY				
509195	74925	3.00	3.00				

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
3.00	CYDS	BDOTCA00 CLASS A		


SPECIAL DELIVERY INSTRUCTIONS
 HWY 21 WEST, LEFT INTO RELLIS THEY WILL MEET YOU
 THERE SITTING IN A SILVER CHEVROLET TRUCK

SALES TAX
 TOTAL

DANGER! MAY CAUSE ALKALI BURNS.
 SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY **FORM: 2205141**

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
8163	37794	user	4882854	68132		13:35	8/2/18
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID	
3.00	CYDS BDOTCA00				D	69090	
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat	
157	1931 lb	5816 lb	5900 lb	-0.28%	0.48% #	3 g	
10	1374 lb	4294 lb	4320 lb	* 0.51%	4.00% #	21 g	
1	293 lb	879 lb	860 lb	-2.16%			
0	158 lb	474 lb	480 lb	1.27%			
900	2 oz	6 oz	6 oz	0.50%			
981							
H2O	242 lb	487 lb	486 lb	-0.24%		58 g	
050	7 oz	38 oz	37 oz	-3.85%			
Actual	Num Batches:						
Load Total:	11949 lb	Design 0.537	Water/Cement 0.542	T	Design 87.0 gl	Actual 81.7 gl	To Add: 5.3 gl
Slump:	5.00 in	Water in Truck: 0.0 gl	Adjust Water: 0.0 gl	/ Load	Trim Water: -1.8 gl/ CYD		

 Texas A&M Transportation Institute <small>Proving Ground 3100 BH-47, Bldg 7001 Green, TX 77067</small> <small>Texas A&M University College Station, TX 77843 Phone 979-845-6376</small>	5.7.2 Concrete Sampling	Doc. No. QPF 5.7.2	Revision Date: 2018-04-17
		Quality Policy Form	Revised by: B. L. Griffith Approved by: D. Kuhn

Project No: 606261 Casting Date: 2018-08-09 Mix Design (psi): 3000

Printed Name of Technician taking Sample: GREG FRITZ Printed Name of Technician breaking Sample: Art Robinson
 Signed Name of Technician taking Sample: [Signature] Signed Name of Technician breaking Sample: [Signature]

BF
2018-08-09

Load No.	Truck No.	Ticket No.	Location (from concrete map)
C2	2116	4879231	2 remaining Segments (South Side)

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
C2	2018-10-2	47 days	4124	118000	1
C2	2018-10-2	1	4103	116000	4002
C2	2018-10-2	1	3731	105500	1

CUSTOMER'S COPY

TICKET NO.



Martin Marietta

1503 LBJ Freeway
Suite 400
Dallas, Tx 75234

4899231



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
12:09	12:19	12:35	12:40	:	:	:

WATER ADDED ON JOB AT CUSTOMER'S REQUEST _____ GAL.
 ALLOWABLE WATER (withheld from batch) _____ GAL.
 TEST CYLINDER TAKEN YES NO BY _____
 CYLINDER TAKEN BEFORE AFTER WATER

CUSTOMER SIGNATURE _____
DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED BY SIGNATURE ABOVE .

ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.

CUSTOMER NAME AND DELIVERY ADDRESS	PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
BRYAN CONSTRUCTION C TAMU RIVERSIDE CAMPUS	617	8116	2030	5.0	292	
	DRIVER NAME	DATE				
	HOUSE, JOHN	8/9/18				
	CUSTOMER NUMBER	PROJECT	CUM. QTY	ORDERED QTY		
	509195	74925	3.00	3.00		

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
3.00	CYDS	BDOTCA00 CLASS A		

SPECIAL DELIVERY INSTRUCTIONS: HWY 21 WEST, LEFT INTO RELLIS THEY WILL MEET YOU AROUND THERE

SALES TAX _____
TOTAL _____

DANGER! MAY CAUSE ALKALI BURNS. SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY FORM: 2205428

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
8116	20640	user		4899231	68419	12:09	8/9/18
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID	
3.00	CYDS BDOTCA00				D	69383	
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat	
157	1331 lb	5816 lb	5800 lb	-0.28%	0.40% M	3 gl	
10	1374 lb	4272 lb	4240 lb	-0.74%	3.50% M	18 gl	
1	293 lb	679 lb	950 lb	8.08%			
8	158 lb	474 lb	460 lb	-2.95%			
900	2 oz	11 oz	12 oz	1.38%			
901	#	oz	oz				
H2O	242 lb	503 lb	501 lb	-0.43%		60 gl	
P00	7 oz	44 oz	43 oz	-2.23%			
Actual	Num Batches: 1						
Load Total:	11954 lb	Design 0.537 Water/Cement 0.515 T		Design 27.0 gl	Actual 80.6 gl	To Add: 6.4 gl	
Slumps: 5.00 in	Water in Truck: 0.0 gl	Adjust Water: 0.0 gl	/ Load	Trim Water: -2.0 gl/ CYD	Notes: Manual feed oc		

Appendix D. MASH Test 3-11 (Crash Test No. 606861-1)

Figure 106. Vehicle properties for Test No. 606861-1

Date: 2018-10-02 Test No.: 606861-1 VIN No.: 1C6RD6GTXC5268732
 Year: 2012 Make: RAM Model: 1500
 Tire Size: 265/70 R 17 Tire Inflation Pressure: 35 psi
 Tread Type: Highway Odometer: 268732
 Note any damage to the vehicle prior to test: None

• Denotes accelerometer location.


NOTES: None

Engine Type: V-8
 Engine CID: 4.7 liter

Transmission Type:
 Auto or Manual
 FWD RWD 4WD

Optional Equipment:
None

Dummy Data:
 Type: 50th percentile male
 Mass: 165 lb
 Seat Position: Impact side



Geometry: inches

A	78.50	F	40.00	K	20.00	P	3.00	U	26.50
B	74.00	G	28.50	L	30.00	Q	30.50	V	30.25
C	227.50	H	61.30	M	68.50	R	18.00	W	61.30
D	44.00	I	11.75	N	68.00	S	13.00	X	78.00
E	140.50	J	27.00	O	46.00	T	77.00		
Wheel Center Height Front	14.75	Wheel Well Clearance (Front)	6.00	Bottom Frame Height - Front	12.50				
Wheel Center Height Rear	14.75	Wheel Well Clearance (Rear)	9.25	Bottom Frame Height - Rear	22.50				

RANGE LIMIT: A=78 ±2 inches; C=237 ±13 inches; E=148 ±12 inches; F=39 ±3 inches; G = > 28 inches; H = 63 ±4 inches; O=43 ±4 inches; M+N/2=67 ±1.5 inches

GVWR Ratings:	Mass: lb	<u>Curb</u>	<u>Test Inertial</u>	<u>Gross Static</u>
Front <u>3700</u>	M _{front}	<u>2930</u>	<u>2826</u>	<u>2911</u>
Back <u>3900</u>	M _{rear}	<u>2053</u>	<u>2189</u>	<u>2269</u>
Total <u>6700</u>	M _{Total}	<u>4983</u>	<u>5015</u>	<u>5180</u>

(Allowable Range for TIM and GSM = 5000 lb ±110 lb)

Mass Distribution:	lb	LF:	RF:	LR:	RR:
		<u>1388</u>	<u>1438</u>	<u>1108</u>	<u>1081</u>

Figure 107. Measurement of vehicle vertical CG for Test No. 606861-1

Date: 2018-10-02 Test No.: 606861-1 VIN: 1C6RD6GTXCS268732
 Year: 2012 Make: RAM Model: 1500
 Body Style: Quad Cab Mileage: 268732
 Engine: 4.7 liter V-8 Transmission: Automatic
 Fuel Level: Empty Ballast: 171 (440 lb max)
 Tire Pressure: Front: 35 psi Rear: 35 psi Size: 265/70 R 17

Measured Vehicle Weights: (lb)			
LF:	<u>1388</u>	RF:	<u>1438</u>
		Front Axle:	<u>2826</u>
LR:	<u>1108</u>	RR:	<u>1081</u>
		Rear Axle:	<u>2189</u>
Left:	<u>2496</u>	Right:	<u>2519</u>
		Total:	<u>5015</u>
			5000 ±110 lb allowed
Wheel Base:	<u>140.50</u> inches	Track: F:	<u>68.50</u> inches
	148 ±12 inches allowed	R:	<u>68.00</u> inches
			Track = (F+R)/2 = 67 ±1.5 inches allowed
Center of Gravity, SAE J874 Suspension Method			
X:	<u>61.33</u> inches	Rear of Front Axle	(63 ±4 inches allowed)
Y:	<u>0.16</u> inches	Left - Right +	of Vehicle Centerline
Z:	<u>28.50</u> inches	Above Ground	(mininum 28.0 inches allowed)

Hood Height: 46.00 inches Front Bumper Height: 27.00 inches
 43 ±4 inches allowed

Front Overhang: 40.00 inches Rear Bumper Height: 30.00 inches
 39 ±3 inches allowed

Overall Length: 227.50 inches
 237 ±13 inches allowed

Figure 108. Sequential photographs for Test No. 606861-1 (overhead view).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

Figure 109. Sequential photographs for Test No. 606861-1 (frontal view).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

Figure 110. Sequential photographs for Test No. 606861-1 (rear view).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

Figure 111. Exterior crush measurements for Test No. 606861-1

Date: 2018-10-02 Test No.: 606861-1 VIN No.: 1C6RD6GTXCS268732
 Year: 2012 Make: RAM Model: 1500

VEHICLE CRUSH MEASUREMENT SHEET¹

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____	Bowing: B1 _____ X1 _____
Corner shift: A1 _____	B2 _____ X2 _____
A2 _____	
End shift at frame (CDC)	Bowing constant
(check one)	$\frac{X1 + X2}{2} =$ _____
< 4 inches _____	
≥ 4 inches _____	

Note: Measure C₁ to C₆ from Driver to Passenger Side in Front or Rear Impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L**	C ₁	C ₂	C ₃	C ₄	C ₅	C ₆	±D
		Width*** (CDC)	Max**** Crush								
1	AT FT BUMPER	26	16	34	2	2.5	5	8	12	16	+14
2	ABOVE FT BUMPER	26	15.5	56	2	5	8	10	13.5	15.5	+72
	Measurements recorded										
	<input checked="" type="checkbox"/> inches or <input type="checkbox"/> mm										

¹Table taken from National Accident Sampling System (NASS).

*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.


**Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

***Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

Figure 112. Occupant compartment measurements for Test No. 606861-1

Date: 2018-10-02 Test No.: 606861-1 VIN No.: 1C6RD6GTXCS268732
 Year: 2012 Make: RAM Model: 1500



OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT

	Before	After (inches)	Differ.
A1	65.00	65.00	0.00
A2	63.00	63.00	0.00
A3	65.50	65.50	0.00
B1	45.00	45.00	0.00
B2	38.00	38.00	0.00
B3	45.00	44.50	-0.50
B4	39.50	39.50	0.00
B5	43.00	43.00	0.00
B6	39.50	39.50	0.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	24.00	-2.00
D1	11.00	11.00	0.00
D2	0.00	0.00	0.00
D3	11.50	11.25	-0.25
E1	58.50	59.00	0.50
E2	63.50	65.75	2.25
E3	63.50	63.50	0.00
E4	63.50	63.50	0.00
F	59.00	59.00	0.00
G	59.00	59.00	0.00
H	37.50	37.50	0.00
I	37.50	37.50	0.00
J*	25.00	24.00	-1.00

*Lateral area across the cab from driver's side kickpanel to passenger's side kickpanel.

Figure 113. Vehicle angular displacements for Test No. 606861-1




Figure 114. Vehicle longitudinal accelerometer trace for Test No. 606861-1 (accelerometer located at center of gravity)




Figure 115. Vehicle lateral accelerometer trace for Test No. 606861-1 (accelerometer located at center of gravity)





Figure 116. Vehicle vertical accelerometer trace for Test No. 606861-1 (accelerometer located at center of gravity)



Appendix E. MASH Test 3-10 (Crash Test No. 606861-2)

Figure 117. Vehicle properties for Test No. 606861-2

Date: 2020-12-11 Test No.: 606861-4 VIN No.: 3N1CN7APOEL862280

Year: 2014 Make: NISSAN Model: VERSA

Tire Inflation Pressure: 36 PSI Odometer: 91861-4 Tire Size: P185/65R15



Describe any damage to the vehicle prior to test: None

• Denotes accelerometer location.

NOTES: None

Engine Type: 4 CYL
 Engine CID: 1.6 L
 Transmission Type:
 Auto or Manual
 FWD RWD 4WD
 Optional Equipment:
None

Dummy Data:
 Type: 50th Percentile Male
 Mass: 165 lb
 Seat Position: IMPACT SIDE



Geometry: inches

A <u>66.70</u>	F <u>32.50</u>	K <u>12.50</u>	P <u>4.50</u>	U <u>15.50</u>
B <u>59.60</u>	G _____	L <u>26.00</u>	Q <u>24.00</u>	V <u>21.25</u>
C <u>175.40</u>	H <u>42.15</u>	M <u>58.30</u>	R <u>16.25</u>	W <u>42.10</u>
D <u>40.50</u>	I <u>7.00</u>	N <u>58.50</u>	S <u>7.50</u>	X <u>79.75</u>
E <u>102.40</u>	J <u>22.25</u>	O <u>30.50</u>	T <u>64.50</u>	_____
Wheel Center Ht Front <u>11.50</u>	Wheel Center Ht Rear <u>11.50</u>	W-H <u>-0.05</u>	_____	_____

RANGE LIMIT: A = 65 ±3 inches; C = 169 ±8 inches; E = 98 ±5 inches; F = 35 ±4 inches; H = 39 ±4 inches; O (Top of Radiator Support) = 28 ±4 inches (M+N)/2 = 59 ±2 inches; W-H < 2 inches or use MASH Paragraph A4.3.2

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static
Front <u>1750</u>	M _{front} <u>1369</u>	<u>1369</u>	<u>1425</u>	<u>1510</u>
Back <u>1687</u>	M _{rear} <u>974</u>	<u>974</u>	<u>979</u>	<u>1059</u>
Total <u>3389</u>	M _{Total} <u>2343</u>	<u>2343</u>	<u>2404</u>	<u>2569</u>

Allowable TIM = 2420 lb ±55 lb | Allowable GSM = 2585 lb ± 55 lb

Mass Distribution:

lb LF: 706 RF: 719 LR: 502 RR: 477


Figure 118. Sequential photographs for Test No. 606861-2 (overhead view).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

0.400 s

0.600 s

Figure 119. Sequential photographs for Test No. 606861-2 (frontal view).



0.000 s



0.300 s



0.100 s



0.200 s



0.400 s



0.600 s



0.500 s



0.700 s

Figure 120. Sequential photographs for Test No. 606861-2 (rear view).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

Figure 121. Exterior crush measurements for Test No. 606861-2

Date: 2018-10-03 Test No.: 606861-2 VIN No.: KNADE223396496067
 Year: 2009 Make: Kia Model: Rio

VEHICLE CRUSH MEASUREMENT SHEET¹

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____	Bowing: B1 _____ X1 _____
Corner shift: A1 _____	B2 _____ X2 _____
A2 _____	
End shift at frame (CDC)	Bowing constant
(check one)	$\frac{X1 + X2}{2} =$ _____
< 4 inches _____	
≥ 4 inches _____	

Note: Measure C₁ to C₆ from Driver to Passenger Side in Front or Rear Impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L***	C ₁	C ₂	C ₃	C ₄	C ₅	C ₆	±D
		Width*** (CDC)	Max**** Crush								
1	AT FT BUMPER	14	8	22	8	6	2	1.5	1	0	+18
2	ABOVE FT BUMPER	14	9	40	0	1	3.25	3.75	6.5	9	+65
	Measurements recorded										
	<input checked="" type="checkbox"/> inches or <input type="checkbox"/> mm										

¹Table taken from National Accident Sampling System (NASS).

*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.




**Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

***Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

Figure 122. Occupant compartment measurements for Test No. 606861-2

Date: 2018-10-03 Test No.: 606861-2 VIN No.: KNADE223396496067
 Year: 2009 Make: Kia Model: Rio



OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT

	Before	After (inches)	Differ.
A1	67.50	67.50	0.00
A2	67.25	67.25	0.00
A3	67.75	67.75	0.00
B1	40.50	40.50	0.00
B2	39.00	39.00	0.00
B3	40.50	40.50	0.00
B4	36.25	36.25	0.00
B5	36.00	36.00	0.00
B6	36.25	36.25	0.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	24.50	-1.50
D1	9.50	9.50	0.00
D2	0.00	0.00	0.00
D3	9.50	8.50	-1.00
E1	51.50	51.75	0.25
E2	51.00	51.75	0.75
F	51.00	51.00	0.00
G	51.00	51.00	0.00
H	37.50	37.50	0.00
I	37.50	37.50	0.00
J*	51.00	50.50	-0.50

*Lateral area across the cab from driver's side kick panel to passenger's side kick panel.

Figure 123. Vehicle angular displacements for Test No. 606861-2




Figure 124. Vehicle longitudinal accelerometer trace for Test No. 606861-2 (accelerometer located at center of gravity)




Figure 125. Vehicle lateral accelerometer trace for Test No. 606861-2 (accelerometer located at center of gravity)






Figure 126. Vehicle vertical accelerometer trace for Test No. 606861-2 (accelerometer located at center of gravity)




Appendix F. Strength Analysis of DOTD Retrofit Bridge Rail System




SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis




Section View of Bridge Rail Section




Section View of Bridge Rail System with Variable Notations





Section View of Bridge Rail System with Key Dimensions




Plan View of Failure Section 2




Plan View of Failure Section 3



Details of Concrete and Reinforcement Bars



Detail Views of Splice Details



Detail Views of Steel Rails



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

General Information:

- Concrete Parapet Strength, $f_c = 4000$ psi
- Anchor Rods are $\phi 3/4" \times 8"$ long, A193 B7 Threaded Anchor: $F_u = 120$ ksi
- All concrete reinforcing steel = Grade 40: $f_y = 40$ ksi
- HSS10x4x3/8 Tube Rails are A500 Grade B Material: $F_y = 46$ ksi
- Reference: AASHTO LRFD Bridge Design Specifications, Section 13, TL-3 Conditions.
- Objective: Calculate the Strength of the Rail based on Worst Case Rail Strength and AASHTO LRFD Section 13 Strength Requirements.

***** Concrete, Reinforcing Steel & Structural Shape Information *****

$f'_c := 4000$ psi	Compressive Strength of Concrete (psi)
$F_{yR} := 46$ ksi	Yield Strength of all Steel Rails (ksi)
$f_y := 40$ ksi	Yield Strength of Concrete Reinforcing Steel (ksi)
$b_{rail} := 12$ in	Width of Concrete Rail (in.)
$d_{rail} := 6$ in	Distance to Tensile Reinf. from Compression Face (in.)
$n_{sCR} := 3$	Number of tensile reinf. bars in Concrete Rail
$A_{sCR} := n_{sCR} \cdot 0.31 \text{ in}^2 = 0.93 \cdot \text{in}^2$	Total Area of Tensile Reinf. (in ²)

***** Anchor Rod Properties *****

$F_{u,rod} := 120$ ksi	Tensile Strength of Anchor Rods (ksi)
$d_{rod} := \frac{3}{4}$ in	Diameter of Anchor Rods (in)
$A_{rod} := \frac{\pi \cdot d_{rod}^2}{4} = 0.442 \cdot \text{in}^2$	Area of a Anchor Rod (in ²)

MASH Design Impact Loads

Test Level	F _t (kip)	F _t (kip)	F _v (kip)	L _t /L _t (ft)	L _v (ft)	H _e (in)	H _{min} (in)
TL 1	13.5	4.5	4.5	4.0	18.0	18.0	18.0
TL 2	27.0	9.0	4.5	4.0	18.0	20.0	18.0
TL 3	71.0	18.0	4.5	4.0	18.0	24.0	29.0
TL 4 (a)	68.0	22.0	38.0	4.0	18.0	25.0	36.0
TL 4 (b)	80.0	27.0	22.0	5.0	18.0	30.0	36.0
TL 5 (a)	160.0	41.0	80.0	10.0	40.0	35.0	42.0
TL 5 (b)	262.0	75.0	160.0	10.0	40.0	43.0	42.0
TL 6	175.0	58.0	80.0	8.0	40.0	56.0	90.0

Note: (a) and (b) denote different TL 4 and TL 5 design force values for bridge rails of different heights.

$$TL := 3$$

Test Level

$$F_t := 71 \text{ kip}$$

Transverse Impact Force (kip)

$$L_t := 4 \text{ ft}$$

Longitudinal Length of Distribution of Transverse Impact Force (ft.)

$$L_{t,amp} := 1.5 \cdot L_t = 6 \text{ ft}$$

Amplified Longitudinal Length of Distribution of Transverse Impact Force (ft.)

- Note: Amplify L_t by 50% since steel rail retrofit will distribute impact load greater than what typically occurs. 50% amplification is typical of what we've seen in previous similar tests.

$$H_e := 19 \text{ in}$$

Height of Transverse Impact Load (in.)

$$H_{e,mod} := H_e + 10 \text{ in} = 29 \text{ in}$$

Modified Height of Transverse Impact Load (in.)

- Note: Due to curb and deck geometry, the impact load will be applied to the barrier at a greater height than the typical H_e . Adding 10 inches to H_e accounts for the curb height.

$$F_v := 4.5 \text{ kip}$$

Vertical Impact Force (kip)

$$L_v := 18 \text{ ft}$$

Longitudinal Length of Distribution of Vertical Impact Force (ft.)

$$L_p := 9 \text{ ft} + 9 \text{ in} + \frac{7}{8} \text{ in} = 117.875 \text{ in}$$

Spacing of Posts (in.)

$$H_p := 34.625 \text{ in}$$

Height of Concrete Post and Beam (in.)


$$H_t := 40 \text{ in}$$

Total height of bridge rail system (in.)

Analysis of Steel and Concrete Rails:

Concrete Rail Properties and Dimensions:

- a) Concrete Rail has a width of 12in and a height of 8in
- b) #5-Gr.40 Rebar is used for Longitudinal Reinforcement



$$A_{sCR} = 0.93 \text{ in}^2$$

Total Area of Tensile Reinf. (in²)

$$b_{rail} = 12 \text{ in}$$

Width of Concrete Rail (in.)

$$d_{rail} = 6 \text{ in}$$

Distance to Tensile Reinf. from Compression Face (in.)

$$f_y = 40 \text{ ksi}$$

Yield Stress of Reinf. (ksi)

$$f'_c = 4 \text{ ksi}$$

Compressive Strength of Concrete (ksi)

$$a_{rail} := \frac{A_{sCR} \cdot f_y}{0.85 \cdot f'_c \cdot b_{rail}} = 0.912 \text{ in}$$

Whitney Stress Block Depth (in.)

$$M_{CR} := A_{sCR} \cdot f_y \cdot \left(d_{rail} - \frac{a_{rail}}{2} \right) = 17.187 \text{ kip} \cdot \text{ft}$$

Moment Strength of Concrete Rail (k-ft)

$$y_{CR} := 28.625 \text{ in}$$

Height of the centroid of the Concrete Rail (in.)



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

Find Height of Resultant Force of Concrete and Steel Rails: (y_{bar1})

HSS10x4x3/8 Steel Rail Properties and Dimensions:

- a) Steel Rails are A500 Gr. B Material, $F_y=46\text{ksi}$
- b) Steel Rails bend about the y-axis

$$F_{yR} = 46 \cdot \text{ksi}$$

Yield Strength of Steel Rail (ksi)

$$Z_{SR} := 14 \text{ in}^3$$

Plastic Sectional Modulus of both Steel Rails (in^3)

$$M_{SR} := 2Z_{SR} \cdot F_{yR} = 107.333 \cdot \text{kip} \cdot \text{ft}$$

Total Plastic Moment Strength of both Steel Rails (k-ft)

$$y_{SR} := 30 \text{ in}$$

Height of the centroid of the Steel Rails (in.)

$$y_{CR} = 28.625 \cdot \text{in}$$

Height of the centroid of the Concrete Rail (in.)

$$M_{CR} = 17.187 \cdot \text{kip} \cdot \text{ft}$$

Moment Strength of Concrete Rail (k-ft)

$$M_{rail1} := M_{SR} + M_{CR} = 124.52 \cdot \text{kip} \cdot \text{ft}$$

Total Moment Capacity of Concrete Rail and Steel Rails (k-ft)

$$y_{bar1} := \frac{M_{SR} \cdot y_{SR} + M_{CR} \cdot y_{CR}}{M_{rail1}} = 29.81 \cdot \text{in}$$

Height of Resultant Force of Concrete Rail and Steel Rails (in.)

$$F_{rail1} := \frac{M_{rail1}}{y_{bar1}} = 50.125 \cdot \text{kip}$$

Total Resistance Force of Concrete Rail and Steel Rails located @ y_{bar1} (kip)



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

Steel Splice Rail Properties and Dimensions:

- a) Steel Splice Rails are A500 Gr. B Material, $F_y=46\text{ksi}$
- b) Steel Splice Rails are HSS5x3x3/8 and HSS4x3x3/8 members
- b) Steel Splice Rails bend about the y-axis

$F_{yR} = 46 \cdot \text{ksi}$	Yield Strength of Steel Splice Rails (ksi)
$Z_{S1} := 5.1\text{in}^3$	Plastic Sectional Modulus of top most Steel Splice Rail (in^3)
$M_{S1} := F_{yR} \cdot Z_{S1} = 19.55 \cdot \text{kip} \cdot \text{ft}$	Plastic Moment Strength of top most Steel Splice Rail (k-ft)
$y_{S1} := 37\text{in}$	Height of the centroid of top most Steel Splice Rail (in.)
$Z_{S2} := 4.18\text{in}^3$	Plastic Sectional Modulus of 2nd from top Steel Splice Rail (in^3)
$M_{S2} := F_{yR} \cdot Z_{S2} = 16.023 \cdot \text{kip} \cdot \text{ft}$	Plastic Moment Strength of 2nd from top Steel Splice Rail (k-ft)
$y_{S2} := 32.5\text{in}$	Height of the centroid of 2nd from top Steel Splice Rail (in.)
$Z_{S3} := 5.1\text{in}^3$	Plastic Sectional Modulus of 3rd from top Steel Splice Rail (in^3)
$M_{S3} := F_{yR} \cdot Z_{S3} = 19.55 \cdot \text{kip} \cdot \text{ft}$	Plastic Moment Strength of 3rd from top Steel Splice Rail (k-ft)
$y_{S3} := 27.25\text{in}$	Height of the centroid of 3rd from top Steel Splice Rail (in.)
$Z_{S4} := 4.18\text{in}^3$	Plastic Sectional Modulus of 4th from top Steel Splice Rail (in^3)
$M_{S4} := F_{yR} \cdot Z_{S4} = 16.023 \cdot \text{kip} \cdot \text{ft}$	Plastic Moment Strength of 4th from top Steel Splice Rail (k-ft)
$y_{S4} := 22.75\text{in}$	Height of the centroid of 4th from top Steel Splice Rail (in.)
$M_S := M_{S1} + M_{S2} + M_{S3} + M_{S4} = 71.147 \cdot \text{kip} \cdot \text{ft}$	Total Plastic Moment Strength of Steel Splice Rails (k-ft)
$y_S := \frac{M_{S1} \cdot y_{S1} + M_{S2} \cdot y_{S2} + M_{S3} \cdot y_{S3} + M_{S4} \cdot y_{S4}}{M_S} = 30.098 \cdot \text{in}$	Height of the centroid of the Steel Splice Rails (in.)



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

Find Height of Resultant Force of Concrete and Steel Splice Rails: ($y_{\bar{r}2}$)

$$M_{CR} = 17.187 \cdot \text{kip} \cdot \text{ft}$$

Moment Capacity of Concrete Rail (k-ft)

$$y_{CR} = 28.625 \cdot \text{in}$$

Height of the centroid of the Concrete Rail (in.)

$$M_S = 71.147 \cdot \text{kip} \cdot \text{ft}$$

Plastic Moment Strength of Steel Splice Rails (k-ft)

$$y_S = 30.098 \cdot \text{in}$$

Height of the centroid of the Steel Splice Rails (in.)

$$M_{\text{rail}2} := M_{CR} + M_S = 88.333 \cdot \text{kip} \cdot \text{ft}$$

Total Moment Capacity of Concrete Rail and Steel Splice Rails (k-ft)

$$y_{\bar{r}2} := \frac{M_S \cdot y_S + M_{CR} \cdot y_{CR}}{M_S + M_{CR}} = 29.811 \cdot \text{in}$$

Height of the centroid of the Concrete Rail and Steel Splice Rails (in.)

$$y_{\bar{r}1} = 29.81 \cdot \text{in}$$

Height of the centroid of the Concrete Rail and Steel Rails (in.)

$$M_{\text{rail}2_y\bar{r}1} := M_{\text{rail}2} \cdot \frac{y_{\bar{r}2}}{y_{\bar{r}1}} = 88.337 \cdot \text{kip} \cdot \text{ft}$$

Total Moment Capacity of Concrete Rail and Steel Splice Rails @ $y_{\bar{r}1}$ (k-ft)

$$M_{\text{rail}1} = 124.52 \cdot \text{kip} \cdot \text{ft}$$

Total Moment Capacity of Concrete Rail and Steel Rails (k-ft)

$$M_{\text{rail}} := \begin{cases} M_{\text{rail}2} & \text{if } M_{\text{rail}2_y\bar{r}1} < M_{\text{rail}1} \\ M_{\text{rail}1} & \text{otherwise} \end{cases} = 88.333 \cdot \text{kip} \cdot \text{ft}$$

Critical Moment Capacity Rails (k-ft)

$$y_{\bar{r}} := \begin{cases} y_{\bar{r}2} & \text{if } M_{\text{rail}2_y\bar{r}1} < M_{\text{rail}1} \\ y_{\bar{r}1} & \text{otherwise} \end{cases} = 29.811 \cdot \text{in}$$

Critical Height of the centroid of the Rails (in.)



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

Analysis of Post (Failure Section 1): P_{P1}

- Failure Section 1 (FS1) Properties and Dimensions:
 a) FS1 has a width of 15in and a height of 10in
 b) #6-Gr.40 Rebar is used for Tensile Reinforcement
 c) See Figure 6 for more information.

$$f_y = 40 \text{ ksi}$$

$$f'_c = 4 \text{ ksi}$$

$$b_{FS1} := 15 \text{ in}$$

Width of FS1 (in.)

$$A_{FS1} := 2 \cdot 0.44 \text{ in}^2 = 0.88 \text{ in}^2$$

Area of Tensile Reinforcement in FS1 (in²)

$$d_{FS1} := 7.625 \text{ in}$$

Distance to Tensile Reinf. from Compression Face of FS1 (in.)

$$y_{FS1} := y_{bar} - 14.625 \text{ in} = 15.186 \text{ in}$$

Height measured from centroid of FS1 to Resultant Force of Rails (in.)

$$a_{FS1} := \frac{A_{FS1} \cdot f_y}{0.85 \cdot f'_c \cdot b_{FS1}}$$

Whitney Stress Block Depth for FS1 (in.)

$$M_{FS1} := A_{FS1} \cdot f_y \cdot \left(d_{FS1} - \frac{a_{FS1}}{2} \right) = 21.354 \text{ kip} \cdot \text{ft}$$

Moment Strength of Post at FS1 (k-ft)

$$P_{P1} := \frac{M_{FS1}}{y_{FS1}} = 16.874 \text{ kip}$$

Strength of Post at FS1 (kip)



Analysis of Post (Failure Section 2): P_{P2}

Failure Section 2 (FS2) Properties and Dimensions:

- a) Assuming FS2 is vertical from top to bottom of upper deck at the intersection with the parapet.
- b) #5-Gr.40 Rebar is used for Tensile Reinforcement
- c) See Figure 4 for more information.

$$f_y = 40 \text{ ksi}$$

$$f'_c = 4 \text{ ksi}$$

$$L_{t,amp} = 6 \text{ ft}$$

Amplified Longitudinal Length of Distribution of Transverse Impact Force (ft)

$$h_{FS2} = 7.75 \text{ in}$$

Distance from roadway surface to centroid of FS2 (in.)
 [See figure 2 for more information]

$$H_p = 34.625 \text{ in}$$

Height of the Concrete Post and Beam measured from top of roadway surface (in.)

$$b_{FS2} := L_{t,amp} + 2 \cdot (H_p - h_{FS2}) = 10.479 \text{ ft}$$

Width of FS2 (in.)
 Note: Width of FS2 is assumed to be the impact force projected outward at a 45 degree angle to the centroid of FS2.

$$A_{FS2} := 9 \cdot 0.31 \text{ in}^2 = 2.79 \text{ in}^2$$

Area of Tensile Reinforcement in FS2 (in²)
 There are 9 bars over b_{FS2}

$$d_{FS2} := 4.25 \text{ in}$$

Distance to Tensile Reinf. from Compression Face of FS2 (in.)
 [See Figure 3 for more information]

$$a_{FS2} := \frac{A_{FS2} \cdot f_y}{0.85 \cdot f'_c \cdot b_{FS2}}$$

Whitney Stress Block Depth for FS2 (in.)

$$M_{FS2} := A_{FS2} \cdot f_y \cdot \left(d_{FS2} - \frac{a_{FS2}}{2} \right) = 38.311 \text{ kip} \cdot \text{ft}$$

Moment Strength at FS2 about the longitudinal axis (k-ft)

$$y_{FS2} := y_{bar} - 7.75 \text{ in} = 22.061 \text{ in}$$

Height measured from centroid of FS2 to Resultant Force of Rails (in.)

$$P_{P2} := \frac{M_{FS2}}{y_{FS2}} = 20.839 \text{ kip}$$

Strength of Post at FS2 (kip)



Analysis of Post (Failure Section 3): P_{P3}

Failure Section 3 (FS3) Properties and Dimensions:

- a) Assuming FS3 is vertical from top to bottom of lower deck at the intersection of the lower deck to curb.
- b) #5-Gr.40 Rebar is used for Tensile Reinforcement
- c) See Figure 5 for more information.

$$f_y = 40 \text{ ksi} \qquad f'_c = 4 \text{ ksi}$$

$$H_p = 34.625 \text{ in}$$

Height of Concrete Post and Beam
measured from top of roadway surface (in.)

$$L_{t,amp} = 6 \text{ ft}$$

Amplified Longitudinal Length of Distribution of Transverse Impact
Force (ft.)

$$h_{FS3} = 3 \text{ in}$$

Vertical distance from roadway surface to centroid of FS3 (in.)
[See Figure 2 for more information]

$$b_{FS3} = L_{t,amp} + 2 \cdot (H_p + h_{FS3}) = 12.271 \text{ ft}$$

Width of FS3 (ft.)
Note: Width of FS3 is assumed to be the impact force projected
outward at a 45 degree angle to the centroid of FS3.

$$A_{FS3} = 10 \cdot 0.31 \text{ in}^2 = 3.1 \text{ in}^2$$

Area of Tensile Reinforcement in FS3 (in²)
There are 10 bars over b_{FS3}

$$d_{FS3} = 4.25 \text{ in}$$

Distance to Tensile Reinf. from Compression Face of FS3 (in.)
[See Figure 3 for more information]

$$a_{FS3} = \frac{A_{FS3} \cdot f_y}{0.85 \cdot f'_c \cdot b_{FS3}}$$

Whitney Stress Block Depth for FS3 (in.)

$$M_{FS3} = A_{FS3} \cdot f_y \cdot \left(d_{FS3} - \frac{a_{FS3}}{2} \right) = 42.637 \text{ kip} \cdot \text{ft}$$

Moment Strength of Post at FS3 (k-ft)

$$y_{FS3} = y_{bar} + 3 \text{ in} = 32.811 \text{ in}$$

Height measured from centroid of FS3 to Resultant
Force of Rails (in.)

$$P_{P3} = \frac{M_{FS3}}{y_{FS3}} = 15.593 \text{ kip}$$

Strength of Post at FS3 (kip)



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

Analysis of Post: P_p

$P_{p1} = 16.874 \cdot \text{kip}$ Strength of Post at FS1 (kip)

$P_{p2} = 20.839 \cdot \text{kip}$ Strength of Post at FS2 (kip)

$P_{p3} = 15.593 \cdot \text{kip}$ Strength of Post at FS3 (kip)

Note: The Limiting ("worst case") Post Strength is taken as P_p

$$P_p := \min(P_{p1}, P_{p2}, P_{p3}) = 15.593 \cdot \text{kip}$$

Total Ultimate Resistance (Nominal Resistance) of Railing: R_R

One Span Failure Mode: $N_1=1$

$$P_P = 15.593 \cdot \text{kip}$$

$$N_1 := 1$$

$$M_{\text{rail}} = 88.333 \cdot \text{kip} \cdot \text{ft}$$

$$L_P = 9.823 \cdot \text{ft}$$

$$L_t = 4 \cdot \text{ft}$$

$$R_1 := \frac{16 \cdot M_{\text{rail}} + (N_1 - 1) \cdot (N_1 + 1) \cdot P_P \cdot L_P}{2 \cdot N_1 \cdot L_P - L_t} = 90.333 \cdot \text{kip}$$

Two Span Failure Mode: $N_2=2$

$$P_P = 15.593 \cdot \text{kip}$$

$$N_2 := 2$$

$$M_{\text{rail}} = 88.333 \cdot \text{kip} \cdot \text{ft}$$

$$L_P = 9.823 \cdot \text{ft}$$

$$L_t = 4 \cdot \text{ft}$$

$$R_2 := \frac{16 \cdot M_{\text{rail}} + N_2^2 \cdot P_P \cdot L_P}{2 \cdot N_2 \cdot L_P - L_t} = 57.408 \cdot \text{kip}$$



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

Total Ultimate Resistance (Nominal Resistance) of Railing: R_R

Three Span Failure Mode: $N_3=3$

$$P_P = 15.593 \cdot \text{kip}$$

$$N_3 := 3$$

$$M_{\text{rail}} = 88.333 \cdot \text{kip} \cdot \text{ft}$$

$$L_p = 9.823 \cdot \text{ft}$$

$$L_t = 4 \cdot \text{ft}$$

$$R_3 := \frac{16 \cdot M_{\text{rail}} + (N_3 - 1) \cdot (N_3 + 1) \cdot P_P \cdot L_p}{2 \cdot N_3 \cdot L_p - L_t} = 48.031 \cdot \text{kip}$$

Four Span Failure Mode: $N_4=4$

$$P_P = 15.593 \cdot \text{kip}$$

$$N_4 := 4$$

$$M_{\text{rail}} = 88.333 \cdot \text{kip} \cdot \text{ft}$$

$$L_p = 9.823 \cdot \text{ft}$$

$$L_t = 4 \cdot \text{ft}$$

$$R_4 := \frac{16 \cdot M_{\text{rail}} + N_4^2 \cdot P_P \cdot L_p}{2 \cdot N_4 \cdot L_p - L_t} = 51.809 \cdot \text{kip}$$



SUBJECT: LADOTD(LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

Total Ultimate Resistance (Nominal Resistance) of Railing: R_R

Five Span Failure Mode: $N_5=5$

$$P_P = 15.593 \cdot \text{kip}$$

$$N_5 := 5$$

$$M_{\text{rail}} = 88.333 \cdot \text{kip} \cdot \text{ft}$$

$$L_p = 9.823 \cdot \text{ft}$$

$$L_t = 4 \cdot \text{ft}$$

$$R_5 := \frac{16 \cdot M_{\text{rail}} + (N_5 - 1) \cdot (N_5 + 1) \cdot P_P \cdot L_p}{2 \cdot N_5 \cdot L_p - L_t} = 54.012 \cdot \text{kip}$$

Six Span Failure Mode: $N_6=6$

$$P_P = 15.593 \cdot \text{kip}$$

$$N_6 := 6$$

$$M_{\text{rail}} = 88.333 \cdot \text{kip} \cdot \text{ft}$$

$$L_p = 9.823 \cdot \text{ft}$$

$$L_t = 4 \cdot \text{ft}$$

$$R_6 := \frac{16 \cdot M_{\text{rail}} + N_6^2 \cdot P_P \cdot L_p}{2 \cdot N_6 \cdot L_p - L_t} = 60.835 \cdot \text{kip}$$



SUBJECT: LADOTD(LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

Total Ultimate Resistance (Nominal Resistance) of Railing: R_R

Seven Span Failure Mode: $N_7=7$

$$P_P = 15.593 \text{ kip}$$

$$N_7 = 7$$

$$M_{\text{rail}} = 88.333 \text{ kip-ft}$$

$$L_p = 9.823 \text{ ft}$$

$$L_t = 4 \text{ ft}$$

$$R_7 = \frac{16 \cdot M_{\text{rail}} + (N_7 - 1) \cdot (N_7 + 1) \cdot P_P \cdot L_p}{2 \cdot N_7 \cdot L_p - L_t} = 65.65 \text{ kip}$$

Eight Span Failure Mode: $N_8=8$

$$P_P = 15.593 \text{ kip}$$

$$N_8 = 8$$

$$M_{\text{rail}} = 88.333 \text{ kip-ft}$$

$$L_p = 9.823 \text{ ft}$$

$$L_t = 4 \text{ ft}$$

$$R_8 = \frac{16 \cdot M_{\text{rail}} + N_8^2 \cdot P_P \cdot L_p}{2 \cdot N_8 \cdot L_p - L_t} = 73.23 \text{ kip}$$



SUBJECT: LADOTD(LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

Total Ultimate Resistance (Nominal Resistance) of Railing: R_R

Note: The Total Ultimate Resistance of the bridge rail system is the minimum value of $R_1 - R_8$

$$R_r := \min(R_1, R_2, R_3, R_4, R_5, R_6, R_7, R_8) = 48.031 \cdot \text{kip} \quad \text{Total Ultimate Resistance of the bridge rail system @ } y_{\text{bar}} \text{ (kip)}$$

$$H_e = 19 \cdot \text{in} \quad \text{Height of Transverse Impact Load (in.)}$$

$$y_{\text{bar}} = 29.811 \cdot \text{in} \quad \text{Height of Resultant Force (in.)}$$


$$F_t = 71 \cdot \text{kip} \quad \text{Transverse Impact Force (kip)}$$

$$R_R := R_r \cdot \left(\frac{y_{\text{bar}}}{H_e} \right) = 75.362 \cdot \text{kip} \quad \text{Total Ultimate Resistance of the bridge rail system @ } H_e \text{ (kip)}$$


CHECK = "OK", since $R_R = 75.4 \text{ kip} > F_t = 71 \text{ kip}$

Appendix G. Details of Louisiana Retrofit Post and Beam with Safety Walk Option 2 for Tests 606861-3&4

Q:\Accreditation-17025-2017\EIFR-000 Project Files\606861-03 - LaDOT - Williams\Drafting, 606861-03\606861-3 Drawing




	Roadside Safety and Physical Security Division - Proving Ground	2020-12-02
	Project #606861-3 LADOT Bridge Rail Retrofit	Sheet 1 of 12 Test Installation
Drawn by GS	Scale 1:150	




	Roadside Safety and Physical Security Division - Proving Ground	2020-12-02
	Project #606861-3 LADOT Bridge Rail Retrofit	Scale 1:150 Sheet 2 of 12 Detail Views
Drawn by GS	Scale 1:150	

Q:\Accreditation-17025-2017\EIR-000 Project Files\606861-03 - LaDOT - Williams\Drafting - 606861-03\606861-3 Drawing



	Roadside Safety and Physical Security Division - Proving Ground	2020-12-02
	Project #606861-3 LADOT Bridge Rail Retrofit	Sheet 3 of 12 Rail Details
Drawn by GS	Scale 1:30	



Attachment Bracket

L 6 x 4 x 1/2
ASTM A36

Elevation Views




Roadside Safety and
Physical Security Division -
Proving Ground

Project #606861-3 LADOT Bridge Rail Retrofit 2020-12-02


Drawn by GS Scale 1:2 Sheet 4 of 12 Bracket Details

- 4a. Contractor shall provide material certs for all steel components.
- 4b. Galvanize all components after fabrication is complete.

Joint Assembly




Top Section, HSS 5 x 3 x 3/8



Bottom Section, HSS 4 x 3 x 3/8


Bolt, 1/2" x 1 1/2" hex A307
with Hex Nut
Type each end



Roadside Safety and
Physical Security Division -
Proving Ground


Project #606861-3 LADOT Bridge Rail Retrofit 2020-12-02

Drawn by GS Scale 1:5 Sheet 5 of 12 Joint Assembly




	Roadside Safety and Physical Security Division - Proving Ground	2020-12-02
	Project #606861-3 LADOT Bridge Rail Retrofit	Sheet 6 of 12 Concrete Details
Drawn by GS	Scale 1:150	

Concrete Section




- 7a. R1/2" this edge. Drip Stop and other exposed concrete edges as shown 3/4" each way.
- 7b. Concrete strength is 3,000 psi.
- 7c. A cold joint in the concrete is permissible here, with minimum 3 days cure time between pours (or when the first pour has reached 1500 psi compressive strength).

	Roadside Safety and Physical Security Division - Proving Ground	2020-12-02
	Project #606861-3 LADOT Bridge Rail Retrofit	Sheet 7 of 12 Concrete Section
Drawn by GS	Scale 1:15	




	Roadside Safety and Physical Security Division - Proving Ground	2020-12-02
	Project #606861-3 LADOT Bridge Rail Retrofit	Sheet 8 of 12 Rebar Placement 1
	Drawn by GS	Scale 1:15

Rebar Placement 2



Elevation View

	Roadside Safety and Physical Security Division - Proving Ground	2020-12-02
	Project #606861-3 LADOT Bridge Rail Retrofit	Sheet 9 of 12 Rebar Placement 2
Drawn by GS	Scale 1:30	




- 10a. Minimum rebar lap distance is 15" for Ø1/2" bars and 18-3/4" for Ø5/8" bars.
- 10b. Embed #5 Dowels 6" into existing concrete and secure with Hilli HY-HIT 200 epoxy according to manufacturer's instructions.
- 10c. All rebar is grade 40 ksi unless otherwise indicated. 60 ksi rebar may not be substituted. Contractor shall provide cert papers for all steel components.

**Texas A&M
Transportation
Institute**

Roadside Safety and
Physical Security Division -
Proving Ground


Project #606861-3 LADOT Bridge Rail Retrofit 2020-12-02

Drawn by GS Scale 1:10 Sheet 10 of 12 Rebar Placement 3



	Roadside Safety and Physical Security Division - Proving Ground	Project #606861-3 LADOT Bridge Rail Retrofit	2020-12-02
	Drawn by GS	Scale 1:10	Sheet 11 of 12 Rebar-Detail 1

11a. All rebar is grade 40 ksi otherwise indicated. 60 ksi rebar may not be substituted. Contractor shall provide cert papers for all steel components.



12a. All rebar is grade 40 ksi otherwise indicated. 60 ksi rebar may not be substituted. Contractor shall provide cert papers for all steel components.




Roadside Safety and Physical Security Division - Proving Ground

Project #606861-3 LADOT Bridge Rail Retrofit	2020-12-02
Drawn by GS	Scale 1:10
Sheet 12 of 12 Rebar: Detail 2	


**Appendix H. Strength Analysis for Retrofit Bridge Rail
Anchored to Solid Concrete Parapet**

1.) Given the following Details




	Texas A&M Transportation Institute	Roadside Safety and Physical Security Division - Proving Ground	2021-09-09
Project #606861	LaDOT Low Parapet	Scale 1:100	Sheet 1 of 3 Installation
Drawn by GES	Scale 1:100	2021-02-25/Low Parapet Drawing	

Figure 1. Detailed Views of Bridge Rail System



**Figure 2. Plan View of Failure
Section 2**



**Figure 3. Plan View of Failure
Section 3**




Figure 4. Section View of a Bridge Rail System




Figure 5a. Elevation View of Bridge Rail System at Ends/Joints

Figure 5b. Elevation View of Bridge Rail System at Midspan




Figure 6. Steel and Rail details




Figure 7. Steel Splice Detail




Figure 8. Steel Post and Blockout Details



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

2.) General Information:

- Concrete Parapet Strength, $f_c = 4000\text{psi}$
- Anchor Rods are $\phi 3/4" \times 12"$ long, A193 B7 Threaded Anchor: $F_u=120\text{ksi}$
- All concrete reinforcing steel = Grade 40: $f_y=40\text{ksi}$
- HSS10x4x3/8 Tube Rails are A500 Grade B Material: $F_y=46\text{ksi}$
- Reference: AASHTO LRFD Bridge Design Specifications, Section 13, TL-3 Conditions.
- Objective: Calculate the Strength of the Rail based on Worst Case Rail Strength and AASHTO LRFD Section 13 Strength Requirements.
- Use Hilti RE500 Epoxy with 10" Embedment

kips = kip

***** Concrete, Reinforcing Steel & Structural Shape Information *****

$f'_c := 4000\text{psi}$	Compressive Strength of Concrete (psi)
$F_{yR} := 46\text{ksi}$	Yield Strength of all Steel Rails (ksi)
$f_y := 40\text{ksi}$	Yield Strength of Concrete Reinforcing Steel (ksi)
$b_w := 13.5\text{in}$	Width of Concrete Parapet/Wall (in.)
$h_w := 18\text{in}$	Height of Concrete Parapet/Wall (in.)
$H_w := 28.625\text{in}$	Height of Concrete Parapet/Wall measured from roadway surface (in.)
$A_{v1} := 0.2\text{in}^2$	Area of one vertical reinforcement bar in tension zone of the Concrete Parapet/Wall (in ²)
$A_{sw1} := 0.2\text{in}^2$	Area of one longitudinal reinforcement bar in tension zone of the Concrete Parapet/Wall (in ²)

***** Anchor Rod Properties *****

$F_{u,rod} := 120\text{ksi}$	Tensile Strength of Anchor Rods (ksi)
$d_{rod} := \frac{3}{4}\text{in}$	Diameter of Anchor Rods (in)
$A_{rod} := \frac{\pi \cdot d_{rod}^2}{4} = 0.442\text{in}^2$	Area of a Anchor Rod (in ²)

MASH Design Impact Loads

Test Level	F_t (kip)	F_L (kip)	F_V (kip)	L_t/L_L (ft)	L_V (ft)	H_e (in)	H_{min} (in)
TL 1	13.5	4.5	4.5	4.0	18.0	18.0	18.0
TL 2	27.0	9.0	4.5	4.0	18.0	20.0	18.0
TL 3	71.0	18.0	4.5	4.0	18.0	24.0	29.0
TL 4 (a)	68.0	22.0	38.0	4.0	18.0	25.0	36.0
TL 4 (b)	80.0	27.0	22.0	5.0	18.0	30.0	36.0
TL 5 (a)	160.0	41.0	80.0	10.0	40.0	35.0	42.0
TL 5 (b)	262.0	75.0	160.0	10.0	40.0	43.0	42.0
TL 6	175.0	58.0	80.0	8.0	40.0	56.0	90.0

Note: (a) and (b) denote different TL 4 and TL 5 design force values for bridge rails of different heights.

$TL := 3$

Test Level

$F_t := 71 \text{ kip}$

Transverse Impact Force (kip)

$L_t := 4 \text{ ft}$

Longitudinal Length of Distribution of Transverse Impact Force (ft.)

$L_{t,amp} := 1.5 \cdot L_t = 6 \text{ ft}$

Amplified Longitudinal Length of Distribution of Transverse Impact Force (ft.)

- Note: Amplify L_t by 50% since steel rail retrofit will distribute impact load greater than what typically occurs. 50% amplification is typical of what we've seen in previous similar tests.

$H_e := 19 \text{ in}$

Height of Transverse Impact Load (in.)

$H_{e,mod} := H_e + 10 \text{ in} = 29 \text{ in}$

Modified Height of Transverse Impact Load (in.)

- Note: Due to curb and deck geometry, the impact load will be applied to the barrier at a greater height than the typical H_e . Adding 10 inches to H_e accounts for the curb height.

$F_V := 4.5 \text{ kip}$

Vertical Impact Force (kip)

$L_V := 18 \text{ ft}$

Longitudinal Length of Distribution of Vertical Impact Force (ft.)

$H_w = 28.625 \text{ in}$

Height of Concrete Parapet measured from the top of the roadway surface (in.)

$H_t := 40 \text{ in}$

Total height of bridge rail system (in.)

3.) Calculate the Bending Capacity based on Failure Section 1 about the Longitudinal Axis: $M_{c,FS1}$

Note: See Figure 1 for more information

$A_{v1} = 0.2 \cdot \text{in}^2$	Area of one vertical reinforcement leg in tension zone (in^2)
$b_c := 12\text{in}$	Unit Width of Wall (in.)
$s_{v,\text{mid}} := 12\text{in}$	Spacing of vertical reinforcement at midspan (in.)
$s_{v,\text{end}} := 12\text{in}$	Average Spacing of vertical reinforcement at the end of the parapet/wall or at a joint per the length of the longitudinal distribution of the impact force (in.)
$A_{v,\text{mid}} := \left(\frac{b_c}{s_{v,\text{mid}}} \right) \cdot A_{v1} = 0.2 \cdot \text{in}^2$	Total Area of vertical reinforcement per unit length of the wall at midspan (in^2)
$A_{v,\text{end}} := \left(\frac{b_c}{s_{v,\text{end}}} \right) \cdot A_{v1} = 0.2 \cdot \text{in}^2$	Total Area of vertical reinforcement per unit length of the wall at the end of the wall or at a joint (in^2)
$a_{c,\text{mid}} := \frac{A_{v,\text{mid}} \cdot f_y}{0.85 \cdot f_c \cdot b_c} = 0.196 \cdot \text{in}$	Depth of Whitney Stress Block at midspan (in.)
$a_{c,\text{end}} := \frac{A_{v,\text{end}} \cdot f_y}{0.85 \cdot f_c \cdot b_c} = 0.196 \cdot \text{in}$	Depth of Whitney Stress Block at the end of the wall or at a joint (in.)
$b_w = 13.5 \cdot \text{in}$	Width of the Concrete Parapet/Wall (in.)
$d_c := b_w - 1.5\text{in} - 0.25\text{in} = 11.75 \cdot \text{in}$	Extreme distance of tension vertical reinforcement of the wall (in.) $d_c = b_w - \text{stirrup cover} - (1/2) \cdot \text{diameter of stirrup}$
$M_{c,\text{mid},FS1} := \frac{\left[A_{v,\text{mid}} \cdot f_y \cdot \left(d_c - \frac{a_{c,\text{mid}}}{2} \right) \right]}{b_c} = 7.768 \cdot \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$	Flexural Resistance of Cantilever Wall specified in Article A13.4.2 at midspan (k-ft/ft)
$M_{c,\text{end},FS1} := \frac{\left[A_{v,\text{end}} \cdot f_y \cdot \left(d_c - \frac{a_{c,\text{end}}}{2} \right) \right]}{b_c} = 7.768 \cdot \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$	Flexural Resistance of Cantilever Wall specified in Article A13.4.2 at the end of the wall or at a joint (k-ft/ft)

4.) Calculate the Bending Capacity based on Failure Section 2 about the Longitudinal Axis: $M_{c,FS2}$

Failure Section 2 (FS2) Properties and Dimensions:

- a) Assuming FS2 is vertical from top to bottom of upper deck at the intersection with the parapet.
 b) #5-Gr40 Rebar is used for Tensile Reinforcement

$$f_y = 40 \text{ ksi}$$

$$f'_c = 4 \text{ ksi}$$

$$H_w = 28.625 \text{ in}$$

Height of Concrete Parapet/Wall measured from top of roadway surface (in.)

$$L_{t,amp} = 6 \text{ ft}$$

Amplified Longitudinal Length of Distribution of Transverse Impact Force (ft)

$$h_{FS2} := 7.75 \text{ in}$$

Distance from roadway surface to centroid of FS2 (in.)
 [See Figure 1 for more information]

$$b_{FS2} := L_{t,amp} + 2 \cdot (H_w - h_{FS2}) = 9.479 \text{ ft}$$

Width of FS2 (in.)
 Note: Width of FS2 is assumed to be the impact force projected outward at a 45 degree angle to the centroid of FS2.
 [See Figure 2 for more information]

$$A_{FS2} := 7 \cdot 0.31 \text{ in}^2 = 2.17 \text{ in}^2$$

Area of Tensile Reinforcement in FS2 (in²)
 [See Figure 2 for more information] There are 9 bars over b_{FS2}

$$d_{FS2} := 4.25 \text{ in}$$

Distance to Tensile Reinf. from Compression Face of FS2 (in.)
 [See Figure 1 for more information]

$$a_{FS2} := \frac{A_{FS2} \cdot f_y}{0.85 \cdot f'_c \cdot b_{FS2}}$$

Whitney Stress Block Depth for FS2 (in.)

$$M_{FS2} := A_{FS2} \cdot f_y \cdot \left(d_{FS2} - \frac{a_{FS2}}{2} \right) = 29.93 \text{ kip} \cdot \text{ft}$$

Moment Strength at FS2 about the longitudinal axis (k-ft)

$$M_{c,FS2} := \frac{M_{FS2}}{L_{t,amp}} = 4.988 \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$$

Moment Strength at FS2 about the longitudinal axis per 1 ft segment of barrier (k-ft/ft)

5.) Calculate the Bending Capacity based on Failure Section 3 about the Longitudinal Axis: $M_{c,FS3}$

Failure Section 3 (FS3) Properties and Dimensions:

- a) Assuming FS3 is vertical from top to bottom of lower deck at the intersection of the lower deck to curb.
 b) #5-Gr.40 Rebar is used for Tensile Reinforcement

$$f_y = 40 \text{ ksi}$$

$$f_c = 4 \text{ ksi}$$

$$H_w = 28.625 \text{ in}$$

Height of Concrete Parapet/Wall measured from top of roadway surface (in.)

$$L_{t,amp} = 6 \text{ ft}$$

Amplified Longitudinal Length of Distribution of Transverse Impact Force (ft)

$$h_{FS3} := 3 \text{ in}$$

Vertical distance from roadway surface to centroid of FS3 (in.)
 [See Figure 1 for more information]

$$b_{FS3} := L_{t,amp} + 2 \cdot (H_w + h_{FS3}) = 11.271 \text{ ft}$$

Width of FS3 (ft)
 Note: Width of FS3 is assumed to be the impact force projected outward at a 45 degree angle to the centroid of FS3.
 [See Figure 3 for more information]

$$A_{FS3} := 11 \cdot 0.31 \text{ in}^2 = 3.41 \text{ in}^2$$

Area of Tensile Reinforcement in FS3 (in²)
 [See Figure 3 for more information]
 There are 11 bars over b_{FS3}

$$d_{FS3} := 4.25 \text{ in}$$

Distance to Tensile Reinf. from Compression Face of FS3 (in.)
 [See Figure 1 for more information]

$$a_{FS3} := \frac{A_{FS3} \cdot f_y}{0.85 \cdot f_c \cdot b_{FS3}}$$

Whitney Stress Block Depth for FS3 (in.)

$$M_{FS3} := A_{FS3} \cdot f_y \cdot \left(d_{FS3} - \frac{a_{FS3}}{2} \right) = 46.623 \text{ kip} \cdot \text{ft}$$

Moment Strength of Post at FS3 (k-ft)

$$M_{c,FS3} := \frac{M_{FS3}}{L_{t,amp}} = 7.77 \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$$

Moment Strength of Post at FS3 per 1 ft segment of barrier (k-ft)

6.) Critical Bending Capacity of the Bridge Rail System about the Longitudinal Axis: M_c

$$M_{cmid.FS1} = 7.768 \cdot \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$$

Flexural Resistance of Cantilever Wall
 specified in Article A13.4.2 at midspan (k-ft/ft)

$$M_{cend.FS1} = 7.768 \cdot \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$$

Flexural Resistance of Cantilever Wall
 specified in Article A13.4.2 at the end of the wall or
 at a joint (k-ft/ft)

$$M_{c.FS2} = 4.988 \cdot \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$$

Moment Strength at FS2 about the longitudinal axis per 1 ft
 segment of barrier (k-ft/ft)

$$M_{c.FS3} = 7.77 \cdot \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$$

Moment Strength of Post at FS3 per 1 ft segment of barrier (k-ft/ft)

$$M_c := \min(M_{cmid.FS1}, M_{cend.FS1}, M_{c.FS2}, M_{c.FS3}) = 4.988 \cdot \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$$

Critical Bending Capacity of the Bridge Rail System
 about the Longitudinal Axis (k-ft/ft)

7.) Calculate the Bending Capacity of the Parapet/Wall about the Vertical Axis: M_w

$$A_{sw1} = 0.2 \cdot \text{in}^2 \quad \text{Area of one Longitudinal bar in tension (in}^2\text{)}$$

$$n_{sw} := 2 \quad \text{Number of Longitudinal bars in tension (in}^2\text{)}$$

$$A_{sw} := n_{sw} \cdot A_{sw1} = 0.4 \cdot \text{in}^2 \quad \text{Total Area of Longitudinal Rebar in tension (in}^2\text{)}$$

$$h_w = 18 \cdot \text{in} \quad \text{Total height of the concrete parapet (in.)}$$

$$a_w := \frac{A_{sw} \cdot f_y}{0.85 \cdot f_c \cdot h_w} = 0.261 \cdot \text{in} \quad \text{Depth of the Whitney Stress Block (in.)}$$


$$b_w = 13.5 \cdot \text{in} \quad \text{Width of the Concrete Parapet/Wall (in.)}$$

$$d_w := b_w - 1.5 \text{in} - 0.5 \text{in} - 0.25 \text{in} = 11.25 \cdot \text{in} \quad \text{Extreme distance of tension longitudinal reinforcement in wall (in.)}$$

$d_w = b_w - \text{cover} - \text{diameter of stirrups} - (1/2) \cdot \text{diameter of longitudinal bars}$

$$M_w := A_{sw} \cdot f_y \cdot \left(d_w - \frac{a_w}{2} \right) = 14.826 \cdot \text{kip} \cdot \text{ft} \quad \text{Flexural Resistance of the Concrete Parapet/Wall about the Vertical Axis(k-ft)}$$

8.) Determine the Ultimate Resistance of the Parapet at Midspan: R_{wmid}



Yield Line Analysis of Concrete Parapet Walls for Impact within Wall Segment.

$h_w = 18 \text{ in}$ Height of the Concrete Parapet/Wall (in.)
 $h_w = H$ in Figure 2

$M_B := 0 \text{ kip} \cdot \text{ft}$ No additional beam strength from the concrete

$M_c = 4.988 \cdot \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$ Flex. Resistance of the Parapet about the Long. Axis (k-ft/ft)


$M_w = 14.826 \cdot \text{kip} \cdot \text{ft}$ Flex. Resistance of the Wall about the Vert. Axis (k-ft)

$L_{t,amp} = 6 \text{ ft}$ Amplified Longitudinal length of distribution of impact force (ft.)

$$L_{cmid} := \frac{L_{t,amp}}{2} + \sqrt{\left(\frac{L_{t,amp}}{2}\right)^2 + \frac{[8 \cdot h_w \cdot (M_B + M_w)]}{M_c}} = 9.683 \text{ ft} \quad (\text{AASHTO Equation A13.3.1-2})$$

$$R_{wmid} := \left[\left(\frac{2}{2 \cdot L_{cmid} - L_{t,amp}} \right) \left[8 \cdot M_B + 8 \cdot M_w + \frac{M_c \cdot (L_{cmid})^2}{h_w} \right] \right] = 64.404 \text{ kip} \quad (\text{AASHTO Equation A13.3.1-1})$$

9.) Determine the Ultimate Resistance of the Parapet at Joints/Ends: R_{wend}



Yield Line Analysis of Concrete Parapet Walls for Impact near End of Wall Segment

$$h_w = 18 \text{ in}$$

Height of the Concrete Parapet/Wall (in.)
 $h_w = H$ in Figure 3

$$M_B = 0$$

No additional concrete beam strength

$$M_w = 14.826 \text{ kip} \cdot \text{ft}$$

Flex. Resistance of the Wall about the Vert. Axis (k-ft)

$$L_{t,amp} = 6 \text{ ft}$$

Amplified Longitudinal length of distribution of impact force (ft)

$$M_c = 4.988 \frac{\text{kip} \cdot \text{ft}}{\text{ft}}$$

Flexural Resistance of the Wall about the Longitudinal Axis at Joints/Ends specified in Article A13.4.2 (k-ft/ft)

$$L_{cend} := \frac{L_{t,amp}}{2} + \sqrt{\left(\frac{L_{t,amp}}{2}\right)^2 + h_w \cdot \left(\frac{M_B + M_w}{M_c}\right)} = 6.669 \text{ ft} \quad (\text{Equation A13.3.1-4})$$

$$R_{wend} := \left(\frac{2}{2 \cdot L_{cend} - L_{t,amp}}\right) \cdot \left[M_B + M_w + \frac{(M_c \cdot L_{cend}^2)}{h_w}\right] = 44.353 \text{ kip} \quad (\text{Equation A13.3.1-3})$$

10. Resistance of Steel Rails:

HSS10x4x3/8 Steel Rail Properties and Dimensions:

- a) Steel Rails are A500 Gr. B Material, $F_y=46\text{ksi}$
b) Steel Rails bend about the y-axis

$$F_{yR} = 46 \cdot \text{ksi}$$

Yield Strength of Steel Rail (ksi)

$$Z_{SR} := 14 \text{in}^3$$

Plastic Sectional Modulus of both Steel Rails (in^3)

$$M_{SR} := 2Z_{SR} \cdot F_{yR} = 107.333 \cdot \text{kip} \cdot \text{ft}$$

Total Plastic Moment Strength of both Steel Rails (k-ft)

$$y_{SR} := 30 \text{in}$$

Height of the centroid of the Steel Rails measured from the top of the roadway surface (in.)

Steel Splice Rail Properties and Dimensions:

- a) Steel Splice Rails are A500 Gr. B Material, $F_y=46\text{ksi}$
b) Steel Splice Rails are HSS5x3x3/8 and HSS4x3x3/8 members
c) Steel Splice Rails bend about the y-axis
d) Note: All heights measured from the top of the roadway surface

$$F_{yR} = 46 \cdot \text{ksi}$$

Yield Strength of Steel Splice Rails (ksi)

$$Z_{S1} := 5.1 \text{in}^3$$

Plastic Sectional Modulus of top most Steel Splice Rail (in^3)

$$M_{S1} := F_{yR} \cdot Z_{S1} = 19.55 \cdot \text{kip} \cdot \text{ft}$$

Plastic Moment Strength of top most Steel Splice Rail (k-ft)

$$y_{S1} := 37 \text{in}$$

Height of the centroid of top most Steel Splice Rail (in.)
(See Figure 4)

$$Z_{S2} := 4.18 \text{in}^3$$

Plastic Sectional Modulus of 2nd from top Steel Splice Rail (in^3)

$$M_{S2} := F_{yR} \cdot Z_{S2} = 16.023 \cdot \text{kip} \cdot \text{ft}$$

Plastic Moment Strength of 2nd from top Steel Splice Rail (k-ft)

$$y_{S2} := 32.5 \text{in}$$

Height of the centroid of 2nd from top Steel Splice Rail (in.)
(See Figure 4)

$$Z_{S3} := 5.1 \text{in}^3$$

Plastic Sectional Modulus of 3rd from top Steel Splice Rail (in^3)

$$M_{S3} := F_{yR} \cdot Z_{S3} = 19.55 \cdot \text{kip} \cdot \text{ft}$$

Plastic Moment Strength of 3rd from top Steel Splice Rail (k-ft)

$$y_{S3} := 27.25 \text{in}$$

Height of the centroid of 3rd from top Steel Splice Rail (in.)
(See Figure 4)



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

$Z_{S4} := 4.18 \text{ in}^3$ Plastic Sectional Modulus of 4th from top Steel Splice Rail (in³)

$M_{S4} := F_{yR} \cdot Z_{S4} = 16.023 \cdot \text{kip} \cdot \text{ft}$ Plastic Moment Strength of 4th from top Steel Splice Rail (k-ft)

$y_{S4} := 22.75 \text{ in}$ Height of the centroid of 4th from top Steel Splice Rail (in.)
 (See Figure 4)

$M_S := M_{S1} + M_{S2} + M_{S3} + M_{S4} = 71.147 \cdot \text{kip} \cdot \text{ft}$ Total Plastic Moment Strength of Steel Splice Rails (k-ft)

$y_S := \frac{M_{S1} \cdot y_{S1} + M_{S2} \cdot y_{S2} + M_{S3} \cdot y_{S3} + M_{S4} \cdot y_{S4}}{M_S} = 30.098 \cdot \text{in}$ Height of the centroid of the Steel Splice Rails (in.)

11.) Find Height of Critical Moment Capacity and Resultant Force of Steel Rails: (M_{rail} & y_{bar})

$M_{SR} = 107.333 \cdot \text{kip} \cdot \text{ft}$ Total Plastic Moment Strength of both Steel Rails (k-ft)

$y_{SR} = 30 \cdot \text{in}$ Height of the centroid of the Steel Rails (in.)

$M_{S_ySR} := M_S \cdot \left(\frac{y_S}{y_{SR}} \right) = 71.379 \cdot \text{kip} \cdot \text{ft}$ Total Plastic Moment Strength of Steel Splice Rails at y_{SR} (k-ft)

$M_{\text{rail}} := \begin{cases} M_S & \text{if } M_{S_ySR} < M_{SR} \\ M_{SR} & \text{otherwise} \end{cases} = 71.147 \cdot \text{kip} \cdot \text{ft}$ Critical Moment Capacity of Rails (k-ft)

$y_{\text{bar}} := \begin{cases} y_S & \text{if } M_{S_ySR} < M_{SR} \\ y_{SR} & \text{otherwise} \end{cases} = 30.098 \cdot \text{in}$ Critical Height of the centroid of the Rails (in.)



12.) Strength of Post at HR based on Post Yielding Pp1

$$Z_{W6x15} := 10.8 \text{ in}^3 \quad F_{yA992} := 50 \text{ ksi}$$

$$F_{T\text{post}} := 71 \text{ kip} \cdot 0.50 \quad \text{Consider 1/2 of maximum impact force on top of post (worst cast)}$$

$$H_{t\text{post}} := 30 \text{ in} - 27.25 \text{ in} = 2.75 \text{ in} \quad \text{Use max impact of center of top rail element for TL-3}$$

$$M_{\text{postimpact}} := H_{t\text{post}} \cdot F_{T\text{post}} = 8.135 \text{ kip} \cdot \text{ft}$$

$$M_{\text{postUltimate}} := Z_{W6x15} \cdot F_{yA992} = 45 \text{ kip} \cdot \text{ft}$$

$$P_{p1} := \frac{M_{\text{postUltimate}}}{H_{t\text{post}}} = 196.364 \text{ kip}$$

13.) Strength of Post based on Adhesive Anchor Strength Pp2

Design Hilti Anchorage System

$$S_{\text{anchors}} := 10 \text{ in} \quad C_{\text{anchors}} := 5 \text{ in} \quad \text{Edge and Anchor Spacing distances (inches)}$$

$$F_{v\text{Hilti}} := 31350 \text{ lbf} \cdot 1.33 \quad \text{Factored ultimate strength from Table 25, Page 151, Hilti 2016 Technical Guide for RE500V3 Epoxy with dynamic loading for 4000 psi concrete. Comparable for full scale static testing (TTI Project 490026 August 2016)}$$

$$f_{AN} := 0.70 \quad \text{Reduction factor for Spacing Table 36, Page 158, 2016 Hilti Technical Guide}$$

$$f_{RN} := 0.40 \quad \text{Reduction factor for Edge Distance With reinforcing use 0.40 factor.}$$

$$Ecc_{BP} := 6 \text{ in} \quad \text{Eccentricity of Anchor Bolts on Baseplate in Tension}$$


$$M_{\text{HiltiAnchors}} := F_{v\text{Hilti}} \cdot f_{AN} \cdot f_{RN} \cdot 2 \cdot Ecc_{BP} = 11.675 \text{ kip} \cdot \text{ft}$$

Use Hilti RE500V3 for A193B7 Threaded Rods, embedded 10 inches minimum

$$P_{p2} := \frac{M_{\text{HiltiAnchors}}}{H_{t\text{post}}} = 50.944 \text{ kip}$$

$$P_p := P_{p2} \quad \text{Limiting post strength based on Hilti Adhesive Strength}$$

14.) Calculate the strength of the Steel & Concrete Rail over 1 and 2 Span As per Section A13.3.3



- $H_R = 30\text{in}$ Centroid height to rail elements
- $H_W = 28.625\text{in}$ Height of concrete parapet
- $t_{bp} = 0.75\text{in}$ Thickness of baseplate
- $R_{wmid} = 64.404\text{kip}$ Strength of the parapet at end R_w kips
- $M_{rail} = 71.147\text{kip}\cdot\text{ft}$
- $Post_{spa} = 6\text{ft}$ Spacing of steel posts (ft.)
- $N_1 = 1$ Number of spans for calculations
- $N_2 = 2$
- $L_t = 4\text{ft}$
- $P_p = 50.944\text{kip}$ Post strength at H_R

$$R_1 := \frac{16 \cdot M_{\text{rail}} + (N_1 - 1) \cdot (N_1 + 1) \cdot P_p \cdot \text{Post}_{\text{spa}}}{2 \cdot N_1 \cdot \text{Post}_{\text{spa}} - L_t} \quad R_1 = 142.293 \cdot \text{kips} \quad \text{Strength over 1 span}$$

$$R_2 := \frac{16 \cdot M_{\text{rail}} + N_2^2 \cdot P_p \cdot \text{Post}_{\text{spa}}}{2 \cdot N_2 \cdot \text{Post}_{\text{spa}} - L_t} \quad R_2 = 118.051 \cdot \text{kips} \quad \text{Strength over 2 spans}$$

$$R_{\text{wreduced}} := \frac{R_{\text{wmid}} \cdot H_w - P_p \cdot H_R}{H_w} = 11.012 \cdot \text{kips} \quad \text{Equation A13.3.3-1 LRFD Section 13}$$

$$R_{\text{bar1}} := R_1 + R_{\text{wmid}} = 206.697 \cdot \text{kips} \quad \text{Strength of the rail 1 span (between posts)}$$

$$Y_{\text{bar1}} := \frac{R_1 \cdot H_R + R_{\text{wmid}} \cdot H_w}{R_{\text{bar1}}} = 29.572 \cdot \text{in} \quad \text{Equation A13.3.3-2 LRFD Section 13}$$




Figure A13.3.3-2 Concrete Wall and Metal Rail Evaluation—Impact at Post.



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

$$R_{\text{bar2}} := P_p + R_2 + R_{\text{wreduced}} = 180.007 \cdot \text{kips} \quad \text{Equation A13.3.3-3 LRfd Section 13} \quad \text{Strength OK for 1 and 2 spans}$$

Strength of the rail at a post

$$Y_{\text{bar2}} := \frac{P_p \cdot H_R + R_2 \cdot H_R + R_{\text{wreduced}} \cdot H_w}{R_{\text{bar2}}} = 29.916 \cdot \text{in} \quad \text{Equation A13.3.3-4 LRFD Section 13}$$

15.) Total Resistance of Bridge Rail System (as continuous): R_T

Since the rail retrofit bears on top and against the concrete parapet, consider the strength of the retrofit in addition to the concrete parapet. Centroid height of the rails very close to top of concrete parapet, therefore impact load for TL-3 will bear rail on parapet concrete

$$R_{\text{wmid}} = 64.404 \cdot \text{kip} \quad \text{Resistance of the Concrete Parapet at midspan (kip)}$$

$$R_{\text{wend}} = 44.353 \cdot \text{kip} \quad \text{Resistance of the Concrete Parapet at joints/ends (kip)}$$

Note: Due to steel rail retrofit, the failure mechanism that will occur in the concrete parapet will not occur like a typical joint/end failure.

$$R_w := R_{\text{wmid}} = 64.404 \cdot \text{kip} \quad \text{Critical Resistance of the Concrete Parapet (kip)}$$

$$H_w = 28.625 \cdot \text{in} \quad \text{Height of the Concrete Parapet measured from the roadway surface (in.)}$$

$$M_{\text{parapet}} := R_w \cdot H_w = 153.63 \cdot \text{kip} \cdot \text{ft} \quad \text{Moment Capacity of the Concrete Parapet (k-ft)}$$

$$y_{\text{bar}} = 30.098 \cdot \text{in} \quad \text{Height of the Centroid of the Steel Rails measured from the roadway surface (in.) (See Figure 4)}$$

$$M_{\text{rail}} = 71.147 \cdot \text{kip} \cdot \text{ft} \quad \text{Moment Capacity of Steel Rails (k-ft)}$$

(bending strength at the splices ... This resistance is very conservative due to dynamic strength at impact.

$$M_T := M_{\text{parapet}} + M_{\text{rail}} = 224.777 \cdot \text{kip} \cdot \text{ft} \quad \text{Total Moment Capacity of Bridge Rail System (k-ft)}$$

$$y_T := \frac{M_{\text{parapet}} \cdot H_w + M_{\text{rail}} \cdot y_{\text{bar}}}{M_T} = 29.091 \cdot \text{in} \quad \text{Centroid Height of the Total Resistance of the Bridge Rail System measured from the roadway surface (in.)}$$

$$R_T := \frac{M_T}{y_T} = 92.719 \cdot \text{kip} \quad \text{Total Resistance of the Bridge Rail System (kip)}$$

from item 15 above.



SUBJECT: LADOTD (LTRC 16) HSS
Tube Bridge Rail Retrofit LRFD
Strength Analysis

16.) Summary & Conclusions:

$$y_T = 29.091 \cdot \text{in}$$

Centroid Height of the Total Resistance of the Bridge Rail System measured from the roadway surface (in.)

$$R_T = 92.719 \cdot \text{kip}$$

Total Resistance of the Bridge Rail System at the centroid height y_T (kip)

$$H_{e,\text{mod}} = 29 \cdot \text{in}$$

Modified Height of the Transverse Impact Force, F_t due to curb and deck geometry (in.)

$$H_e = 19 \cdot \text{in}$$

From Full scale crash testing, truck impacts rail @ H_e

$$R_R := R_T \left(\frac{y_T}{H_e} \right) = 141.964 \cdot \text{kip}$$

Total Resistance of the Bridge Rail System located at H_e (kip)

$$F_t = 71 \cdot \text{kip}$$

Transverse Impact Force located at H_e (kip)

$$\text{Post}_{\text{spa}} = 6 \text{ ft}$$

Use W6x15 Post size with 2 ~ Hilti 3/4" Dia. A193 B7 Threaded Rods 12 inches long, embedded 10 inches and anchored with RE500V3

CHECK= "OK", since: $R_R = 140.0 \text{ kips @ } 19 \text{ inches height} > F_t = 71 \text{ kips}$

Appendix I. Supporting Certification Documents for Test No. 606861-3&4

CERTIFIED MATERIAL TEST REPORT FOR ASTM A307, GRADE A - HEX BOLTS

FACTORY: ZHEJIANG GOLDEN AUTOMOTIVE FASTENER CO.LTD DATE: MAY.20,2016
 ADDRESS: XITANG QIAO HAIYAN ZHEJIANG CHINA MFG LOT NUMBEF0405006
 CUSTOMER: BRIGHTON-BEST INTERNATIONAL(TAIWAN)INC. PO NUMBER: C11420
 SAMPLE SIZE: ACC. TO ASME B18.18-2011 Categories 2
 SIZE: 1/2-13X1-1/2" ZP QTY: 48150 PCS PART NO 494086
 HEADMARKS: 307A + NDF

STEEL PROPERTIES:
 STEEL GRADE: 1008 HEAT NUMBER: 1B-4201965

CHEMISTRY SPEC:	C %	Mn%	P %	S %
TEST:	0.29 max	1.20 max	0.04max	0.15max
	0.05	0.25	0.024	0.023

DIMENSIONAL INSPECTIONS		SPECIFICATION: ASME B18.2.1-2012		
CHARACTERISTICS	SPECIFIED	ACTUAL RESULT	ACC.	REJ.
APPEARANCE	ASTM F788/F788M-13	PASSED	100	0
THREAD	ANSI B1.1-08 2A	PASSED	32	0
WIDTH FLATS	0.750"-0.725"	0.728"-0.748"	8	0
WIDTH A/C	0.866"-0.826"	0.834"-0.855"	8	0
HEAD HEIGHT	0.364"-0.302"	0.308"-0.335"	8	0
BODY DIA.		FULL THREAD	8	0
THREAD LENGTH			8	0
LENGTH	1.54"-1.44"	1.46"-1.47"	8	0

MECHANICAL PROPERTIES:		SPECIFICATION: ASTM A307-2014 GR-A			
CHARACTERISTICS	TEST METHOD	SPECIFIED	ACTUAL RESULT	ACC.	REJ.
CORE HARDNESS :	ASTM E18-14a	69-100 HRB	81-85 HRB	8	0
WEDGE TENSILE :	ASTM F606-14	MIN 60KSI	72-75 KSI	4	0
ZINC PLATED	ASTM F1941-15	FE/Zn 3AN	PASS	15	0

ALL TESTS IN ACCORDANCE WITH THE METHODS PRESCRIBED IN THE APPLICABLE ASTM SPECIFICATION. WE CERTIFY THAT THIS DATA IS A REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL SUPPLIER AND TESTING LABORATORY.
All parts meet the requirements of FQA and records of compliance
 Maker's ISO#CN11/20818



(SIGNATURE OF Q.A. LAB MGR.)
 (ZHEJIANG GOLDEN AUTOMOTIVE FASTENER CO.LTD)



Phone: 800-547-6758 | Fax: 503-227-4634
 3441 NW Guam Street, Portland, OR 97210
 Web: www.portlandbolt.com | Email: sales@portlandbolt.com

CERTIFICATE OF CONFORMANCE

For: CUSTOM FABRICATORS & REPAIRS
 PB Invoice#: 133286
 Cust PO#: PO-00408
 Date: 8/13/2020
 Shipped: 8/13/2020

We certify that the following items were manufactured and tested in accordance with the chemical, mechanical, dimensional and thread fit requirements of the specifications referenced.

Description: 5/8 X 5-1/2 GALV ASTM A449 ROUND HEAD BOLT

Heat#: 3090536		Base Steel: 1045	Diam: 5/8
----------------	--	------------------	-----------

Source: COMMERCIAL METALS CO Proof Load: 19,200 LBF

C : .460	Mn: .750	P : .011	Hardness: 269 HBN
S : .021	Si: .250	Ni: .070	Tensile: 35,340 LBF RA: .00%
Cr: .110	Mo: .040	Cu: .280	Yield: 0 Elon: .00%
Pb: .000	V : .000	Cb: .001	Sample Length: 0
N : .010		CE: .6057	Charpy: CVN Temp:


LOT#19812

Nuts:
 ASTM A563DH HVY HX

Washers:
 ASTM F436-1 RND

Coatings:
 ITEMS HOT DIP GALVANIZED PER ASTM F2329/A153C

Other:
 ALL ITEMS MELTED & MANUFACTURED IN THE USA

By: 
 Certification Department Quality Assurance
 Dane McKinnon



CMC STEEL TEXAS
1 STEEL MILL DRIVE
SEGUIN TX 78155-7510

CERTIFIED MILL TEST REPORT
For additional copies call
830-372-8771

We hereby certify that the test results presented here
are accurate and conform to the reported grade specification

Roberto A. Davilla
Roberto A. Davilla
Quality Assurance Manager

HEAT NO.: 3090536		S O L D T O		S H I P T O		CPU Seguin		Delivery#: 83085550			
SECTION: ROUND 5/8 x 20"0" 1045		3441 NW Guam St		1 Steel Mill Dr		1925538		BOL#: 1925538			
GRADE: AISI 1045		Portland OR		Seguin TX		45869		CUST PO#: 45869			
ROLL DATE: 09/07/2019		US 97210-1613		US 78155-7510		9999999999		CUST P/N:			
MELT DATE: 08/15/2019		5032275488		T		O		DLVRY LBS / HEAT: 4589.000 LB			
Cert. No.: 83085550 / 090536A032		5032274634		O				DLVRY PCS / HEAT: 220 EA			
Characteristic		Value		Characteristic		Value		Characteristic		Value	
C	0.46%	Bend Test 1	Passed	<p>The Following is true of the material represented by this MTR:</p> <ul style="list-style-type: none"> *Matrix is fully killed *100% melted and rolled in the USA *EN10204:2004 3.1 compliant *Contains no weld repair *Contains no Mercury contamination *Manufactured in accordance with the latest version of the plant quality manual *Meets the "Buy America" requirements of 23 CFR635.410, 49 CFR 661 *Warning: This product can expose you to chemicals which are known to the State of California to cause cancer, birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov 							
Mn	0.75%	Yield Strength test 2	71.2ksi								
P	0.011%	Tensile Strength test 2	111.7ksi								
S	0.021%	Elongation test 2	26%								
Si	0.25%	Elongation Gage Lgth test 2	2IN								
Cu	0.28%	Bend Test Diameter	2.188IN								
Cr	0.11%	BHN @ Surface test 1	228BHN								
Ni	0.07%	Macro Etch Method	ASTM E381								
Mo	0.040%	Macro Surface Rating	1								
V	0.000%	Macro Random Rating	1								
Cb	0.001%	Macro Core Rating	1								
Sn	0.009%										
Al	0.000%										
N	0.0105%										
Yield Strength test 1	71.9ksi										
Tensile Strength test 1	112.4ksi										
Elongation test 1	17%										
Elongation Gage Lgth test 1	8IN										
Reduction of Area test 1	45%										
REMARKS : ROUND STEEL BAR CARBON GRADE HOT ROLLED											



UNYTITE INC.
INNOVATIVE FASTENING SYSTEMS

Unytite, Inc.
One Unytite Drive
Peru, IL 61354
Tel 815-224-2221
Fax 815-224-3434

INSPECTION CERTIFICATE

Job No: 32394 Job Information Certified Date: 4/2/20

Customer: Ship To:
Customer Part No:
Customer PO No: Shipped Qty:
Lot Number: 32394-6215169002

Part Information

Part No: A563 5/8-11 +0.020 DH HHN HDG BLUE DYE 
Description: ASTM A563 HHN, Grade DH, Hot Dipped Galv, Blue Dye
Manufactured Quantity: 153,268

Applicable Specifications			
Specification	Amend	Specification	Amend
ASME B1.1	2003	ASME B18.2.2	2015
ASME B18.2.6	2019	ASME B18.2.6M	2012
ASTM A563	2015	ASTM F2329/F2329M	2015
ASTM F606/606M	2019	ASTM F812	2017



Test Results
Test No: 21749 Test: A563 DH Mechanical Properties

Description	Hardness (HRC)	Tempering Temp (800 degree F Min)	Proof Load (Pass ASTM Min LBS)	Shape & Dimension ASME B18.2.2	Thread Precision ASME B18.1.1	Visual ASTM F812
Sample Inspection	28.2	1,166	33,900	Pass	Pass	Pass

Certified Chemical Analysis

Heat No	Grade	Manufacturer	Origin	C	Mn	P	S	Si	Cr	Ni	Cu
6215169002	1045	Centaur Ameristeel	USA	0.4600	0.7700	0.0090	0.0310	0.2000	0.1300	0.0700	0.2200

Notes
All tests are in accordance with the latest revisions of the methods prescribed in the applicable SAE and ASTM Specifications.
The samples tested conform the specifications as described/listed above and were manufactured free of mercury contamination and there is no welding performed in the production of the products. No heats to which Bismuth, Selenium, Tellurium, or Lead was intentionally added have been used to produce products.
The steel was melted and manufactured in the U.S.A. and the product was manufactured and tested in the U.S.A.
We certify that this data is true representation of information provided by the material supplier and our testing laboratory. This certified material test report relates only to the items listed on this document and may not be reproduced except in full.

	 Thorsen, Chris - Supervisor, Quality Date: 4/2/20
---	--

45478-1



US-ML-ST PAUL
1678 RED ROCK ROAD
SAINT PAUL, MN 55119
USA

CERTIFIED MATERIAL TEST REPORT

Page 1/1
DOCUMENT ID: 0000038284
HEAT / BATCH: 62151690/02

CUSTOMER SHIP TO
UNYTITE INC LASALLE PLANT
325 CIVIC ROAD
LA SALLE, IL 61301
USA

CUSTOMER BILL TO
UNYTITE INC
1 UNYTITE DR
PERU, IL 61354-9710
USA

SALES ORDER
8310712/000060

GRADE
1043M23F2ZN

SHAPE / SIZE
Round Bar / 7/8"

LENGTH
24 10"

WEIGHT
21.462 LB

CUSTOMER MATERIAL N°
B10455C0.8750 I

DATE
01/14/2020

REVISION
ASTM A29-16
ASTM A276-17

BILL OF LADING
1332-0000077194

DATE
01/14/2020


CHEMICAL COMPOSITION		E381 S		E381 R		E381 C	
C %	0.46	C %	0.22	C %	0.13	C %	0.18
Mn %	0.77	Mn %	0.20	Mn %	0.07	Mn %	0.18
P %	0.009	P %	0.031	P %	0.007	P %	0.018
S %	0.003	S %	0.020	S %	0.007	S %	0.018
Si %	0.031	Si %	0.20	Si %	0.07	Si %	0.18
Cr %	0.009	Cr %	0.031	Cr %	0.07	Cr %	0.13
Ni %	0.009	Ni %	0.031	Ni %	0.07	Ni %	0.13
Mo %	0.009	Mo %	0.031	Mo %	0.07	Mo %	0.13
Al %	0.009	Al %	0.031	Al %	0.07	Al %	0.13
As %	0.009	As %	0.031	As %	0.07	As %	0.13
Se %	0.009	Se %	0.031	Se %	0.07	Se %	0.13
Fe %	0.009	Fe %	0.031	Fe %	0.07	Fe %	0.13

METALLURGICAL CHARACTERISTICS		E381 S		E381 R		E381 C	
Y %	0.033	Y %	0.010	Y %	0.033	Y %	0.000
Sp %	0.010	Sp %	0.010	Sp %	0.010	Sp %	0.010
Nb %	0.000	Nb %	0.000	Nb %	0.000	Nb %	0.000
Al %	0.005	Al %	0.005	Al %	0.005	Al %	0.005

HARDENABILITY
D1 A235
I45
L37

COMMENTS / NOTES

Material 100% melted and rolled in the USA. Manufacturing processes for this steel, which may include scrap melted in an electric arc furnace and hot rolling, have been performed at Gerdau St. Paul Mill, 1678 Red Rock Road, Saint Paul, Minnesota, USA. All product produced from strand cast billets. Silicon killed (deoxidized) steel. No weld repair performed. Steel not exposed to mercury or any liquid alloy which is liquid at ambient temperatures during processing or while in Gerdau St. Paul Mills possession. Any modification to this certification as provided by Gerdau-St. Paul Mill without the expressed written consent of Gerdau St. Paul Mill negates the validity of this test report. This report shall not be reproduced except in full, without the expressed written consent of Gerdau St. Paul Mill. Gerdau St. Paul Mill is not responsible for the inability of this material to meet specific applications.
Roll batch 62151690/02 roll date 12/5/2019 Fine Grain (FG 5-8)
Quality Program Manual Rev. 10, Implemented date 11/8/2019
Macro S1 R1 C1 Reduction Ratio: 49.9 (ASTM E381-17 E4.5.18a)



Debra L. Kariesch

The above figures are certified chemical and physical test records as contained in the permanent records of Company. We certify that these data are correct and in compliance with specified requirements. Weld repair has not been performed on this material. This material, including the billets, was melted USA. CMTR complies with EN 10204 3.1.

Blaskov
BIASKAR YALAMANCHILI
QUALITY DIRECTOR

Phone: (609) 367-1071 Email: Blaskar.Yalamanchili@gerdau.com

M
ALEA BRANENBURG
QUALITY ASSURANCE MGR.

Phone: (611) 731-5662 Email: Alea.Brandenburg@gerdau.com

Universal Galvanizing, Inc.

510 E. South 1st St.
Wright City, Missouri 63390
Phone:(636)791-2016 Fax:(636)745-0667

Date: 3-27-20

RE: GALVANIZING CERTIFICATE
UNYTITE, INC.
PO# P009098

QTY	PART NUMBER/DESCRIPTION	LOT NUMBER	COATING THICKNESS
153,268	A563 5/8-11+0.020 GRADE DH HEAVY HEX NUT	32394-6215169002	3.5 AVG. MILS
148,064	A563 5/8-11+0.020 GRADE DH HEAVY HEX NUT	32395-6215169002	3.5 AVG. MILS

THIS WILL CERTIFY THAT THE MATERIAL GALVANIZED ON THE ABOVE JOB MEETS ASTM F2329 SPECIFICATIONS. THIS MATERIAL WAS GALVANIZED IN THE USA AT UNIVERSAL GALVANIZING INC IN WRIGHT CITY, MO AT A ZINC BATH TEMPERATURE OF 840° WITH A PLUS MINUS VARIANCE OF 5°. THE MATERIALS ITEMIZED IN THIS SHIPMENT ARE CERTIFIED TO BE IN COMPLIANCE WITH THE APPLICABLE ASTM STANDARDS AND THE IOWA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, IMs AND MEET THE BUY AMERICA REQUIREMENTS AS DESCRIBED IN IM 107 FOR ALL STEEL, IRON PRODUCTS AND COATINGS.

Joseph Jokisch

Joseph Jokisch, Quality/ Shipping & Receiving



TECHNICAL STAMPING, INC.

50600 E. RUSSELL, SCHMIDT BLVD.
CHESTERFIELD TWP., MI 48051
PH(586)948-3285 / FX(586)948-3286

**MATERIAL
CERTIFICATION**

CUSTOMER NAME		CUSTOMER ORDER NUMBER				DATE			
Portland Bolt & Mfg Co		45681				5/4/2020			
PART NUMBER - CUSTOMER LOT NO.		LOT NUMBER				QUANTITY			
5/8" F436 Hdg 16443		1019-282				20,000			
STEEL GRADE	HEAT	C	MN	P	S	SI	AL	REVISION	
	31938550	.52	.72	.008	.0001	.24	.028	ASTM F-436-10	
SPECIFICATION		ACTUAL				GAUGE			
O.D - 1.281 - 1.345		1.313 - 1.316				CALIPER			
I.D - .688 - .720		.703 - .706				CALIPER, PIN GAUGE			
THICKNESS- .122 - .177		.123 - .126				MICROMETER			
FLAT- Max .010		.003				CALIPER			
HEAT TREAT - 38 - 45HRC		41 - 43							
PLATING-		See Attached Cert							
OTHER		N/A							

WE HEREBY CERTIFY THIS PRODUCT WAS PRODUCED UNDER A ISO 9001 QUALITY ASSURANCE SYSTEM. ISO 9001 CERTIFICATION NUMBER-1255 - DATE OF REGIS. JAN. 3 2003
ALL MATERIALS ARE MADE AND MELTED IN THE U.S.A. THIS PRODUCT WAS MANUFACTURED IN CHESTERFIELD, MICHIGAN, U.S.A. THIS PRODUCT CONFORMS TO ALL REQUIREMENTS
FOR WASHERS AS PRODUCED ACCORDING TO A.S.T.M. F-436-10. THE ABOVE TEST RESULTS APPLY ONLY TO THE ITEMS TESTED. THIS TEST REPORT MUST NOT BE REPRODUCED
EXCEPT IN FULL WITHOUT PRIOR WRITTEN APPROVAL.

**CERTIFIED
ISO 9001:**

Shirley M. McKen
AUTHORIZED SIGNATURE

"MADE AND MANUFACTURED IN THE USA"

Qty 3008 Rev. 2 11/25/01

45681-2

9350

INDUSTRIAL STEEL TREATING COMPANY, INC

613 Carroll Street Jackson, MI 49202
P.O. Box 98 Jackson MI, 49204
Voice: 517-787-6312 Fax: 517-787-5441

HEAT TREAT CERTIFICATION

Customer:
TECHNICAL STAMPING, INC.
Attn: SHANNON COX
50600 E. RUSSELL SCHMIDT
CHESTERFIELD, MI 48051

Certification Date:
10/29/2019

Page: 1 of 1

Order Details

Part Number: F0058
Packing Slip: 7259
Purchase Order:
IST Order Number: 801460-1
Lot Number: 1019-282
Heat Number: 31938550

Blue Print Rev: 1279
Material Type: 1030 - 1050
Quantity: 400,244
Net Weight: 13,128.0
Part Desc: WASHER
Comments: 9 TUBS#1218,1989,C91,951,
416,921,003,640,655


SPECIFICATIONS

HRC 38 - 45
HEAT TREATED IN THE USA

RESULTS

HRC 41-43
HEAT TREATED IN THE USA

Approval:



Tom Levy - Quality Assurance Supervisor

Contact

Tom Levy - Quality Assurance Supervisor
Voice: 517-780-9043 Fax: 517-787-5441
E-Mail: tolevy@indstl.com

This Certification cannot be reproduced except in full, without written authorization from Industrial Steel Treating Company, LLC.

9350

CERTIFICATE OF CONFORMANCE

SABRE STEEL INC.
23680 RESEARCH DRIVE
FARMINGTON HILLS, MI 48335
248-615-0500



10/14/2019 1:23:57 PM

Sold To: TECHNICAL STAMPING
50600 E. RUSSELL SCHMIDT BLVD.
CHESTERFIELD TWP., MI 48051

Ship To: TECHNICAL STAMPING
50600 RUSSELL SCHMIDT BLVD.
CHESTERFIELD TWP., MI 48051

Cust PO: S91539

Ship Date: 10/15/2019

Sales Order: 77172

Weight: 29,710#

CHEMICAL ANALYSIS

Heat Number:	31938550			
C: .52	Mn: .72	P: .008	S: .0001	
Si: .24	Ti: .001	Cr: .04	Mo:	
Cu: .10	Al: .028	Cb:	Va: .002	
Ni: .03	B:	Sn:	N:	

PHYSICAL PROPERTIES


YS: TS: E:

Chemistry: C1050

Line: 1 Item: .122min X 3.9500 C1050
Grade: HRP&O High Carbon
Cust Part: F0058M

Comment: Tags 065946 A thru H Made & Melted In The USA

WE HEREBY CERTIFY THE ABOVE FIGURES ARE ACCURATELY STATED, MEET YOUR MATERIAL REQUIREMENTS AND ARE TRACEABLE IN OUR RECORDS BACK TO THE PRODUCER AND/OR AN ACCREDITED TEST LABORATORY.


Quality Assurance Manager

4350



4500 County Road 59
Butler, IN 46721 USA
Telephone (260) 868-8000
Fax (260) 868-8955

Metallurgical Certification

Cert # 3360599

Voss Industries - T 7925 Beech Daly Road Taylor, MI 48180 United States		Contact Taylor RECEIVING P: 313-291-8535		Coil # 19B448749	Coil Alias Heat # 31938550
Ship To	Sabre Steel Inc. 23680 Research Drive Farmington Hills, MI 48335 United States		Order # 663249		PO # 65716 - 4
Sold To	Contact Bob Alexander P: 847-695-2900 F: 847-695-2950		Line Item # 4	Part #	
Length 2.227 ft. / 679 m	Width 50.250 in. / 1,276 mm	Material Spec. SAE 1050 WITH SILICON			
Weight 49,350 lbs / 22,384.77 kg	Gauge 0.1250 in. / 3.18 mm Mn	Product Desc. Prime Hot Rolled Band			
Chem Treat Oiled		Cert Comment			
Surface Treatment					

Ladle Chemical Analysis (%)

C	Mn	P	S	Si	Al	Cu	Ni	Cr	Mo	Sn	N	V	Nb	Ti	B	Ca	Pb	Zr
0.52	0.72	0.008	0.000	0.24	0.028	0.10	0.03	0.04	0.02	0.007	0.007	0.002	0.000	0.001	0.0000	0.002	0.000	0.0001

Mechanical Properties (If applicable)

Hiroshi Kimura
Hiroshi Kimura
Metallurgist

Shipped from Butler, IN, United States.
Melted, thin slab cast and rolled by proud Americans in Butler, IN, USA.
SDI does not weld or repair Prime Hot Rolled Band products.
All tests were performed according to applicable standards and are correct as contained in the records of the company.



January 09, 2020

Technical Stamping
50600 E. Russell Schmidt
Chesterfield TWP, MI 48051

To Whom It May Concern:

This is to certify that the hot dip galvanizing of the following washers on your Purchase Order number 1651 conforms to specification ASTM A-153. The following sizes and lot numbers comply with the coating, workmanship, finish, and appearance requirements of ASTM F2329 specifications. The hot dip galvanizing is ROHS compliant. The galvanizing process was conducted in a temperature range of 830F to 855F.

<u>PIECES</u>	<u>PART# & SIZE</u>	<u>LOT NUMBER</u>	<u>AVERAGE ZINC COATING IN MILS.</u>
90,090	#F0058 5/8" WASHER	1019-282	4.18

This certification in no way implies anything other than the quality of our hot dip galvanizing as it pertains to your order.

This product was galvanized in Rockford, IL USA

Yours very truly,

AZZ Galvanizing Rockford, IL

A handwritten signature in cursive script that reads "Peggy Doering".

Peggy Doering
Office Manager

PD:ac



Vulcan Threaded Products
 10 Cross Creek Trail
 Pelham, AL 35124
 Tel (205) 620-5100
 Fax (205) 620-5150

JOB MATERIAL CERTIFICATION

Job No: 676043	Job Information	Certified Date: 6/8/20
Containers: S17187917		
Customer: Interstate Threaded Products		Ship To: 2200 Singleton Blvd Dallas, TX 75212
Vulcan Part No: ATR B7 5/8x12 HDG		
Customer Part No: ATR B7 5/8x12 HDG		
Customer PO No: 43237		Shipped Qty: 96 Ft
Order No: 403988		Line No: 3
Note:		

Applicable Specifications				
Type	Specification	Rev	Amend	Option
	ASTM F1554 Gd 105 S4	2018		
Heat Treat	ASME SA-193/SA-193M B7	2013		
	ASTM A193 B7	2019		

Test Results
 See following pages for tests

Certified Chemical Analysis									
Heat No: 20688450								Origin: USA	
C	Mn	P	S	Si	Cr	Mo	Ni	V	Cu
0.42	0.85	0.010	0.003	0.29	0.88	0.15	0.05	0.001	0.14
Al	Nb	Sn	Ti	N	B	Dl	RR	G.S.	Macro S
0.029	0.002	0.007	0.001	0.0050	0.0001	4.57	160:1	fine	1
Macro R	Macro C	J1	J2	J3	J4	J6	J6	J7	J8
1	1	57	57	57	57	57	54	53	51
J9	J10	J12	J14	J16	J18	J20	J24	J28	J32
50	48	46	44	41	40	39	37	34	33

Notes

Processed material is Tempered - Stress Free. No weld repair performed on the material. No Mercury used in the production of this material. Melted and Manufactured in the USA.
 Grade - 4140
 EAF Melted



Vulcan Threaded Products
 10 Cross Creek Trail
 Pelham, AL 35124
 Tel (205) 620-5100
 Fax (205) 620-5150

JOB MATERIAL CERTIFICATION

Job No: 668113	Job Information	Certified Date: 4/8/20
Containers: S17411160		
Customer: Winzer Corp		Ship To: 1214 S. Texas Ave Bryan, TX 77803-4582
Vulcan Part No: ATR B7 3/4x12 HDG		
Customer Part No: ATR B7 3/4x12 HDG		
Customer PO No: 1103397		Shipped Qty: 1 containers
Order No: 407308		Line No: 1
Note:		

Applicable Specifications

Type	Specification	Rev	Amend	Option
-	ASTM F1554 Gd 105 S4	2018		
Heat Treat	ASTM A193 B7	2019		

Test Results

See following pages for tests

Certified Chemical Analysis

Heat No: 10649220										Origin: USA
C	Mn	P	S	Si	Cr	Mo	Ni	V	Cu	
0.41	0.87	0.018	0.024	0.27	0.91	0.20	0.06	0.002	0.16	
Al	Nb	Sn	Ti	N	B	DI	FR	G.S.	Macro S	
0.028	0.001	0.007	0.002	0.0070	0.0001	5.21	54:1	fine	1	
Macro R	Macro C	J1	J2	J3	J4	J5	J6	J7	J8	
1	1	57	57	57	57	57	57	55	54	
J9	J10	J12	J14	J16	J18	J20	J24	J28	J32	
53	51	49	47	45	44	43	41	39	37	

Notes

Processed material is Tempered - Stress Free. No weld repair performed on the material. No Mercury used in the production of this material. Melted and Manufactured in the USA.
 Grade - 4140
 EAF Melted



Vulcan Threaded Products
 10 Cross Creek Trail
 Pelham, AL 35124
 Tel (205) 620-5100
 Fax (205) 620-5150

JOB MATERIAL CERTIFICATION

Job No: 668113 **Job Information** **Certified Date:** 4/8/20
Containers: S17411160

Test Results

Part No: BAR B7 .6813x292 HT

Test No: 59660 **Test:** Quench & Temper Information (Lbs)

Description	Austenitizing Temp (F)	Tempering Temp (F)	Run Speed (Ft/min)	Quench Water Temp (F)	Note
Results	1,660	1,346	40	89	

Test No: 59665 **Test:** Partial Decarb Test

Description	Surface Carb.	Partial Surface Decarb.	Note
	Pass	Pass	

Test No: 59666 **Test:** F1554-105 FB Requirements

Description	Tensile (ksi)	Yield 0.2% Offset (ksi)	Elongation (%)	Elongation Gage Length (8in)	ROA (%)	Note
	138	129	13.1	8in	58.8	tested by external provider

Test No: 59667 **Test:** A193 B7, F1554-105 Requirements

Description	Tensile (ksi)	Yield 0.2% Offset (ksi)	Elongation (%)	Elongation Gage Length	ROA (%)	Midradius Hardness	Surface Hardness	Center Hardness	Hardness Test Type	Note
139	127	22	4D	61	29	29	29	29	HRC	
138	127	21	4D	59	30	30	29	29	HRC	
137	125	20	4D	64	28	29	29	29	HRC	
137	129	21	4D	61	29	29	29	29	HRC	
139	128	19	4D	61	29	29	29	29	HRC	
138	125	19	4D	62	29	29	28	28	HRC	
137	126	21	4D	61	29	29	29	29	HRC	
139	128	20	4D	61	30	30	30	30	HRC	
137	126	19	4D	61	29	29	29	29	HRC	

Test No: 59668 **Test:** F1554 Gd105 S4 Charpy ft/lbs Requirements

Description	Container	Test Temp (F)	Test1 (ft/lbs)	Test2 (ft/lbs)	Test3 (ft/lbs)	Results Avg (ft/lbs)	Note
		-20	81	102	86	90	

The reported test results conform to the specifications listed above.
 The reported test results are the actual values measured on the samples taken from the production lot.
 Material was manufactured, tested, and inspected as required by the product standard and in accordance with Vulcan's ISO 9001:2015 Quality Management System registered June 30th, 2017.
 Material was tested in accordance with the current revision of ASTM A370, F606, and F2328 test methods.
 This test report shall not be reproduced or distributed, except in full, without the written permission of Vulcan Steel Products.
 Document is in accordance with EN 10204 - 3.1B of 2004 (3.1).


 Norwood, Sallie - Certification Engineer Date: 4/8/20

**CERTIFIED MATERIAL TEST REPORT
FOR ASTM A194/A194M-10a GRADE 2H HVY HEX NUTS**

FACTORY: NINGBO HAIXIN HARDWARE CO.,LTD. DATE: AUG.08.2011
 ADDRESS: XIJINGTANG,LUOTUO NINGBO ZHEJIANG 315205
CHINA MFG LOT NUMBER: 1033130006
 CUSTOMER: BRIGHTON-BEST INTERNATIONAL (TAIWAN) INC PO NUMBER: U04584
 QNTY SHIPPED: 28.800MPCS PART NO: 313150
 SAMPLE SIZE : ACC. TO ASME B18 . 18 . 1 - 02
 SIZE & DESCRIPTION: 5/8-11+0.020"(HDG)

STEEL PROPERTIES:

STEEL GRADE: SWRCH45K SIZE: 25mm HEAT NO: 331105231

CHEMISTRY COMPOSITION:

CHEMIST	C %	Mn %	P %	S %	Si %	Cr %	Ni %	Cu %	Mo %	OTHERS
SPE:	MIN	MAX	MAX	MAX	MAX					
	0.40	1.00	0.04	0.05	0.40					
TEST:	0.45	0.73	0.009	0.01	0.21					

DIMENSIONAL INSPECTIONS


CHARACTERISTICS	TEST METHOD	SPECIFICATION: ASME/ANSI B18 . 2 . 2 - 87(R1999)			
		SPECIFIED	ACTUAL RESULT	ACC.	REJ.
APPEARANCE	ASTM F812-02		PASSED	100	0
WIDTH A/F	1.031 "-1.062"		1.042"-1.052"	32	0
WIDTH A/C	1.175"-1.227 "		1.180"-1.221"	32	0
THREAD	ASME B1.1-02		PASSED	8	0
HEIGHT	0.587"-0.631"		0.597"-0.611"	32	0
MARK	2H* LM		PASSED	100	0

MECHANICAL PROPERTIES:

CHARACTERISTICS	TEST METHOD	SPECIFICATION: ASTM A194-10a			
		SPECIFIED	ACTUAL RESULT	ACC.	REJ.
HARDNESS	ASTM E18-05	24-35HRC	HRC28-30	5	0
PROOF LOAD	ASTM F606-07	39550lbf	39550lbf	5	0
DECARBURIZATION	SAE J121		PASSED	1	0
HARDNESS AFTER 24H AT 540 ^o C	ASTM A194 MIN 89 HRB		HRB 92-94	5	0
TEMPERING TEMPERATURE	Min455 ^o C		PASSED(520 ^o C)		
MACROETCH	ASTM E381	S1/R1/C1-S4/R4/C4	S2/R2/C2	5	0

PARTS ARE MANUFACTURED AND TESTED IN ACCORDANCE WITH ASTM A194/A194M-10a
 ALL TESTS IN ACCORDANCE WITH THE METHODS PRESCRIBED SPECIFICATION. WE CERTIFY
 THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL
 SUPPLIER AND OUR TESTING LABORATORY.

All parts meet the requirements of FQA and records of compliance are on file.
 Maker's ISO#00109Q10593R0M/3302


 (SIGNATURE OF Q.A. LAB MGR.)
 (NAME OF MANUFACTURER)

NINGBO DONGXIN HIGH-STRENGTH NUT CO.,LTD

TEST CERTIFICATE (EN 10204.3.1)

TEL:0086-574-86531750

FAX:0086-574-86531751

www.d-x.com.cn

dongxin@d-x.com.cn

Customer: BRIGHTON-BEST INTERNATIONAL	P/O NO.: B16100374	QTY(MP): 33.75	INVOICE NO: 17075DX228-018
	Product Description: ASTM A194 2H Heavy Hex Nuts		
	Specification: 3/4"-10	T/O: 0.51	Lot#: 1610DX228-0242
	Material: 45K	Surface Finish: HDG	Heat No.: J11604926
	Mark: DX,2HZN	Part Number:	313200

Chemical Composition

Specification:ASTM A194-16

Element	C	Mn	P	S	Si
Requirement	≥0.40	≤1.00	≤0.04	≤0.05	≤0.40
Result	0.44	0.69	0.019	0.004	0.15

Mechanical Properties

Specification:ASTM A194-16

Test Item	Standard	Results	Sampling	Test method
Hardness after Treatment (540°C 24h HRB)	MIN89	92-94	5	ASTM E18-14
Hardness HRC	24 - 35	27 - 31	4	ASTM E18-14
Proof loading LBF	58450	58736	3	ASTMA962/A962M-09

Dimensions

Specification:ASTM/ANSI/ASME B18.2.2.10

Test Item	Spec.	Inspection Results	Sampling	Rej	Remark	Test method
Width across flats(mm)	30.78 - 31.75	31.24-31.42	125	0	OK	-----
Width across angle(mm)	35.10 - 36.65	35.80-35.97	125	0	OK	-----
Height(mm)	18.03 - 19.25	18.52-18.72	125	0	OK	-----
Go Gauge	GO	GO	125	0	OK	ASTM B1.1-02
No-Go	NO GO	NO GO	125	0	OK	ASTM B1.1-02
Appearance	OK	OK	125	0	OK	ASTM F812-07

MACROETCH

Division	Surface Condition	Random Condition	Center Segregation	Spec. Of test method
Spec.	S2	R2	C3	ASTM E381
Results	S2	R2	C3	

NOTE: Test Standards:ASTM A194/A194M-2016/ WAF TO DIN934-1987 H=D (HEIGHT=1 DIAMETER) Standard Specification for Carbon and Alloy Steel nuts.
Quench at 830°C about 80 minutes, Tempering at 550°C about 80 minutes
We hereby certify that all the above results are original from our actual testing, and the products have proved to comply with the relevant standards.
Signed on Behalf of Ningbo Dongxin High- Strength Nut Co., Ltd. Date:2017.02.27

(2)


宁波东鑫高强度螺母有限公司
NINGBO DONGXIN HIGH-STRENGTH NUT CO., LTD

HEXICO ENTERPRISE CO., LTD.

NO.355-3,SEC. 3,CHUNG SHAN ROAD,KAU-JEN,TAINAN,TAIWAN,R.O.C.
 TEL : 886 - 6 - 2390616 FAX : 886 - 6 - 2308947

INSPECTION CERTIFICATE

MARKING



CUSTOMER PORTEOUS FASTENER CO.
 PART NAME ASTM F436 - 09 TYPE 1 WASHERS (HOT DIP GALV. PER ASTM A153)
 SIZE 3/4 " DATE April 08, 2011
 PART NO. W2A6C6000S6JV REPORT NO. 1000408-02
 CUST. PART NO. 00385-3200-024 SHIPPING NO. _____
 MATERIAL / DIA. 10B20 / 23 mm ORDER NO. 10122251
 HEAT(COIL) NO. 3B143 LOT NO. 022C6PF41
 LOT QTY 72,000 PCS DOCUMENT NO. 9709015
 STANDARD OF SAMPLING SCHEME ANSI / ASME B18.18.2 M

DIMENSIONS IN inch

INSPECTION ITEM	SPECIFICATION	INSPECTION RESULTS		REMARKS	
		MIN.	MAX.		
1	OUTSIDE DIAMETER	1.4360 - 1.5000	1.4547	1.4681	
2	INSIDE DIAMETER	0.8130 - 0.8450	0.8311	0.8354	
3	THICKNESS	0.1220 - 0.1770	0.1311	0.1394	
4	HARDNESS	HRC 26 - 45	26.1	27.0	
5	COATING	HOT DIP GALV. 43 μm	46.0	75.6	
6	APPEARANCE	VISUAL	OK		

HOT DIP GALV. 43 μm	1	2	3	4	5	6	7	8	9	10
SAMPLE SIZE : 10 PCS	49.1	58.2	62.0	75.6	71.4	49.2	51.4	56.9	66.7	46.0


INSPECTED BY Yu Tain Lin CERTIFIED BY Jing Yeh Tsao

HEXICO ENTERPRISE CO., LTD.

NO.355-3,SEC. 3,CHUNG SHAN ROAD,KAU-JEN,TAINAN,TAIWAN,R.O.C.
 TEL : 886 - 6 - 2390616 FAX : 886 - 6 - 2308947

INSPECTION CERTIFICATE

MARKING



CUSTOMER PORTEOUS FASTENER CO.
 PART NAME ASTM F436 - 09 TYPE 1 WASHERS (HOT DIP GALV. PER ASTM A153)
 SIZE 5/8 " DATE April 01, 2011
 PART NO. W2A6C5000S6JV REPORT NO. 1000401-01
 CUST. PART NO. 00385-3000-024 SHIPPING NO. _____
 MATERIAL / DIA. 10B20 / 20 mm ORDER NO. 10122251
 HEAT(COIL) NO. 1Q961 LOT NO. 022C5PF41
 LOT QTY 72,000 PCS DOCUMENT NO. 9802003
 STANDARD OF SAMPLING SCHEME ANSI / ASME B18.18.2 M

DIMENSIONS IN inch

INSPECTION ITEM	SPECIFICATION	INSPECTION RESULTS		REMARKS	
		MIN.	MAX.		
1	OUTSIDE DIAMETER	1.2810 - 1.3450	1.2909	1.3181	
2	INSIDE DIAMETER	0.6880 - 0.7200	0.7134	0.7197	
3	THICKNESS	0.1220 - 0.1770	0.1264	0.1421	
4	HARDNESS	HRC 26 - 45	26.5	31.4	
5	COATING	HOT DIP GALV. 43 μm	46.6	104.0	
6	APPEARANCE	VISUAL	OK		

HOT DIP GALV. 43 μm	1	2	3	4	5	6	7	8	9	10
SAMPLE SIZE : 10 PCS	46.6	50.6	99.2	84.7	81.6	104.0	101.0	88.3	65.1	70.9

INSPECTED BY Yu Tain Lin CERTIFIED BY Jing Yeh Tsao

Atlas Tube Canada
 200 Clark St.
 Harrow Ontario Canada
 N0R 1G0
 Tel: 519-738-3541
 Fax: 519-738-3537



REF. B/L: 80954217
 Date: 06/01/2020
 Customer: 192

Sold To
 Tritle S. Steel Supply
 PO Box 21119
 HOUSTON TX 77026
 USA

Shipped To
 Intsel Steel Distributors
 11310 West Little York
 HOUSTON TX 77041
 USA

MATERIAL TEST REPORT

Material: 7.0x5.0x250x40 010(2x2).

Material No: 70050250

Sales Order: 1514677

Purchase Order: WLY-24734

Heat No C Mn 0.190 0.780
 P 0.009
 S 0.009
 Si 0.014
 Al 0.034
 Cu 0.057
 Cb 0.004
 Cr 0.034
 Ni 0.020
 Mo 0.007
 Ti 0.002
 V 0.002
 B 0.002
 N 0.0040
 Ca 0.0002

Made in: Canada
 Melted in: Canada

PCS Yield 057709 Psi
 Tensile 066926 Psi
 Eln.2in 34.5 %
 Recycled Content 36.90%
 Method BOF
 MILL STELCO
 Nanticoke, ON

Material Note:
 Sales Or. Note:

Material No: 100060250

Material: 10.0x6.0x250x48 010(2x1).

Sales Order: 1521362

Purchase Order: WLY-24807

Heat No C Mn 0.190 0.810
 P 0.009
 S 0.009
 Si 0.017
 Al 0.045
 Cu 0.050
 Cb 0.005
 Cr 0.041
 Ni 0.016
 Mo 0.004
 Ti 0.002
 V 0.002
 B 0.002
 N 0.0040
 Ca 0.0002

Made in: Canada
 Melted in: Canada

PCS Yield 063304 Psi
 Tensile 073933 Psi
 Eln.2in 36.5 %
 Recycled Content 36.90%
 Method BOF
 MILL STELCO
 Nanticoke, ON

Material Note:
 Sales Or. Note:

Material No: 100060250

Authorized by Quality Assurance: *James Richard*

The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements. CE calculated using the AWS D1.1 method.





Atlas Tube Canada
 200 Clark St.
 Harrow Ontario Canada
 NOR 1G0
 Tel: 519-738-3541
 Fax: 519-738-3537

Sold To
 Triple S Steel Supply
 PO Box 21119
 HOUSTON TX 77026
 USA

REF B/L: 80954217
 Date: 06/01/2020
 Customer: 192

Shipped To
 Intsel Steel Distributors
 11310 West Little York
 HOUSTON TX 77041
 USA

MATERIAL TEST REPORT

Material: 10.0x6.0x250x48.0"0(2x2).		Material No: 100060250	Made in: Canada
Sales Order: 1521362	Purchase Order: WLY-24807		Melted in: Canada
Heat No: 797482	C Mn P S Si	Al Cu Cb Cr Mo Ni	V Ti B N Ca
	0.200 0.790 0.014 0.009 0.014	0.034 0.048 0.004 0.042 0.004 0.017	0.002 0.002 0.002 0.002 0.002 0.002
Bundle No: M201435080	Yield 071252 Psi	Eln.2in 32.5 %	CE: 0.35
Heat: 797482	MILL: STELCO	Recycled Content: 36.90%	ASTM A500-18 GRADE B&C
	Mill Location: Nanticoke,ON	Method: BOF	Pre-Consumer (Post Industrial): 14.40%
Material Note:			% Harvested: 100%
Sales Or. Note:			Within Miles of Location: 1000
Material: 10.0x8.0x625x25.0"0(1x1)REC		Material No: 100080625	Made in: Canada
Sales Order: 1521862	Purchase Order: WLY-24818		Melted in: Canada
Heat No: 842890	C Mn P S Si	Al Cu Cb Cr Mo Ni	V Ti B N Ca
	0.190 0.800 0.014 0.008 0.016	0.050 0.048 0.005 0.061 0.006 0.019	0.002 0.002 0.002 0.002 0.002 0.002
Bundle No: M201426482	Yield 059292 Psi	Eln.2in 32.3 %	CE: 0.34
Heat: 842890	MILL: STELCO	Recycled Content: 36.90%	ASTM A500-18 GRADE B&C
	Mill Location: Nanticoke,ON	Method: BOF	Pre-Consumer (Post Industrial): 14.40%
Material Note:			% Harvested: 100%
Sales Or. Note:			Within Miles of Location: 1000

Authorized by Quality Assurance: *Jan-Redwood*
 The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements.
 CE calculated using the AWS D1.1 method.



REF. B/L: 80954217
 Date: 05/01/2020
 Customer: 192



Atlas Tube Canada
 200 Clark St.
 Harrow Ontario Canada
 NOR 160
 Tel: 519-738-3541
 Fax: 519-738-3537

Sold To
 Triple S Steel Supply
 PO Box 21199
 HOUSTON TX 77026
 USA

MATERIAL TEST REPORT

Shipped To
 Intset Steel Distributors
 11310 West Little York
 HOUSTON TX 77041
 USA

Material: 4.0x4.0x313x48"0"0(5x2).
 Material No: 400403134800
 Made in: Canada
 Melted in: Canada

Sales Order: 1514677
 Purchase Order: WLY-24734

Heat No	C	Mn	P	S	Si	Al	Cu	Cb	Mo	Ni	Cr	V	Ti	B	N	Ca
797410	0.190	0.810	0.012	0.010	0.018	0.048	0.048	0.006	0.004	0.015	0.035	0.002	0.002	0.0002	0.0050	0.0002

CE: 0.34
 Within Miles of Location: 1000

Bundle No: M101985797
 Heat: 797410
 MILL: STELCO
 Nanticoke.ON

Yield: 067661 Psi
 Tensile: 073420 Psi
 Eln.2in: 29.5 %
 Recycled Content: 36.90%
 Post Consumer: 19.80%
 Pre-Consumer (Post Industrial): 14.40%

Material Note:
 Sales Or. Note:

Material: 8.0x6.0x500x48"0"0(2x2).
 Material No: 800605004800
 Made in: Canada
 Melted in: Canada

Sales Order: 1521578
 Purchase Order: WLY-24813

Heat No	C	Mn	P	S	Si	Al	Cu	Cb	Mo	Ni	Cr	V	Ti	B	N	Ca
796584	0.200	0.810	0.013	0.007	0.022	0.042	0.058	0.005	0.006	0.023	0.053	0.002	0.002	0.0002	0.0040	0.0002

CE: 0.36
 Within Miles of Location: 1000

Bundle No: M201431614
 Heat: 796584
 MILL: STELCO
 Nanticoke.ON

Yield: 062920 Psi
 Tensile: 074005 Psi
 Eln.2in: 31.0 %
 Recycled Content: 36.90%
 Post Consumer: 19.80%
 Pre-Consumer (Post Industrial): 14.40%

Material Note:
 Sales Or. Note:

Authorized by Quality Assurance: *Jean Richard*
 The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements.
 CE calculated using the AWS D1.1 method.



REF.B/L: 80954217
 Date: 06/01/2020
 Customer: 192



Atlas Tube Canada
 200 Clark St.
 Harrow, Ontario Canada
 NOR 1G0
 Tel: 519-738-3541
 Fax: 519-738-3537

Shipped To
 Insteel Steel Distributors
 11310 West Little York
 HOUSTON TX 77041
 USA

MATERIAL TEST REPORT

Sold To
 Triple S Steel Supply
 PO Box 21119
 HOUSTON TX 77026
 USA

Material: 10.0x4.0x250x48"0"0(2x3).
 Material No: 1000402504800
 Made in: Canada
 Melted in: Canada

Sales Order: 1514677
 Purchase Order: WLY-24734

Heat No	C	Mn	P	S	Si	Al	Cu	Cr	Ni	Mo	Ti	B	N	Ca
797471	0.180	0.750	0.007	0.010	0.012	0.032	0.042	0.004	0.006	0.020	0.034	0.002	0.0002	0.0002

CE: 0.32

Bundle No: M201438465
 Yield Pcs: 6
 Tensile Method: 070681 Psi
 Elongation: 35.0 %
 Recycled Content: 36.90%
 Post Consumer: 19.80%
 Certification: ASTM A500-18 GRADE B&C
 Pre-Consumer (Post Industrial): 14.40%

Heat: 797471
 MILL: STELCO
 Location: Nanticoke, ON

Material Note:
 % Harvested: 100%
 Within Miles of Location: 1000

Material: 10.0x4.0x375x48"0"0(2x2).
 Material No: 1000403754800
 Made in: Canada
 Melted in: Canada

Sales Order: 1514677
 Purchase Order: WLY-24734

Heat No	C	Mn	P	S	Si	Al	Cu	Cr	Ni	Mo	Ti	B	N	Ca
797415	0.200	0.800	0.014	0.007	0.016	0.038	0.035	0.005	0.018	0.042	0.002	0.0002	0.0030	0.0002

CE: 0.35

Bundle No: M201438379
 Yield Pcs: 4
 Tensile Method: 067269 Psi
 Elongation: 35.0 %
 Recycled Content: 36.90%
 Post Consumer: 19.80%
 Certification: ASTM A500-18 GRADE B&C
 Pre-Consumer (Post Industrial): 14.40%

Heat: 797415
 MILL: STELCO
 Location: Nanticoke, ON

Material Note:
 % Harvested: 100%
 Within Miles of Location: 1000

Authorized by Quality Assurance: *Joan Richard*
 The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements.
 CE calculated using the AWS D1.1 method.



REF. B/L: 80954217
 Date: 06/01/2020
 Customer: 192



Atlas Tube Canada
 200 Clark St.
 Harrow Ontario Canada
 N0R 1G0
 Tel: 519-738-3541
 Fax: 519-738-3537

Sold To
 Triple S Steel Supply
 P.O. Box 21119
 HOUSTON TX 77026
 USA

Shipped To
 Insteel Steel Distributors
 11310 West Little York
 HOUSTON TX 77041
 USA

MATERIAL TEST REPORT

Material:	12.0x8.0x625x48"0"0(2x1).	Material No:	1200806254800	Made in:	Canada																
Sales Order:	1521362	Purchase Order:	WLY-24807	Melted in:	Canada																
Heat No	C	Al	0.034	Cu	0.048	Cb	0.005	Mo	0.004	Ni	0.017	Cr	0.037	V	0.002	Ti	0.002	B	N	Ca	
797462	0.190	0.790	0.015	0.048	0.005	0.004	0.017	0.037	0.002	0.002	0.002	0.002	0.002	0.002	0.002	0.002	0.002	0.002	0.002	0.002	
Bundle No	PCS	Yield	Tensile	Eln.2in	Recycled Content	Post Consumer	Pre-Consumer	CE	ASTM A500-18 GRADE B&C	Within Miles of Location											
M201439535	2	058567 Psi	071370 Psi	29.3 %	36.90%	19.80%	14.40%	0.34		100%	1000										
Heat	MILL	Mill Location	Method	Recycled Content	Post Consumer	Pre-Consumer	CE	ASTM A500-18 GRADE B&C	Within Miles of Location												
797462	STELCO	Nanticoke,ON	BOF	36.90%	19.80%	14.40%	0.34		100%	1000											
Material Note:																					
Sales Or. Note:																					

Authorized by Quality Assurance: *Jean Richard*
 The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements.
 CE calculated using the AWS D1.1 method.



Atlas Tube Corp. Chicago
 1855 East 122nd Street
 Chicago Illinois USA
 60633
 Tel: 773-646-4500
 Fax: 773-646-6128



REF B/L: 80940403
 Date: 03/10/2020
 Customer: 192

Sold To
 Triple S Steel Supply
 PO Box 21119
 HOUSTON TX 77026
 USA

Shipped To
 Intsel Steel Distributors
 11310 West Little York
 HOUSTON TX 77041
 USA

MATERIAL TEST REPORT

Material: 8.0x4.0x500x40*0*(3x1)PB

Sales Order: 1498356

Material No: 80040500

Purchase Order: WLY-24524

Made in: USA
 Melted in: USA

Heat No	C	Mn	P	S	Si	Al	Cu	Cb	Mo	Ni	Cr	V	Ti	B	N	Ca
Y05692	0.200	0.770	0.010	0.007	0.014	0.045	0.020	0.004	0.006	0.010	0.040	0.001	0.001	0.0001	0.0050	0.0000
Bundle No	PCs		Yield	Tensile		Elon. 2in		Certification		Pre-Consumer (Post Industrial)		CE: 0.34				
M800931466	3		065915 Psi	075380 Psi		33 %		ASTM A500-18 GRADE B&C		14.40%		100%		Within Miles of Location		
Heat	MILL	USSTEEL		MILL Location		Recycled Content		Post Consumer		Pre-Consumer (Post Industrial)		14.40%				
Y05692	USSTEEL	GARY, IN		GARY, IN		36.90%		19.80%		14.40%		100%				
Material Note:																
Sales Or. Note:																

Material: 4.0x3.0x375x40*0*(4x3).

Sales Order: 1492004

Material No: 400303754000

Purchase Order: WLY-24410

Made in: USA
 Melted in: USA

Heat No	C	Mn	P	S	Si	Al	Cu	Cb	Mo	Ni	Cr	V	Ti	B	N	Ca
D83893	0.210	0.760	0.019	0.010	0.018	0.050	0.030	0.003	0.004	0.010	0.050	0.002	0.001	0.0001	0.0040	0.0000
Bundle No	PCs		Yield	Tensile		Elon. 2in		Certification		Pre-Consumer (Post Industrial)		CE: 0.35				
M800931772	3		061002 Psi	081030 Psi		32 %		ASTM A500-18 GRADE B&C		14.40%		100%		Within Miles of Location		
Heat	MILL	USSTEEL		MILL Location		Recycled Content		Post Consumer		Pre-Consumer (Post Industrial)		14.40%				
D83893	USSTEEL	GARY, IN		GARY, IN		36.90%		19.80%		14.40%		100%				
Material Note:																
Sales Or. Note:																

Authorized by Quality Assurance: *James Richard*

The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements. CE calculated using the AWS D1.1 method.



REF./I.L.: 80940403
 Date: 03/10/2020
 Customer: 192

Atlas Tube
 A DIVISION OF ZEKELMAN INDUSTRIES

Atlas Tube Corp. Chicago
 1855 East 122nd Street
 Chicago Illinois USA
 60633
 Tel: 773-646-4500
 Fax: 773-646-6128

Shipped To
 Insteel Steel Distributors
 1130 West Little York
 HOUSTON TX 77041
 USA

MATERIAL TEST REPORT

Material: 4.0x3.0x375x40'0"(4x3)
Material No: 400303754000
Sales Order: 1492004
Purchase Order: WLY-24410

Heat No	C	Mn	P	S	Si	Al	Cu	Cr	Mo	Ni	Cr	V	Ti	B	N	Ca
D83894	0.190	0.780	0.014	0.007	0.014	0.047	0.030	0.003	0.004	0.010	0.040	0.001	0.001	0.0001	0.0040	0.0000

Bundle No M800931772
Yield 963360 Psi
Tensile 077169 Psi
Eln.2In 31 %
Method BOF
Recycled Content 36.90%
Pre-Consumer (Post Industrial) 14.40%
CE: 0.33

Heat D83894
MILL USSTEEL
Mill Location GARY,IN

Material Note:
Sales Or. Note:

Made in: USA
Melted in: USA

% Harvested 100%
Within Miles of Location 500

Material: 7.0x5.0x500x40'0"(3x1)
Material No: 700505004000
Sales Order: 1485177
Purchase Order: WLY-24291

Heat No	C	Mn	P	S	Si	Al	Cu	Cr	Mo	Ni	Cr	V	Ti	B	N	Ca
Y05253	0.190	0.800	0.013	0.008	0.018	0.044	0.020	0.004	0.003	0.010	0.050	0.001	0.001	0.0000	0.0060	0.0000

Bundle No M800931582
Yield 3
Tensile 079066 Psi
Eln.2In 36 %
Method BOF
Recycled Content 36.90%
Pre-Consumer (Post Industrial) 14.40%
CE: 0.34

Heat Y05253
MILL USSTEEL
Mill Location GARY,IN

Material Note:
Sales Or. Note:

Made in: USA
Melted in: USA

% Harvested 100%
Within Miles of Location 500

Authorized by Quality Assurance: *James Richard*
 The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements.
 CE calculated using the AWS D1.1 method.





Atlas Tube Corp. Chicago
1855 East 122nd Street
Chicago Illinois USA
60633
Tel: 773-646-4500
Fax: 773-646-6128

REF./L: 80940403
Date: 03/10/2020
Customer: 192

Shipped To
Insel Steel Distributors
11310 West Little York
HOUSTON TX 77041
USA

MATERIAL TEST REPORT

Material: 7.0x5.0x500x40*0(3x1). **Material No:** 700505004000
Sales Order: 1485177 **Purchase Order:** WLY-24291
 Heat No C Mn P S Si Al Cu Cr Ni Mo V Ti B N Ca
 Y05253 0.190 0.800 0.013 0.008 0.018 0.044 0.020 0.050 0.010 0.003 0.001 0.000 0.0060 0.0000
Bundle No PCS Yield Tensile Eln.2in Certification
 M800931583 3 066337 Psi 079066 Psi 36 % ASTM A500-18 GRADE B&C
 Heat Y05253 USSTEEL GARY,IN 066337 Psi 079066 Psi 36 % Recycled Content Post-Consumer Pre-Consumer (Post Industrial)
 Method BOF 36.90% 19.80% 14.40%
Material Note: Within Miles of Location
Sales Or. Note: 100% Harvested 500

Material: 8.0x8.0x500x48*0(2x2). **Material No:** 800805004800
Sales Order: 1498356 **Purchase Order:** WLY-24524
 Heat No C Mn P S Si Al Cu Cr Ni Mo V Ti B N Ca
 M87505 0.180 0.780 0.010 0.005 0.010 0.042 0.030 0.030 0.010 0.005 0.001 0.001 0.0060 0.0000
Bundle No PCS Yield Tensile Eln.2in Certification
 M901119365 2 060302 Psi 071291 Psi 34 % ASTM A500-18 GRADE B&C
 Heat M87505 USSTEEL GARY,IN 060302 Psi 071291 Psi 34 % Recycled Content Post-Consumer Pre-Consumer (Post Industrial)
 Method BOF 36.90% 19.80% 14.40%
Material Note: Within Miles of Location
Sales Or. Note: 100% Harvested 500

Authorized by Quality Assurance: *Jean-Philippe*

The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements.
 CE calculated using the AWS D1.1 method.



Atlas Tube Corp. Chicago
 1855 East 122nd Street
 Chicago Illinois USA
 60633
 Tel: 773-646-4500
 Fax: 773-646-6128



REF. B/L: 80940403
 Date: 03/10/2020
 Customer: 192

Sold To
 Triple S Steel Supply
 PO Box 21119
 HOUSTON TX 77026
 USA

Shipped To
 Inset Steel Distributors
 1310 West Little York
 HOUSTON TX 77041
 USA

MATERIAL TEST REPORT

Material: 8.0x8.0x500x48"0"(2x2).

Sales Order: 1498356

Heat No: Y05507
 C 0.200 Mn 0.790 P 0.008 S 0.008 Si 0.004 Al 0.050 Cu 0.020 Cb 0.004 Mo 0.005 Ni 0.010 Cr 0.040 V 0.002 Ti 0.001 B 0.0001 N 0.0040 Ca 0.0000
 Bundle No: M901119365
 PCS 2
 Yield 059317 Psi
 Tensile 071270 Psi
 Eln.Zin 38 %
 Heat: Y05507
 MILL USSTEEL
 GARY,IN
 Recycled Content 36.90%
 Method BOF
 Post Consumer 19.80%
 Pre-Consumer (Post Industrial) 14.40%
 Certification: ASTM A500-18 GRADE B&C
 CE: 0.34
 Material Note:
 Sales Or. Note:

Material No: 800805004800

Purchase Order: WLY-24524

Made in: USA
 Melted in: USA
 % Harvested 100%
 Within Miles of Location 500

Material: 8.0x8.0x500x48"0"(2x2).

Sales Order: 1498356

Heat No: D83797
 C 0.190 Mn 0.780 P 0.007 S 0.006 Si 0.012 Al 0.049 Cu 0.030 Cb 0.004 Mo 0.005 Ni 0.010 Cr 0.030 V 0.001 Ti 0.001 B 0.0001 N 0.0060 Ca 0.0000
 Bundle No: M901114557
 PCS 2
 Yield 056430 Psi
 Tensile 078625 Psi
 Eln.Zin 34 %
 Heat: D83797
 MILL USSTEEL
 GARY,IN
 Recycled Content 36.90%
 Method BOF
 Post Consumer 19.80%
 Pre-Consumer (Post Industrial) 14.40%
 Certification: ASTM A500-18 GRADE B&C
 CE: 0.33
 Material Note:
 Sales Or. Note:

Material No: 800805004800

Purchase Order: WLY-24524

Made in: USA
 Melted in: USA
 % Harvested 100%
 Within Miles of Location 500

Authorized by Quality Assurance: *Jean Richard*

The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements. CE calculated using the AWS D1.1 method.



Atlas Tube

A DIVISION OF ZEKELMAN INDUSTRIES

Atlas Tube Corp. Chicago
1855 East 122nd Street
Chicago Illinois USA
60633
Tel: 773-646-4500
Fax: 773-646-6128

Sold To
Triple S Steel Supply
PO Box 21119
HOUSTON TX 77026
USA

REF.B/L: 80940403
Date: 03/10/2020
Customer: 192

Shipped To
Insel Steel Distributors
1310 West Little York
HOUSTON TX 77041
USA

MATERIAL TEST REPORT

Material: 8.0x8.0x500x48"0(2x2).

Sales Order: 1498356

Heat No T01125
C 0.180
Mn 0.770
P 0.006
S 0.008
Si 0.012
Al 0.056
Cu 0.030
Cb 0.004
Mo 0.005
Ni 0.010
Cr 0.040
V 0.001
Ti 0.001
B 0.0001
N 0.0050
Ca 0.0000
Yield 065336 Psi
Tensile 077781 Psi
Eln.Zin 36 %
PCs 2
Method BOF
Recycled Content 36.90%
Post Consumer 19.80%
Pre-Consumer 14.40%
MILL USSTEEL
GARY,IN

Material Note:
Sales Or. Note:

Material No: 800805004800

Purchase Order: WLY-24524

ASTM A500-18 GRADE B&C
Certification
Pre-Consumer (Post Industrial)
14.40%
CE: 0.32
% Harvested 100%
Within Miles of Location 500

Made in: USA
Melted in: USA

Material: 12.0x12.0x250x40"0(2x2).

Sales Order: 1494355

Heat No C93111
C 0.200
Mn 0.830
P 0.013
S 0.004
Si 0.030
Al 0.030
Cu 0.170
Cb 0.003
Mo 0.020
Ni 0.050
Cr 0.070
V 0.003
Ti 0.002
B 0.0003
N 0.0060
Ca 0.0017
Yield 057441 Psi
Tensile 075486 Psi
Eln.Zin 28 %
PCs 4
Method EAF
Recycled Content 60.60%
Post Consumer 21.70%
Pre-Consumer 39.00%
MILL GALLATIN
Ghent,KY

Material Note:
Sales Or. Note:

Material No: 1201202504000

Purchase Order: WLY-24454

ASTM A500-18 GRADE B&C
Certification
Pre-Consumer (Post Industrial)
39.00%
CE: 0.38
% Harvested 100%
Within Miles of Location 500

Made in: USA
Melted in: USA

Authorized by Quality Assurance: *Joan Richard*

The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements.
CE calculated using the AWS D1.1 method.



Atlas Tube Corp. Chicago
 1855 East 122nd Street
 Chicago Illinois USA
 60633
 Tel: 773-646-4500
 Fax: 773-646-6128



REF./I/L: 80934498
 Date: 02/10/2020
 Customer: 192

Sold To
 Triple S Steel Supply
 PO Box 21119
 HOUSTON TX 77028
 USA

Shipped To
 Intsel Steel Distributors
 11310 West Little York
 HOUSTON TX 77041
 USA

MATERIAL TEST REPORT

Material: 5.0x2.0x250x48"0(4x3).

Sales Order: 1472390

Heat No M87395 C 0.200 Mn 0.800 P 0.009 S 0.007 Si 0.012 Al 0.045 Cu 0.020 Cb 0.004 Mo 0.008 Ni 0.010 Cr 0.030 V 0.001 Ti 0.001 B 0.001 N 0.0050 Ca 0.0000
 Bundle No M800923834 PCs Yield 12
 Heat M800923834 12 057589 Psi
 Heat M87395 MILL USSTEEL MILL Location GARY,IN
 Material Note:
 Sales Or. Note:

Material No: 50020250

Purchase Order: WLY-24050

Method BOF
 Tensile 076143 Psi
 Eln.Zin 28 %
 Recycled Content 36.90%
 Post_Consumer 19.80%
 Pre_Consumer 14.40%
 Certification ASTM A500-18 GRADE B&C
 CE: 0.35
 % Harvested 100%
 Within Miles of Location 500

Made in: USA
 Melted in: USA

Material: 5.0x3.0x375x40"0(1x8)PB

Sales Order: 1485177

Heat No E84426 C 0.200 Mn 0.780 P 0.010 S 0.007 Si 0.008 Al 0.039 Cu 0.030 Cb 0.005 Mo 0.008 Ni 0.010 Cr 0.030 V 0.001 Ti 0.001 B 0.0001 N 0.0060 Ca 0.0000
 Bundle No M800913733 PCs Yield 2
 Heat M800913733 2 069108 Psi
 Heat E84426 MILL USSTEEL MILL Location GARY,IN
 Material Note:
 Sales Or. Note:

Material No: 50030375

Purchase Order: WLY-24291

Method BOF
 Tensile 081026 Psi
 Eln.Zin 29 %
 Recycled Content 36.90%
 Post_Consumer 19.80%
 Pre_Consumer 14.40%
 Certification ASTM A500-18 GRADE B&C
 CE: 0.34
 % Harvested 100%
 Within Miles of Location 500

Made in: USA
 Melted in: USA

Authorized by Quality Assurance: *John Richard*

The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements. CE calculated using the AWS D1.1 method.



Atlas Tube Corp. Chicago
1855 East 122nd Street
Chicago Illinois USA
60633
Tel: 773-646-4600
Fax: 773-646-6128



REF/B/L: 80934498
Date: 02/10/2020
Customer: 192

Sold To
Triple S Steel Supply
PO Box 21119
HOUSTON TX 77026
USA

Shipped To
Intsel Steel Distributors
11310 West Little York
HOUSTON TX 77041
USA

MATERIAL TEST REPORT

Material: 5.0x3.0x375x40"0(1x8)PB

Material No: 50030375

Sales Order: 1485177

Purchase Order: WLY-24291

Heat No	C	Mn	P	S	Si	Al	Cu	Cb	Mo	Ni	Cr	V	Ti	B	N	Ca
M87383	0.180	0.750	0.010	0.006	0.008	0.048	0.020	0.006	0.003	0.010	0.030	0.001	0.001	0.0001	0.0040	0.0000
Bundle No	Yield															
M800913733	068851 Psi															
Heat	Tensile															
M87383	080685 Psi															
MATERIAL Note:	Method BOF															
Sales Or. Note:	Recycled Content 36.90%															
	Eln.Zin 29 %															
	Pre-Consumer (Post Industrial) 19.80%															
	Post-Consumer 14.40%															
	ASTM A500-18 GRADE B&C															
	CE: 0.32															
	% Harvested 100%															
	Within Miles of Location 500															

Material: 12.0x6.0x313x48"0(2x2)

Material No: 1200603134800

Sales Order: 1472390

Purchase Order: WLY-24050

Heat No	C	Mn	P	S	Si	Al	Cu	Cb	Mo	Ni	Cr	V	Ti	B	N	Ca
W86982	0.200	0.770	0.008	0.008	0.013	0.052	0.010	0.005	0.005	0.010	0.030	0.001	0.001	0.0001	0.0040	0.0000
Bundle No	Yield															
M901114292	060722 Psi															
Heat	Tensile															
W86982	077505 Psi															
MATERIAL Note:	Method BOF															
Sales Or. Note:	Recycled Content 36.90%															
	Eln.Zin 29 %															
	Pre-Consumer (Post Industrial) 19.80%															
	Post-Consumer 14.40%															
	ASTM A500-18 GRADE B&C															
	CE: 0.34															
	% Harvested 100%															
	Within Miles of Location 500															

Authorized by Quality Assurance: *Juan Beland*
The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements.
CE calculated using the AWS D1.1 method.



Atlas Tube Corp. Chicago
 1655 East 122nd Street
 Chicago Illinois USA
 60633
 Tel: 773-646-4500
 Fax: 773-646-6128



REF./I/L: 80934498
 Date: 02/10/2020
 Customer: 192

Sold To
 Triple S Steel Supply
 PO Box 21119
 HOUSTON TX 77026
 USA

Shipped To
 Insteel Steel Distributors
 11310 West Little York
 HOUSTON TX 77041
 USA

MATERIAL TEST REPORT

Material: 12.0x6.0x375x40'0"(2x2). **Material No:** 1200603754000 **Made in:** USA
Sales Order: 1485177 **Purchase Order:** WLY-24291 **Melted in:** USA

Heat No	C	Mn	P	S	Si	Al	Cu	Cr	Ni	Mo	Ti	B	N	Ca
D00023	0.200	0.800	0.013	0.011	0.020	0.042	0.050	0.080	0.020	0.008	0.001	0.001	0.0000	0.0010
Bundle No														
M90114268														
PCs														
4														
Yield														
059674 Psi														
Tensile														
072705 Psi														
Eln.2in														
32 %														
Recycled Content														
36.90%														
Method														
BOF														
Post-Consumer														
19.80%														
Pre-Consumer														
14.40%														
ASTM A500-18 GRADE B&C														
Certification														
CE: 0.36														

Material: 14.0x4.0x500x40'0"(1x4). **Material No:** 1400405004000 **Made in:** USA
Sales Order: 1485177 **Purchase Order:** WLY-24291 **Melted in:** USA

Heat No	C	Mn	P	S	Si	Al	Cu	Cr	Ni	Mo	Ti	B	N	Ca
T01126	0.190	0.770	0.009	0.008	0.022	0.050	0.030	0.040	0.010	0.006	0.001	0.001	0.0040	0.0000
Bundle No														
M90114122														
PCs														
4														
Yield														
061481 Psi														
Tensile														
074159 Psi														
Eln.2in														
33 %														
Recycled Content														
36.90%														
Method														
BOF														
Post-Consumer														
19.80%														
Pre-Consumer														
14.40%														
ASTM A500-18 GRADE B&C														
Certification														
CE: 0.33														
% Harvested														
100%														
Within Miles of Location														
500														

Authorized by Quality Assurance: *Jean Richard*

The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements. CE calculated using the AWS D1.1 method.



Atlas Tube Corp. Chicago
1855 East 122nd Street
Chicago Illinois USA
60633
Tel: 773-646-4500
Fax: 773-646-6128



REF B/L: 80834498
Date: 02/10/2020
Customer: 192

Sold To
Triple S Steel Supply
PO Box 21119
HOUSTON TX 77026
USA

Shipped To
Intsel Steel Distributors
11310 West Little York
HOUSTON TX 77041
USA

MATERIAL TEST REPORT

Material: 14.0x6.0x375x48'0"(1x3).

Sales Order: 1487345

Heat No	C	Mn	P	S	Si	Al	Cu	Cb	Mo	Ni	Cr	V	Ti	B	N	Ca	
D83794	0.200	0.760	0.011	0.010	0.009	0.047	0.020	0.003	0.008	0.010	0.040	0.001	0.001	0.0001	0.0060	0.0000	
Bundle No	Yield		Tensile		Eln.2in		Recycled Content		Post. Consumer		Pre-Consumer (Post Industrial)		CE: 0.34		Within Miles of Location		
M901113006	062368 Psi		076088 Psi		33 %		36.90%		19.80%		14.40%		100%		500		
Heat	MILL	Yield		Tensile		Eln.2in		Recycled Content		Post. Consumer		Pre-Consumer (Post Industrial)		CE: 0.34		Within Miles of Location	
D83794	USSTEEL	062368 Psi		076088 Psi		33 %		36.90%		19.80%		14.40%		100%		500	
Material Note:	GARY,IN																
Sales Or. Note:																	

Material No: 1400603754800

Purchase Order: WLY-24338

Heat No	C	Mn	P	S	Si	Al	Cu	Cb	Mo	Ni	Cr	V	Ti	B	N	Ca	
D83392	0.160	0.460	0.015	0.013	0.008	0.051	0.030	0.004	0.007	0.020	0.060	0.002	0.001	0.0001	0.0070	0.0000	
Bundle No	Yield		Tensile		Eln.2in		Recycled Content		Post. Consumer		Pre-Consumer (Post Industrial)		CE: 0.26		Within Miles of Location		
M901107193	051671 Psi		074921 Psi		30 %		36.90%		19.80%		14.40%		100%		500		
Heat	MILL	Yield		Tensile		Eln.2in		Recycled Content		Post. Consumer		Pre-Consumer (Post Industrial)		CE: 0.26		Within Miles of Location	
D83392	USSTEEL	051671 Psi		074921 Psi		30 %		36.90%		19.80%		14.40%		100%		500	
Material Note:	GARY,IN																
Sales Or. Note:																	

Material: 16.0x8.0x313x40'0"(1x3).

Sales Order: 1487345

Heat No	C	Mn	P	S	Si	Al	Cu	Cb	Mo	Ni	Cr	V	Ti	B	N	Ca	
D83392	0.160	0.460	0.015	0.013	0.008	0.051	0.030	0.004	0.007	0.020	0.060	0.002	0.001	0.0001	0.0070	0.0000	
Bundle No	Yield		Tensile		Eln.2in		Recycled Content		Post. Consumer		Pre-Consumer (Post Industrial)		CE: 0.26		Within Miles of Location		
M901107193	051671 Psi		074921 Psi		30 %		36.90%		19.80%		14.40%		100%		500		
Heat	MILL	Yield		Tensile		Eln.2in		Recycled Content		Post. Consumer		Pre-Consumer (Post Industrial)		CE: 0.26		Within Miles of Location	
D83392	USSTEEL	051671 Psi		074921 Psi		30 %		36.90%		19.80%		14.40%		100%		500	
Material Note:	GARY,IN																
Sales Or. Note:																	

Material No: 1600803134000

Purchase Order: WLY-24338

Heat No	C	Mn	P	S	Si	Al	Cu	Cb	Mo	Ni	Cr	V	Ti	B	N	Ca	
D83392	0.160	0.460	0.015	0.013	0.008	0.051	0.030	0.004	0.007	0.020	0.060	0.002	0.001	0.0001	0.0070	0.0000	
Bundle No	Yield		Tensile		Eln.2in		Recycled Content		Post. Consumer		Pre-Consumer (Post Industrial)		CE: 0.26		Within Miles of Location		
M901107193	051671 Psi		074921 Psi		30 %		36.90%		19.80%		14.40%		100%		500		
Heat	MILL	Yield		Tensile		Eln.2in		Recycled Content		Post. Consumer		Pre-Consumer (Post Industrial)		CE: 0.26		Within Miles of Location	
D83392	USSTEEL	051671 Psi		074921 Psi		30 %		36.90%		19.80%		14.40%		100%		500	
Material Note:	GARY,IN																
Sales Or. Note:																	

Authorized by Quality Assurance: *Joan Riedel*

The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements. CE calculated using the AWS D1.1 method.





US-ML-CARTERSVILLE
384 OLD GRASSDALE ROAD NE
CARTERSVILLE, GA 30121
USA

CERTIFIED MATERIAL TEST REPORT

CUSTOMER SHIP TO INTSEL STEEL DISTRIBUTORS LP 11310 W LITTLE YORK RD HOUSTON, TX 77041-4917 USA	CUSTOMER BILL TO INTSEL STEEL DISTRIBUTORS LP HOUSTON, TX 77226-1119 USA	GRADE GGMULTI	SHAPE / SIZE Angle / 6X4X1/2	DOCUMENT ID: 000245874
SALES ORDER 78332030000010	BILL OF LADING 1323-0000135212	LENGTH 40'00"	WEIGHT 19,440 LB	HEAT / BATCH 55061469/02
CUSTOMER PURCHASE ORDER NUMBER WLY-23175	DATE 06/03/2019	SPECIFICATION / DATE OF REVISION ASTM A529-14, A572-15 ASTM A6-17, A536-14, ASME SA-36 ASTM A709-17, AASHTO M270-15 CSA G40.20-13/G40.21-13		

CHEMICAL COMPOSITION	C	0.15	Mn	1.00	P	0.015	S	0.021	Si	0.20	Cr	0.32	Ni	0.11	Cu	0.11	Mo	0.025	V	0.001	Nb	0.009	N	0.0100	Pb	0.0040
----------------------	---	------	----	------	---	-------	---	-------	----	------	----	------	----	------	----	------	----	-------	---	-------	----	-------	---	--------	----	--------

CHEMICAL COMPOSITION	Sp	0.011
----------------------	----	-------

MECHANICAL PROPERTIES	Elong.	26.20	UTS	MPa	536	YS 0.2%	MPa	366
		25.40	MPa	538			MPa	370

COMMENTS / NOTES

This grade meets the requirements for the following grades:
ASTM Grades: A36; A529-50; A572-50; A709-36; A709-50
CSA Grades: 44W; 50W
AASHTO Grades: M270-36; M270-50
ASME Grades: SA36

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

Shackley
BHASKAR YALAMANCHILI
QUALITY DIRECTOR

YAN WANG
QUALITY ASSURANCE MGR.

Phone: (409) 287-1071 Email: Bhaskar.Yalamanchili@gerdau.com
Phone: (770) 387 5718 Email: yan.wang@gerdau.com



6226 W. 74TH STREET
CHICAGO, IL 60638
Tel: 708-496-0380
Fax: 708-563-1950

https://www.nucortubular.com
https://www.ntportal.com
Certificate Number: MAR 341996

SSW 7/22/2020 MTRs AG 1961

Sold By:
NUCOR TUBULAR PRODUCTS INC.
MARSEILLES DIVISION
1201 E. BROADWAY
MARSEILLES, IL 61341
Tel: 815 795-4400
Fax: 815 795-4449

Purchase Order No: SSW112611
Sales Order No: MAR 394124 - 1
Bill of Lading No: MAR 232863 - 4
Invoice No:

Shipped: 5/29/2020
Invoiced:

Sold To:
2734 - SERVICE STEEL WAREHOUSE CO., L.P.
PO BOX 9607
HOUSTON, TX 77213

Ship To:
1 - SERVICE STEEL WAREHOUSE CO.
8415 CLINTON DRIVE
HOUSTON, TX 77029

CERTIFICATE OF ANALYSIS and TESTS

Customer Part No:

Certificate No: MAR 341996

Test Date: 5/27/2020

TUBING A500 GRADE B(C)

Total Pieces 12 Total Weight Lbs 18,766

10" X 4" X 3/8" X 48'

* DOMESTIC STEEL M&M *

Bundle Tag	Mill	Heat	Specs	Y/T Ratio	Pieces	Weight Lbs
400062	13N	A96500	YLD=52500/TEN=67580/ELG=34.8	0.7769	6	9,383
400063	13N	A96500	YLD=52500/TEN=67580/ELG=34.8	0.7769	6	9,383

Mill #: 13N Heat #: A96500 Carbon Eq: 0.1534 Heat Src Origin: MELTED AND MANUFACTURED IN THE USA

C	Mn	P	S	Si	Al	Cu	Cr	Mo	V	Ni	Nb	Sn
0.0600	0.4100	0.0080	0.0030	0.0200	0.0440	0.1100	0.0500	0.0200	0.0020	0.0500	0.0120	0.0040
N	B	Ti	Ca									
0.0061	0.0001	0.0010	0.0019									

LEED Information (based on the most recent LEED information from the producing mill)

Method	Location	Recycled Content	Post Consumer	Post Industrial
EAF	Ghent, KY	66.9%	28.2%	38.8%

Certification:

I certify that the above results are a true and correct copy of records prepared and maintained by NUCOR TUBULAR PRODUCTS INC. Sworn this day, 5/27/2020.

THE SPECIFICATIONS LISTED BELOW REPRESENT THE CURRENT ISSUED DATES OF THESE STANDARDS. THIS DOES NOT INDICATE THAT THE MATERIAL ABOVE CONFORMS TO EACH OR ALL OF THE STANDARDS. WE CERTIFY THE MATERIAL ABOVE TO THE SPECIFICATION LISTED IN THE LINE DESCRIPTION.

- CURRENT STANDARDS:**
A252-19
A500/A500M-18
A513/A513M-19
ASTM A53/A53M-18 | ASME SA-53/SA-53M-18
A847/A847M-14
A1085/A1085M-15
IN COMPLIANCE WITH EN 10204 SECTION 4.1
INSPECTION CERTIFICATE TYPE 3.1

Chris Allen

Chris Allen, ASQ CMQ/OE
Quality Systems Supervisor



CMC STEEL TEXAS
1 STEEL MILL DRIVE
SEGUIN TX 78155-7510

CERTIFIED MILL TEST REPORT
For additional copies call
830-372-8771

We hereby certify that the test results presented here
are accurate and conform to the reported grade specification

Raula
Rolando A. Davila
Quality Assurance Manager

S O L D T O		S H I P T O		S O L D T O	
HEAT NO.: 3099966		CMC Construction Svcs College Stati		CMC Construction Svcs College Stati	
SECTION: REBAR 10MM (#3) 20'0" 300/40		10650 State Hwy 30		10650 State Hwy 30	
GRADE: ASTM A615-20 Grade 300/40		College Station TX		College Station TX	
ROLL DATE: 09/25/2020		US 77845-7950		US 77845-7950	
MELT DATE: 09/13/2020		979 774 5900		979 774 5900	
Cert. No.: 83224860 / 099966A357				DLVRY LBS / HEAT: 2106.000 LB	
				DLVRY PCS / HEAT: 280 EA	
				Delivery#: 83224860	
				BOL#: 73793087	
				CUST PO#: 862925	
				CUST P/N:	

Characteristic	Value	Characteristic	Value
C	0.10%		
Mn	0.74%		
P	0.012%		
S	0.048%		
Si	0.19%		
Cu	0.31%		
Cr	0.10%		
Ni	0.12%		
Mo	0.059%		
V	0.000%		
Cb	0.000%		
Sn	0.013%		
Al	0.000%		
Yield Strength test 1	47.8ksi		
Tensile Strength test 1	66.1ksi		
Elongation test 1	26%		
Elongation Gage Lgth test 1	8IN		
Bend Test 1	Passed		
Bend Test Diameter	1.313IN		

The Following is true of the material represented by this MTR:

- *Material is fully killed
- *100% melted and rolled in the USA
- *EN10204:2004 3.1 compliant
- *Contains no weld repair
- *Contains no Mercury contamination
- *Manufactured in accordance with the latest version of the plant quality manual
- *Meets the "Buy America" requirements of 23 CFR635.410, 49 CFR 661
- *Warning: This product can expose you to chemicals which are known to the State of California to cause cancer, birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov

REMARKS :



CMC STEEL TEXAS
1 STEEL MILL DRIVE
SEGUIN TX 78155-7510

CERTIFIED MILL TEST REPORT
For additional copies call
830-372-8771

We hereby certify that the test results presented here
are accurate and conform to the reported grade specification

R. Baraka
Rolando A. Davila
Quality Assurance Manager

S O L D T O		S H I P T O		S O L D T O	
HEAT NO.: 3099959		CMC Construction Svcs College Stati		CMC Construction Svcs College Stati	
SECTION: REBAR 13MM (#4) 20"0" 300/40		10650 State Hwy 30		10650 State Hwy 30	
GRADE: ASTM A615-20 Grade 300/40		College Station TX		College Station TX	
ROLL DATE: 09/17/2020		US 77845-7950		US 77845-7950	
MELT DATE: 09/13/2020		979 774 5900		979 774 5900	
Cert. No.: 83224860 / 099959A293					
Delivery#: 83224860		BOL#: 73793087		CUST PO#: 862925	
CUST P/N:		DLVRY LBS / HEAT: 2191.000 LB		DLVRY PCS / HEAT: 164 EA	
Characteristic	Value	Characteristic	Value	Characteristic	Value
C	0.11%				
Mn	0.81%				
P	0.013%				
S	0.048%				
Si	0.17%				
Cu	0.30%				
Cr	0.14%				
Ni	0.13%				
Mo	0.058%				
V	0.000%				
Cb	0.001%				
Sn	0.012%				
Al	0.000%				
Yield Strength test 1	47.0ksi				
Tensile Strength test 1	64.4ksi				
Elongation test 1	26%				
Elongation Gage Lgth test 1	8IN				
Bend Test 1	Passed				
Bend Test Diameter	1.750IN				
<p>The Following is true of the material represented by this MTR:</p> <ul style="list-style-type: none"> *Material is fully killed *100% melted and rolled in the USA *EW10204:2004 3.1 compliant *Contains no weld repair *Contains no Mercury contamination *Manufactured in accordance with the latest version of the plant quality manual *Meets the "Buy America" requirements of 23 CFR635.410, 49 CFR 661 *Warning: This product can expose you to chemicals which are known to the State of California to cause cancer, birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov 					

REMARKS :



CMC STEEL TEXAS
1 STEEL MILL DRIVE
SEGUIN TX 78155-7510

CERTIFIED MILL TEST REPORT
For additional copies call
830-372-8771

We hereby certify that the test results presented here
are accurate and conform to the reported grade specification

R. Paula
Rolanda A. Devila
Quality Assurance Manager

S O L D T O		S H I P T O		S H I P T O	
CMC Construction Svcs College Stati		CMC Construction Svcs College Stati		CMC Construction Svcs College Stati	
10650 State Hwy 30 College Station TX US 77845-7950 979 774 5900		10650 State Hwy 30 College Station TX US 77845-7950 979 774 5900		10650 State Hwy 30 College Station TX US 77845-7950 979 774 5900	
Characteristic	Value	Characteristic	Value	Characteristic	Value
HEAT NO.:	3099508	Delivery#:	83224860		
SECTION:	REBAR 16MM (#5) 20"0" 300/40	BOL#:	73793087		
GRADE:	ASTM A615-20 Grade 300/40	CUST PO#:	862925		
ROLL DATE:	08/28/2020	CUST P/N:			
MELT DATE:	08/25/2020	DLVRY LBS / HEAT:	4380.000 LB		
Cert. No.:	83224860 / 099508A138	DLVRY PCS / HEAT:	210 EA		
C	0.20%				
Mn	0.75%				
P	0.010%				
S	0.049%				
Si	0.18%				
Cu	0.33%				
Cr	0.11%				
Ni	0.11%				
Mo	0.043%				
V	0.000%				
Cb	0.001%				
Sn	0.014%				
Al	0.001%				
Yield Strength test 1	48.6ksi				
Tensile Strength test 1	71.6ksi				
Elongation test 1	24%				
Elongation Gage Lgth test 1	8IN				
Bend Test 1	Passed				
Bend Test Diameter	2.188IN				
<p>The Following is true of the material represented by this MTR:</p> <ul style="list-style-type: none"> *Material is fully killed *100% melted and rolled in the USA *EN10204:2004 3.1 compliant *Contains no weld repair *Contains no Mercury contamination *Manufactured in accordance with the latest version of the plant quality manual *Meets the "Buy America" requirements of 23 CFR635.410, 49 CFR 661 *Warning: This product can expose you to chemicals which are known to the State of California to cause cancer, birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov 					

REMARKS :

TUCKER CONCRETE

8930 LACY WELL RD CS
979-777-8749 VM1802

Job # TUCKER
LA DOT TTI

TICKET # 1027

START DATE: 10/30/2020 TIME: 08:56:02
STOP DATE: 10/30/2020 TIME: 09:17:14

MIX DESIGN B1350

RAW CEMENT COUNTS ----- 5949
RAW CONVEYOR COUNTS ----- 4419

TOTAL YARDS 10.05

MATERIAL	RATE	SETTING	TOTAL
CATYPE	487.4	LBPM	4725.8LBS
LRMSAND	5.5	GATE	13949.7LBS
RGBLEND	7.8	GATE	19266.2LBS
WATER	21.1	GPM	262.7GAL
SIKA686	1.2	GPM	12.1GAL
NC4	0.8	GPM	8.0OZ

NAME -----
NOTES:

TUCKER_concrete

9797776749

1904
TUCKER_CONST
LA_DOT_TTI

TICKET # 1357

START DATE: 2020-10-30 TIME: 10:20:38
STOP DATE: 2020-10-30 TIME: 10:34:59

MIX DESIGN: B1350

RAW CEMENT COUNTS: 3736
RAW CONVEYOR COUNTS: 127042
CONVEYOR SPEED: 45
TOTAL YARDS 6.75

MATERIAL	RATE SETTING	TOTAL
CEMENT	8.45924LBS/	3081.079
SAND	5.781536 GA	9100.307
ADJUSTED:		12568.65
STONE	7.619714 GA	
ADJUSTED:		168.0812
WATER	27.59709GAL	0.00Z
ADMIX #1	0.00Z/MIN	0.00Z
ADMIX #2	167.3850Z/M	0.00Z
ADMIX #3	0.00Z/MIN	0.00Z

ASTM DATA AVAILABLE UPON REQ

Name _____
NOTES:

LADOTD

CONCRETE COMPRESSIVE STRENGTH TEST REPORT

Report Number: A1171057.0151
 Service Date: 10/30/20
 Report Date: 10/30/20
 Task: 606861-3 (LADOT)

Terracon
 6198 Imperial Loop
 College Station, TX 77845-5765
 979-846-3767 Reg No: F-3272

Client

Texas Transportation Institute
 Attn: Gary Gerke
 TTI Business Office
 3135 TAMU
 College Station, TX 77843-3135

Project

Riverside Campus
 Riverside Campus
 Bryan, TX

Project Number: A1171057

Material Information

Specified Strength: 3,000 psi @ 28 days

Mix ID: B1350
 Supplier: Tucker
 Batch Time: 1000
 Truck No.: Plant: Ticket No.: 1027

Field Test Data

Test	Result	Specification
Slump (in):	7 1/2	Max 8
Air Content (%):	1.8	
Concrete Temp. (F):	68	40 - 95
Ambient Temp. (F):	55	40 - 95
Plastic Unit Wt. (pcf):	146.2	Not Specified
Yield (Cu. Yds.):		

Sample Information

Sample Date: 10/30/20 Sample Time: 1008
 Sampled By: Cullen Turney
 Weather Conditions: Clear, no wind
 Accumulative Yards: 10/20 Batch Size (cy): 10
 Placement Method: Direct Discharge
 Water Added Before (gal): 0
 Water Added After (gal): 0
 Sample Location: South east end
 Placement Location: 606861-3(LADOT)

Laboratory Test Data

Set No.	Specimen ID	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Maximum Load (lbs)	Compressive Strength (psi)	Fracture Type	Tested By
1	A	6.00	28.27		12/10/20	41 F	132,160	4,670	1	SLS
1	B	6.00	28.27		12/10/20	41 F	128,080	4,530	2	SLS
1	C	6.00	28.27		12/10/20	41 F	124,660	4,410	1	SLS
1	D					Hold				

Initial Cure: Outside

Final Cure: Field Cured

Comments: F = Field Cured

Samples Made By: Terracon

Services: Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

Terracon Rep.: Cullen Turney

Start/Stop: 0815-1400

Reported To:

Contractor:

Report Distribution:

(1) Texas Transportation Institute, Gary Gerke (1) Terracon Consultants, Inc., Alex Dunigan, P.E.
 (1) Texas Transportation Institute, Bill Griffith

Test Methods: ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

CONCRETE COMPRESSIVE STRENGTH TEST REPORT

Report Number: A1171057.0151
 Service Date: 10/30/20
 Report Date: 10/30/20
 Task: 606861-3 (LADOT)



6198 Imperial Loop
 College Station, TX 77845-5765
 979-846-3767 Reg No: F-3272

Client

Texas Transportation Institute
 Attn: Gary Gerke
 TTI Business Office
 3135 TAMU
 College Station, TX 77843-3135

Project

Riverside Campus
 Riverside Campus
 Bryan, TX

Project Number: A1171057

Material Information

Specified Strength: 3,000 psi @ 28 days

Mix ID: B1350
 Supplier: Tucker
 Batch Time: 1030
 Truck No.: Plant: Ticket No.: 1357

Field Test Data

Test	Result	Specification
Slump (in):	7 1/4	Max 8
Air Content (%):	1.9	
Concrete Temp. (F):	68	40 - 95
Ambient Temp. (F):	57	40 - 95
Plastic Unit Wt. (pcf):	146.4	Not Specified
Yield (Cu. Yds.):		

Sample Information

Sample Date: 10/30/20 Sample Time: 1035
 Sampled By: Cullen Turney
 Weather Conditions: Clear, no wind
 Accumulative Yards: 20/20 Batch Size (cy): 10
 Placement Method: Direct Discharge
 Water Added Before (gal): 0
 Water Added After (gal): 0
 Sample Location: North west end
 Placement Location: 606861-3(LADOT)

Laboratory Test Data

Set No.	Specimen ID	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Maximum Load (lbs)	Compressive Strength (psi)	Fracture Type	Tested By
2	A	6.00	28.27		12/10/20	41 F	124,320	4,400	1	SLS
2	B	6.00	28.27		12/10/20	41 F	121,970	4,310	1	SLS
2	C	6.00	28.27		12/10/20	41 F	123,700	4,370	1	SLS
2	D					Hold				

Initial Cure: Outside

Final Cure: See Comments

Comments: F = Field Cured

Samples Made By: Terracon

Services: Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

Terracon Rep.: Cullen Turney

Start/Stop: 0815-1400

Reported To:

Contractor:

Report Distribution:

(1) Texas Transportation Institute, Gary Gerke (1) Terracon Consultants, Inc., Alex Dunigan, P.E.
 (1) Texas Transportation Institute, Bill Griffith

Reviewed By:

Alexander Dunigan
 Project Manager

Test Methods: ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

TUCKER_concrete

979-777-6749
TRUCK #4
TUCKER CONSTRUCTION
TTI_LA_DOT

TICKET # 292

START DATE: 2020-11-05 TIME: 08:59:55
STOP DATE: 2020-11-05 TIME: 09:25:51

MIX DESIGN: B1350

RAW CEMENT COUNTS: 4751
RAW CONVEYOR COUNTS: 161573
CONVEYOR SPEED: 50
TOTAL YARDS 8.286

MATERIAL	RATE SETTING	TOTAL
CEMENT	9.343309LBS	3894.87L
SAND	6.013903 GA	11505.07
ADJUSTED:		
STONE	7.916514 GA	15889.93
ADJUSTED:		
WATER	27.58288GAL	193.7082
ADMIX #1	0.00Z/MIN	0.00Z
ADMIX #2	0.00Z/MIN	0.00Z
ADMIX #3	0.00Z/MIN	0.00Z
TOTAL SAND MOISTURE:	0.0	
TOTAL STONE MOISTURE:	0.0	

Name _____
NOTES:

CONCRETE COMPRESSIVE STRENGTH TEST REPORT

Report Number: A1171057.0154
 Service Date: 11/05/20
 Report Date: 11/06/20
 Task: 606861-3 (LADOT)



6198 Imperial Loop
 College Station, TX 77845-5765
 979-846-3767 Reg No: F-3272

Client

Texas Transportation Institute
 Attn: Gary Gerke
 TTI Business Office
 3135 TAMU
 College Station, TX 77843-3135

Project

Riverside Campus
 Riverside Campus
 Bryan, TX

Project Number: A1171057

Material Information

Specified Strength: 3,000 psi @ 28 days

Mix ID: B1350
 Supplier: Tucker Concrete
 Batch Time: 0800 Plant:
 Truck No.: 4 Ticket No.: 292

Field Test Data

Test	Result	Specification
Slump (in):	4 3/4	
Air Content (%):	1.2	
Concrete Temp. (F):	74	
Ambient Temp. (F):	63	
Plastic Unit Wt. (pcf):	147.2	
Yield (Cu. Yds.):		

Sample Information

Sample Date: 11/05/20 Sample Time: 0820
 Sampled By: Matcek, James
 Weather Conditions: Partly cloudy
 Accumulative Yards: 8.28 Batch Size (cy): 8.28
 Placement Method: Direct Discharge
 Water Added Before (gal): 0
 Water Added After (gal): 0
 Sample Location: 20' West of Southeast end
 Placement Location: Curb

Laboratory Test Data

Set No.	Specimen ID	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Maximum Load (lbs)	Compressive Strength (psi)	Fracture Type	Tested By
1	A	6.00	28.27	11/06/20	12/10/20	35 F	133,780	4,730	1	SLS
1	B	6.00	28.27	11/06/20	12/10/20	35 F	125,810	4,450	1	SLS
1	C	6.00	28.27	11/06/20	12/10/20	35 F	127,600	4,510	1	SLS
1	D			11/06/20		Hold				

Initial Cure: Outside

Final Cure: Field Cured

Comments: F = Field Cured

Samples Made By: Terracon

Services: Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

Terracon Rep.: Matcek, James

Start/Stop: 0715-0915

Reported To:

Contractor:

Report Distribution:

(1) Texas Transportation Institute, Gary Gerke (1) Terracon Consultants, Inc., Alex Dunigan, P.E.
 (1) Texas Transportation Institute, Bill Griffith

Reviewed By:

Alexander Dunigan
 Project Manager

Test Methods: ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

TUCKER_concrete

979-777-6749
TRUCK #4
TUCKER CONSTRUCTION
LA_DOT_TTI

TICKET # 340

START DATE: 2020-11-19 TIME: 07:57:42
STOP DATE: 2020-11-19 TIME: 08:41:15

MIX DESIGN: B1350

RAW CEMENT COUNTS: 2227
RAW CONVEYOR COUNTS: 83512
CONVEYOR SPEED: 50
TOTAL YARDS 3.884

MATERIAL	RATE SETTING	TOTAL
CEMENT	9.343309LBS	1825.695
SAND	6.013903 GA	5946.61L
ADJUSTED:		
STONE	7.916514 GA	8213.006
ADJUSTED:		
WATER	23.58288GAL	92.5162G
ADMIX #1	0.00Z/MIN	0.00Z
ADMIX #2	0.00Z/MIN	0.00Z
ADMIX #3	268.3716OZ/	909.8145
TOTAL SAND MOISTURE:	0.0	
TOTAL STONE MOISTURE:	0.0	

Name _____

NOTES:

CONCRETE COMPRESSIVE STRENGTH TEST REPORT

Report Number: A1171057.0155
 Service Date: 11/19/20
 Report Date: 11/19/20
 Task: 606861-3 (LADOT)

Terracon
 6198 Imperial Loop
 College Station, TX 77845-5765
 979-846-3767 Reg No: F-3272

Client

Texas Transportation Institute
 Attn: Gary Gerke
 TTI Business Office
 3135 TAMU
 College Station, TX 77843-3135

Project

Riverside Campus
 Riverside Campus
 Bryan, TX

Project Number: A1171057

Material Information

Specified Strength: 3,000 psi @ 28 days

Mix ID: B1350
 Supplier: Tucker
 Batch Time: 0700
 Truck No.: 4
 Plant:
 Ticket No.: 340

Field Test Data

Test	Result	Specification
Slump (in):	6 3/4	
Air Content (%):	2.5	
Concrete Temp. (F):	69	
Ambient Temp. (F):	54	
Plastic Unit Wt. (pcf):	145.8	
Yield (Cu. Yds.):		

Sample Information

Sample Date: 11/19/20 Sample Time: 0712
 Sampled By: Cullen Turney
 Weather Conditions: Cloudy, no wind
 Accumulative Yards: 10/10 Batch Size (cy): 10
 Placement Method: Direct Discharge
 Water Added Before (gal): 0
 Water Added After (gal): 0
 Sample Location: 10' west of Southeast end
 Placement Location: 606861-3 half wall

Laboratory Test Data

Set No.	Specimen ID	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Maximum Load (lbs)	Compressive Strength (psi)	Fracture Type	Tested By
1	A	6.00	28.27	11/19/20	12/10/20	21 F	113,160	4,000	2	SLS
1	B	6.00	28.27	11/19/20	12/10/20	21 F	111,410	3,940	1	SLS
1	C	6.00	28.27	11/19/20	12/10/20	21 F	117,530	4,160	2	SLS
1	D			11/19/20		Hold				

Initial Cure: Outside

Final Cure: Field Cured

Comments: F = Field Cured

Samples Made By: Terracon

Services: Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

Terracon Rep.: Cullen Turney

Start/Stop: 0600-1000

Reported To:

Contractor:

Report Distribution:

(1) Texas Transportation Institute, Gary Gerke (1) Terracon Consultants, Inc., Alex Dunigan, P.E.
 (1) Texas Transportation Institute, Bill Griffith

Reviewed By:


 Alexander Dunigan
 Project Manager

Test Methods: ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Appendix J. MASH Test 3-11 (Crash Test No. 606861-3)

Figure 127. Vehicle properties for Test No. 606861-3

Date: 2020-12-14 Test No.: 606861-3 VIN No.: 1C6RR6GT0ES287150
 Year: 2014 Make: RAM Model: _____
 Tire Size: 265/70 R 17 Tire Inflation Pressure: 35 psi
 Tread Type: Highway Odometer: 118074
 Note any damage to the vehicle prior to test: None

• Denotes accelerometer location.

NOTES: None

Engine Type: V-8
 Engine CID: 5.7L

Transmission Type:
 Auto or Manual
 FWD RWD 4WD

Optional Equipment:
None

Dummy Data:
 Type: 50th percentile male
 Mass: 165 lb
 Seat Position: IMPACT SIDE

Geometry: inches

A	<u>78.50</u>	F	<u>40.00</u>	K	<u>20.00</u>	P	<u>3.00</u>	U	<u>26.75</u>
B	<u>74.00</u>	G	<u>28.50</u>	L	<u>30.00</u>	Q	<u>30.50</u>	V	<u>30.25</u>
C	<u>227.50</u>	H	<u>61.46</u>	M	<u>68.50</u>	R	<u>18.00</u>	W	<u>61.40</u>
D	<u>44.00</u>	I	<u>11.75</u>	N	<u>68.00</u>	S	<u>13.00</u>	X	<u>79.00</u>
E	<u>140.50</u>	J	<u>27.00</u>	O	<u>46.00</u>	T	<u>77.00</u>		
Wheel Center Height Front	<u>14.75</u>	Wheel Well Clearance (Front)	<u>6.00</u>	Bottom Frame Height - Front	<u>12.50</u>				
Wheel Center Height Rear	<u>14.75</u>	Wheel Well Clearance (Rear)	<u>9.25</u>	Bottom Frame Height - Rear	<u>22.50</u>				

RANGE LIMIT: A=78 ±2 inches; C=237 ±13 inches; E=148 ±12 inches; F=39 ±3 inches; G = > 28 inches; H = 63 ±4 inches; O=43 ±4 inches; (M+N)/2=67 ±1.5 inches

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static
Front <u>3700</u>	M_{front}	<u>2925</u>	<u>2844</u>	<u>2929</u>
Back <u>3900</u>	M_{rear}	<u>2131</u>	<u>2212</u>	<u>2292</u>
Total <u>6700</u>	M_{Total}	<u>5056</u>	<u>5056</u>	<u>5221</u>

(Allowable Range for TIM and GSM = 5000 lb ±110 lb)

Mass Distribution:	lb	LF:	RF:	LR:	RR:
		<u>1430</u>	<u>1414</u>	<u>1154</u>	<u>1058</u>




Figure 128. Measurement of vehicle vertical CG for Test No. 606861-3

Date: 2020-12-14 Test No.: 606861-3 VIN: 1C6RR6GT0ES287150
 Year: 2014 Make: RAM Model: 1500
 Body Style: Quad Cab Mileage: 118074
 Engine: 5.7L V-8 Transmission: Automatic
 Fuel Level: Empty Ballast: 140 (440 lb max)
 Tire Pressure: Front: 35 psi Rear: 35 psi Size: 265/70 R 17

Measured Vehicle Weights: (lb)			
LF:	<u>1430</u>	RF:	<u>1414</u>
Front Axle:		<u>2844</u>	
LR:	<u>1154</u>	RR:	<u>1058</u>
Rear Axle:		<u>2212</u>	
Left:	<u>2584</u>	Right:	<u>2472</u>
Total:		<u>5056</u>	
5000 ±110 lb allowed			
Wheel Base:	<u>140.50</u> inches	Track: F:	<u>68.50</u> inches
148 ±12 inches allowed		R:	<u>68.00</u> inches
Track = (F+R)/2 = 67 ±1.5 inches allowed			
Center of Gravity, SAE J874 Suspension Method			
X:	<u>61.47</u> inches	Rear of Front Axle	(63 ±4 inches allowed)
Y:	<u>-0.76</u> inches	Left -	Right + of Vehicle Centerline
Z:	<u>28.5</u> inches	Above Ground	(mininum 28.0 inches allowed)

Hood Height: 46.00 inches Front Bumper Height: 27.00 inches
 43 ±4 inches allowed

Front Overhang: 40.00 inches Rear Bumper Height: 30.00 inches
 39 ±3 inches allowed

Overall Length: 227.50 inches
 237 ±13 inches allowed


Figure 129. Sequential photographs for Test No. 606861-3 (overhead view).



0.000 s




0.400 s



0.100 s




0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

Figure 130. Sequential photographs for Test No. 606861-3 (frontal view).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

Figure 131. Sequential photographs for Test No. 606861-3 (rear view).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

Figure 132. Exterior crush measurements for Test No. 606861-3

Date: 2020-12-14 Test No.: 606861-3 VIN No.: 1C6RR6GT0ES287150
 Year: 2014 Make: RAM Model: 1500

VEHICLE CRUSH MEASUREMENT SHEET¹

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____	Bowing: B1 _____ X1 _____
Corner shift: A1 _____	B2 _____ X2 _____
A2 _____	
End shift at frame (CDC)	Bowing constant
(check one)	$\frac{X1 + X2}{2} =$ _____
< 4 inches _____	
≥ 4 inches _____	

Note: Measure C₁ to C₆ from Driver to Passenger Side in Front or Rear Impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L**	C ₁	C ₂	C ₃	C ₄	C ₅	C ₆	±D
		Width*** (CDC)	Max**** Crush								
1	Front plane at bmp ht	16	11.0	40	-	-	-	-	-	-	18
2	Side plane at bmp ht	16	9.0	56	-	-	-	-	-	-	78
	Measurements recorded										
	<input checked="" type="checkbox"/> inches or <input type="checkbox"/> mm										

¹Table taken from National Accident Sampling System (NASS).

*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.


**Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

***Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

Figure 133. Occupant compartment measurements for Test No. 606861-3

Date: 2020-12-14 Test No.: 606861-3 VIN No.: 1C6RR6GT0ES287150
 Year: 2014 Make: RAM Model: 1500



OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT

	Before	After (inches)	Differ.
A1	65.00	65.00	0.00
A2	63.00	63.00	0.00
A3	65.50	65.50	0.00
B1	45.00	45.00	0.00
B2	38.00	38.00	0.00
B3	45.00	45.00	0.00
B4	39.50	39.50	0.00
B5	43.00	43.00	0.00
B6	39.50	39.50	0.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	26.00	0.00
D1	11.00	11.00	0.00
D2	0.00	0.00	0.00
D3	11.50	11.50	0.00
E1	58.50	58.50	0.00
E2	63.50	63.50	0.00
E3	63.50	63.50	0.00
E4	63.50	63.50	0.00
F	59.00	59.00	0.00
G	59.00	59.00	0.00
H	37.50	37.50	0.00
I	37.50	37.50	0.00
J*	25.00	25.00	0.00

*Lateral area across the cab from driver's side kickpanel to passenger's side kickpanel.

Figure 134. Vehicle angular displacements for Test No. 606861-3




Figure 135. Vehicle longitudinal accelerometer trace for Test No. 606861-3 (accelerometer located at center of gravity)




Figure 136. Vehicle lateral accelerometer trace for Test No. 606861-3 (accelerometer located at center of gravity)





Figure 137. Vehicle vertical accelerometer trace for Test No. 606861-3 (accelerometer located at center of gravity)



Appendix K. MASH Test 3-10 (Crash Test No. 606861-4)

Figure 138. Vehicle properties for Test No. 606861-4

Date: 2020-12-11 Test No.: 606861-4 VIN No.: 3N1CN7APOEL862280
 Year: 2014 Make: NISSAN Model: VERSA
 Tire Inflation Pressure: 36 PSI Odometer: 91861-4 Tire Size: P185/65R15

Describe any damage to the vehicle prior to test: None

• Denotes accelerometer location.



NOTES: None

Engine Type: 4 CYL
 Engine CID: 1.6 L

Transmission Type:
 Auto or Manual
 FWD RWD 4WD

Optional Equipment:
None

Dummy Data:
 Type: 50th Percentile Male
 Mass: 165 lb
 Seat Position: IMPACT SIDE



Geometry: inches

A <u>66.70</u>	F <u>32.50</u>	K <u>12.50</u>	P <u>4.50</u>	U <u>15.50</u>
B <u>59.60</u>	G _____	L <u>26.00</u>	Q <u>24.00</u>	V <u>21.25</u>
C <u>175.40</u>	H <u>42.15</u>	M <u>58.30</u>	R <u>16.25</u>	W <u>42.10</u>
D <u>40.50</u>	I <u>7.00</u>	N <u>58.50</u>	S <u>7.50</u>	X <u>79.75</u>
E <u>102.40</u>	J <u>22.25</u>	O <u>30.50</u>	T <u>64.50</u>	
Wheel Center Ht Front <u>11.50</u>	Wheel Center Ht Rear <u>11.50</u>	W-H <u>-0.05</u>		

RANGE LIMIT: A = 65 ±3 inches; C = 169 ±8 inches; E = 98 ±5 inches; F = 35 ±4 inches; H = 39 ±4 inches; O (Top of Radiator Support) = 28 ±4 inches (M+N)/2 = 59 ±2 inches; W-H < 2 inches or use MASH Paragraph A4.3.2

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static
Front <u>1750</u>	M _{front}	<u>1369</u>	<u>1425</u>	<u>1510</u>
Back <u>1687</u>	M _{rear}	<u>974</u>	<u>979</u>	<u>1077</u>
Total <u>3389</u>	M _{Total}	<u>2343</u>	<u>2404</u>	<u>2587</u>


Allowable TIM = 2420 lb ±55 lb | Allowable GSM = 2585 lb ± 55 lb

Mass Distribution:
 lb LF: 706 RF: 719 LR: 502 RR: 477

Figure 139. Sequential photographs for Test No. 606861-4 (overhead view).



0.000 s




0.400 s



0.100 s



0.500 s




0.200 s



0.600 s



0.300 s



0.700 s

Figure 140. Sequential photographs for Test No. 606861-4 (frontal view).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

Figure 141. Sequential photographs for Test No. 606861-4 (rear view).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

Figure 142. Exterior crush measurements for Test No. 606861-4

Date: 2020-12-11 Test No.: 606861-4 VIN No.: 3N1CN7APOEL862280
 Year: 2014 Make: NISSAN Model: VERSA

VEHICLE CRUSH MEASUREMENT SHEET¹

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____ Corner shift: A1 _____ A2 _____ End shift at frame (CDC) (check one) < 4 inches _____ ≥ 4 inches _____	Bowing: B1 _____ X1 _____ B2 _____ X2 _____ Bowing constant $\frac{X1 + X2}{2} = \underline{\hspace{2cm}}$

Note: Measure C₁ to C₆ from Driver to Passenger Side in Front or Rear Impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L***	C ₁	C ₂	C ₃	C ₄	C ₅	C ₆	±D
		Width** (CDC)	Max**** Crush								
1	Front plane at bumper ht	14	9.0	30	-	-	-	-	-	-	11
2	Side plane at bumper ht	14	6.0	44	-	-	-	-	-	-	60
	Measurements recorded										
	<input checked="" type="checkbox"/> inches or <input type="checkbox"/> mm										

¹Table taken from National Accident Sampling System (NASS).

*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.




**Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

***Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

Figure 143. Occupant compartment measurements for Test No. 606861-4

Date: 2020-12-11 Test No.: 606861-4 VIN No.: 3N1CN7APOEL862280
 Year: 2014 Make: NISSAN Model: VERSA



OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT

	Before	After (inches)	Differ.
A1	75.00	75.00	0.00
A2	74.00	74.00	0.00
A3	74.00	74.00	0.00
B1	43.00	43.00	0.00
B2	37.00	37.00	0.00
B3	43.00	43.00	0.00
B4	46.50	46.50	0.00
B5	42.50	42.50	0.00
B6	46.50	46.50	0.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	26.00	0.00
D1	12.50	12.50	0.00
D2	0.00	0.00	0.00
D3	10.00	9.50	-0.50
E1	45.00	45.00	0.00
E2	48.75	48.75	0.00
F	47.50	47.50	0.00
G	47.50	47.50	0.00
H	39.00	39.00	0.00
I	39.00	39.00	0.00
J*	48.50	48.00	-0.50

*Lateral area across the cab from driver's side kick panel to passenger's side kick panel.

Figure 144. Vehicle angular displacements for Test No. 606861-4




Figure 145. Vehicle longitudinal accelerometer trace for Test No. 606861-4 (accelerometer located at center of gravity)




Figure 146. Vehicle lateral accelerometer trace for Test No. 606861-4 (accelerometer located at center of gravity)





Figure 147. Vehicle vertical accelerometer trace for Test No. 606861-4 (accelerometer located at center of gravity)



This public document is published at a total cost of \$200. 29 copies of this public document were published in this first printing at a cost of \$200. The total cost of all printings of this document including reprints is \$200. This document was published by Louisiana Transportation Research Center to report and publish research findings as required in R.S. 48:105. This material was duplicated in accordance with standards for printing by state agencies established pursuant to R.S. 43:31. Printing of this material was purchased in accordance with the provisions of Title 43 of the Louisiana Revised Statutes.