



U.S. Department
of Transportation
**Federal Aviation
Administration**

Advisory Circular

Subject: Change 19 to STANDARDS FOR
SPECIFYING CONSTRUCTION OF AIRPORTS--
Updates Excavation and Embankment
Specification

Date: 4/8/83
Initiated by: AAS-200

AC No: 150/5370-10
Change: 19

1. PURPOSE. Item P-152, Excavation and Embankment, has been extensively revised and rewritten in guide specification format. Reference to FAA Test 611 Compaction and Control Tests has been deleted, and a paragraph on rock fill has been added.

The Change number and date of change are carried at the top of each page.

PAGE CONTROL CHART

Remove Pages	Dated	Insert Pages	Dated
77-88	10/24/74	77-88	4/8/83
		88-1 thru 88-2	4/8/83

LEONARD E. MUDD
Director, Office of Airport Standards

M-4946

TRANSMITTAL SHEET

SUBJECT: Change 18 and Change 19 to AC 150/5370-10, Standards for
Specifying Construction of Airports

1. PURPOSE: This sheet transmits changes 18 and 19 to subject
advisory circular.

2. ACTION: Follow the directions on the page control charts for each
change for proper page inserts to the basic advisory circular.

Distribution: STD AC 150 Series

Initiated by: AAS-200

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

1. DESCRIPTION

3

1.1 This item covers excavation, disposal, placement, and compaction of all materials within the limits of the work required to construct runway safety areas, runways, taxiways, aprons, and intermediate, as well as other areas for drainage, building construction, parking, or other purposes in accordance with these specifications and in conformity to the dimensions and typical section shown on the plans.

8

8

11

14

17

18

18

1.2 CLASSIFICATION. All material excavated shall be classified as defined below:

21

21

(a) Unclassified Excavation. Unclassified excavation shall consist of the excavation and disposal of all material, regardless of its nature, which is not otherwise classified and paid for under the following items.

24

24

26

26

(b) Rock Excavation. Rock excavation shall include all solid rock in ledges, in bedded deposits, in unstratified masses, and conglomerate deposits which are so firmly cemented they cannot be removed without blasting or using rippers. All boulders containing a volume of more than 1/2 cubic yard (0.4 cubic meter) will be classified as "rock excavation".

29

31

32

34

34

35

(c) Muck Excavation. Muck excavation shall consist of the removal and disposal of deposits of mixtures of soils and organic matter not suitable for foundation material. Muck shall include materials which will decay or produce subsidence in the embankment. It may be made up of decaying stumps, roots, logs, humus, or other material not satisfactory for incorporation in the embankment.

38

39

40

40

43

45

45

(d) Drainage Excavation. Drainage excavation shall consist of all excavation made for the primary purpose of drainage and includes drainage ditches, such as intercepting, inlet or outlet; temporary levee construction; or any other type as shown on the plans.

48

49

51

53

53

(e) Borrow Excavation. Borrow excavation shall consist of approved material required for the construction of embankment or for other portions of the work in excess of the quantity of usable material available from required excavations. Borrow material shall be obtained from areas within the limits of the airport property but outside the normal limits of necessary grading, or from areas outside the airport.

56

57

57

59

59

60

61

65.1

All material excavated shall be considered "unclassified" unless the Engineer specifies other classifications in the project specifications.

66

67

67

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

Delete the classifications not applicable to a project.

69

70.2

1.3 Unsuitable Excavation. Any material containing vegetable or organic matter, such as muck, peat, organic silt, or sod shall be considered unsuitable for use in embankment construction. Material, when approved by the Engineer as suitable to support vegetation, may be used on the embankment slope.

76

80

80

82

83

2. CONSTRUCTION METHODS.

85

2.1 GENERAL. Before beginning excavation, grading, and embankment operations in any area, the area shall be completely cleared and grubbed in accordance with Item P-151.

90

91

92

The suitability of material to be placed in embankments shall be subject to approval by the Engineer. All unsuitable material shall be disposed of in waste areas shown on the plans. All waste areas shall be graded to allow positive drainage of the area and of adjacent areas. The surface elevation of waste areas shall not extend above the surface elevation of adjacent usable areas of the airport, unless specified on the plans or approved by the Engineer.

94

96

97

97

98

98

100

100

When the Contractor's excavating operations encounter artifacts of historical or archeological significance, the operations shall be temporarily discontinued. At the direction of the Engineer, the Contractor shall excavate the site in such a manner as to preserve the artifacts encountered and allow for their removal. Such excavation will be paid for as extra work.

102

104

105

106

107

108

Those areas outside of the pavement areas in which the top layer of soil material has become compacted, by hauling or other activities of the Contractor shall be scarified and disked to a depth of 4 inches (10 cm), in order to loosen and pulverize the soil.

110

111

112

113

113

If it is necessary to interrupt existing surface drainage, sewers or under-drainage, conduits, utilities, or similar underground structures the Contractor shall be responsible for and shall take all necessary precautions to preserve them or provide temporary services. When such facilities are encountered, the Contractor shall notify the Engineer, who shall arrange for their removal if necessary. The Contractor shall, at his/her own expense, satisfactorily repair or pay the cost of all damage to such facilities or structures which may result from any of the Contractor's operations during the period of the contract.

116

119

120

121

123

125

127

128

129

129

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

2.2 EXCAVATION. No excavation shall be started until the work has been staked out by the Contractor and the Engineer has obtained elevations and measurements of the ground surface. All suitable excavated material shall be used in the formation of embankment, subgrade, or for other purposes shown on the plans. All unsuitable material shall be disposed of as shown on the plans.

When the volume of the excavation exceeds that required to construct the embankments to the grades indicated, the excess shall be used to grade the areas of ultimate development or disposed of as directed. When the volume of excavation is not sufficient for constructing the fill to the grades indicated, the deficiency shall be obtained from borrow areas.

The grade shall be maintained so that the surface is well drained at all times. When necessary, temporary drains and drainage ditches shall be installed to intercept or divert surface water which may affect the work.

(a) Selective Grading. When selective grading is indicated on the plans, the more suitable material as designated by the Engineer shall be used in constructing the embankment or in capping the pavement subgrade. If, at the time of excavation, it is not possible to place this material in its final location, it shall be stockpiled in approved areas so that it can be measured for payment for rehandling as specified in Paragraph 3.3.

(b) Undercutting. Rock, shale, hardpan, loose rock, boulders, or other material unsatisfactory for runway safety areas, subgrades, roads, shoulders, or any areas intended for turbing shall be excavated to a minimum depth of 12 inches (30 cm), or to the depth specified by the Engineer, below the subgrade. Muck, peat, matted roots, or other yielding material, unsatisfactory for subgrade foundation, shall be removed to the depth specified. Unsuitable materials shall be disposed of at locations shown on the plans. This excavated material shall be paid for at the contract unit price per cubic yard (per cubic meter) for [**_____]. The excavated area shall be refilled with suitable material, obtained from the grading operations or borrow areas and thoroughly compacted by rolling. The necessary refilling will constitute a part of the embankment. Where rock cuts are made and refilled with selected material, any pockets created in the rock surface shall be drained in accordance with the details shown on the plans.

The Engineer shall specify the appropriate class of excavation. If rock or muck excavation is not included under paragraph 1.2, unclassified excavation should be specified.

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

The plans shall show details for draining pockets created in rock cuts.

197

197

198.2

(c) Overbreak. Overbreak, including slides, is that portion of any material displaced or loosened beyond the finished work as planned or authorized by the Engineer. The Engineer shall determine if the displacement of such material was unavoidable and his/her decision shall be final. All overbreak shall be graded or removed by the Contractor and disposed of as directed; however, payment will not be made for the removal and disposal of overbreak which the Engineer determines as avoidable. Unavoidable overbreak will be classified as "Unclassified Excavation".

206

206

208

208

209

209

211

211

212

212

(d) Removal of Utilities. The removal of existing structures and utilities required to permit the orderly progress of work will be accomplished by someone other than the Contractor, e.g., the utility unless otherwise shown on the plans. All existing foundations shall be excavated for at least 2 feet (0.6 m) below the top of subgrade or as indicated on the plans, and the material disposed of as directed. All foundations thus excavated shall be backfilled with suitable material and compacted as specified herein.

215

216

216

218

219

220

222

222

222

(e) Compaction Requirements. The subgrade under areas to be paved shall be compacted to a depth of [**] and to a density of not less than [**] percent of the maximum density as determined by ASTM [**].

225

227

229

230

234.1

Subgrades Under Flexible Pavements. The Engineer shall specify compaction to a depth of 6 inches (15 cm) and to a density of not less than 95 percent for cohesive soils or 100 percent for noncohesive soils for areas serving single gear aircraft. For areas serving dual gear or dual tandem gear aircraft the Engineer shall specify the required compaction depths and densities as determined from AC 150/5320-6, Chapter 3, Section 2.

236

236

237

238

239

239

240

242

Subgrades Under Rigid Pavements. The Engineer shall specify the compaction depth and densities as determined from AC 150/5320-6, Chapter 3, Section 3.

245

246

248

The Engineer shall specify ASTM D698 for areas designated for aircraft with gross weights of 60,000 pounds (26 000 Kg) or less, and ASTM D1557 for areas designated for aircraft with gross weights greater than 60,000 pounds (26 000 Kg).

250

251

253

253

254.2

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

Payment for suitable materials removed, manipulated, and replaced in order to obtain the required depth of density will be paid for as unclassified excavation.

261

261

261

The in-place field density shall be determined in accordance with ASTM D1556 or ASTM D2167. Stones or rock fragments larger than 4 inches (10 cm) in their greatest dimension will not be permitted in the top 6 inches (15 cm) of the subgrade. The finished grading operations, conforming to the typical cross section, shall be completed and maintained at least 1,000 feet (305 m) ahead of the paving operations or as directed by the Engineer.

263

264

265

266

267

269

269

In cuts, all loose or protruding rocks on the back slopes shall be barred loose or otherwise removed to line of finished grade of slope. All cut-and-fill slopes shall be uniformly dressed to the slope, cross section, and alignment shown on the plans or as directed by the Engineer.

272

273

274

276

276

Blasting will be permitted only when proper precautions are taken for the safety of all persons, the work, and the property. All damage done to the work or property shall be repaired at the Contractor's expense. All operations of the Contractor in connection with the transportation, storage, and use of explosives shall conform to all State and local regulations and explosive manufacturers' instructions, with applicable approved permits reviewed by the Engineer. Any approval given, however, will not relieve the Contractor of his responsibility in blasting operations.

278

282

282

283

285

286

286

287

287

287

Where blasting is approved, the Contractor shall employ a vibration consultant, approved by the Engineer, to advise on explosive charge weights per delay and to analyze records from seismograph recordings. The seismograph shall be capable of producing a permanent record of the three components of the motion in terms of particle velocity, and in addition shall be capable of internal dynamic calibration.

290

292

292

293

294

295

295

In each distinct blasting area, where pertinent factors affecting blast vibrations and their effects in the area remain the same, the Contractor shall submit a blasting plan of the initial blasts to the Engineer for approval. This plan must consist of hole size, depth, spacing, burden, type of explosives, type of delay sequence, maximum amount of explosive on any one delay period, depth of rock, and depth of overburden if any. The maximum explosive charge weights per delay included in the plan shall not be increased without the approval of the Engineer.

298

298

299

300

305

306

309

309

310

The Contractor shall keep a record of each blast fired -- its date, time and location; the amount of explosives used, maximum explosive charge weight per delay period, and, where necessary, seismograph records identified by instrument number and location.

313

316

318

319

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

These records shall be made available to the Engineer on a monthly basis or in tabulated form at other times as required.

321

321

2.3 BORROW EXCAVATION. Borrow area(s) within the airport property are indicated on the plans. Borrow excavation shall be made only at these designated locations and within the horizontal and vertical limits as staked or as directed.

324

325

325

326

When borrow sources are outside the boundaries of the airport property, it shall be the Contractor's responsibility to locate and obtain the supply, subject to the approval of the Engineer. The Contractor shall notify the Engineer, at least 15 days prior to beginning the excavation, so necessary measurements and tests can be made. All unsuitable material shall be disposed of by the Contractor. All borrow pits shall be opened up to expose the vertical face of various strata of acceptable material to enable obtaining a uniform product. Borrow pits shall be excavated to regular lines to permit accurate measurements, and they shall be drained and left in a neat, presentable condition with all slopes dressed uniformly.

328

329

330

332

333

334

335

336

337

338

338

338

2.4 DRAINAGE EXCAVATION. Drainage excavation shall consist of excavating for drainage ditches such as intercepting, inlet or outlet; for temporary levee construction; or for any other type as designed or as shown on the plans. The work shall be performed in the proper sequence with the other construction. All satisfactory material shall be placed in fills; unsuitable material shall be placed in waste areas or as directed. Intercepting ditches shall be constructed prior to starting adjacent excavation operations. All necessary work shall be performed to secure a finish true to line, elevation, and cross section.

341

342

344

345

345

347

347

348

349

351

351

The Contractor shall maintain ditches constructed on the project to the required cross section and shall keep them free of debris or obstructions until the project is accepted.

353

354

354

2.5 PREPARATION OF EMBANKMENT AREA. Where an embankment is to be constructed to a height of 4 feet (1.2 meters) or less, all sod and vegetable matter shall be removed from the surface upon which the embankment is to be placed, and the cleared surface shall be completely broken up by plowing or scarifying to a minimum depth of 6 inches (150 mm). This area shall then be compacted as indicated in Paragraph 2.6. When the height of fill is greater than 4 feet (1.2 meters), sod not required to be removed shall be thoroughly disked and recompact to the density of the surrounding ground before construction of embankment.

357

358

358

359

360

361

362

363

364

364

Where embankments are to be placed on natural slopes steeper than 3 to 1, horizontal benches shall be constructed as shown on the plans.

366

367

367

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

*****	371.1
The Engineer shall include benching details on the plans	372
based on the type of material, degree of consolidation of	373
the material, and the degree of homogeneity of the material.	374
The minimum width of the bench shall be sufficient to	375
accommodate construction equipment.	375
*****	376.2
No direct payment shall be made for the work performed under this	381
section. The necessary clearing and grubbing and the quantity of	382
excavation removed will be paid for under the respective items of	382
work.	382
2.6 FORMATION OF EMBANKMENTS. Embankments shall be formed in	385
successive horizontal layers of not more than 8 inches (20 cm) in	386
loose depth for the full width of the cross section, unless	387
otherwise approved to the Engineer.	387
The grading operations shall be conducted, and the various soil	390
strata shall be placed, to produce a soil structure as shown on	391
the typical cross section or as directed. Materials such as	392
brush, hedge, roots, stumps, grass and other organic matter,	396
shall not be incorporated or buried in the embankment.	397
Operations on earthwork shall be suspended at any time when	399
satisfactory results cannot be obtained because of rain,	400
freezing, or other unsatisfactory conditions of the field. The	403
Contractor shall drag, blade, or slope the embankment to provide	405
proper surface drainage.	405
The material in the layer shall be within +/- 2 percent of	407
optimum moisture content before rolling to obtain the prescribed	408
compaction. In order to achieve a uniform moisture content	409
throughout the layer, wetting or drying of the material and	410
manipulation shall be required when necessary. Should the	411
material be too wet to permit proper compaction or rolling, all	412
work on all of the affected portions of the embankment shall be	412
delayed until the material has dried to the required moisture	413
content. Sprinkling of dry material to obtain the proper	414
moisture content shall be done with approved equipment that will	414
sufficiently distribute the water. Sufficient equipment to	416
furnish the required water shall be available at all times.	416
Samples of all embankment materials for testing, both before and	418
after placement and compaction, will be taken for each [**_____].	420
Based on these tests, the Contractor shall make the necessary	422
corrections and adjustments in methods, materials or moisture	424
content in order to achieve the correct embankment density.	424

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

It is recommended that density tests be made for each 1000 cubic yards (30 cubic meters) of material placed per layer. The Engineer may specify other frequencies as appropriate to the job size. If it is necessary (because of the presence of expansive soils or other unusually sensitive soils) to apply special controls to the moisture content of the soil during or after compaction to ensure strength, the Engineer shall specify the appropriate moisture content. The moisture limitations shall be specified using acceptable moisture ranges as determined by ASTM D698.

428.1

429

430

431

432

433

433

435

436

436

437

438.2

Rolling operations shall be continued until the embankment is compacted to not less than 95 percent of maximum density for noncohesive soils; and 90 percent of maximum density for cohesive soils as determined by ASTM [**_____] Under all areas to be paved, the embankments shall be compacted to a depth of [**_____] and to a density of not less than [**_____] percent of the maximum density as determined by ASTM [**_____] *****

443

444

445

447

449

452

453

457.1

Subgrade Under Flexible Pavements. The Engineer shall specify the required compaction depths and densities as determined from AC 150/5320-6, Chapter 3, Section 2.

459

459

461

Subgrade Under Rigid Pavements. The Engineer shall specify the required compaction depths and densities as determined from AC 150/5320-6, Chapter 3, Section 3.

464

464

467

The Engineer shall specify ASTM D698 for areas designated for aircraft with gross weights of 60,000 pounds or less and ASTM D1557 for areas designated for aircraft with gross weights greater than 60,000 pounds.

469

470

471

471

For soils with expansive characteristics, the maximum density should be determined in accordance with ASTM D698 regardless of aircraft weight. *****

473

474

474

475.2

On all areas outside of the pavement areas, no compaction will be required on the top 4 inches (10 m).

481

481

The in-place field density shall be determined in accordance with ASTM D1556 or ASTM D2167.

483

483

Compaction areas shall be kept separate, and no layer shall be covered by another until the proper density is obtained.

485

485

During construction of the embankment, the Contractor shall route his equipment at all times, both when loaded and when empty, over the layers as they are placed and shall distribute the travel

488

490

490

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

evenly over the entire width of the embankment. The equipment shall be operated in such a manner that hardpan, cemented gravel, clay, or other chunky soil material will be broken up into small particles and become incorporated with the other material in the layer.

492

493

495

496

496

In the construction of embankments, layer placement shall begin in the deepest portion of the fill; as placement progresses, layers shall be constructed approximately parallel to the finished pavement grade line.

499

500

501

501

When rock and other embankment material are excavated at approximately the same time, the rock shall be incorporated into the outer portion of the embankment and the other material shall be incorporated under the future paved areas. Stones or fragmentary rock larger than 4 inches (10 cm) in their greatest dimensions will not be allowed in the top 6 inches (15 cm) of the subgrade. Rockfill shall be brought up in layers as specified or as directed and every effort shall be exerted to fill the voids with the finer material forming a dense, compact mass. Rock or boulders shall not be disposed of outside the excavation or embankment areas, except at places and in the manner designated by the Engineer.

503

504

505

506

506

507

508

509

511

511

512

512

When the excavated material consists predominantly of rock fragments of such size that the material cannot be placed in layers of the prescribed thickness without crushing, pulverizing or further breaking down the pieces, such material may be placed in the embankment as directed in layers not exceeding 2 feet (0.6 meter) in thickness. Each layer shall be leveled and smoothed with suitable leveling equipment and by distribution of spalls and finer fragments of rock. These type lifts shall not be constructed above an elevation 4 feet (1.2 meters) below the finished subgrade. Density requirements will not apply to portions of embankments constructed of materials which cannot be tested in accordance with specified methods.

514

515

516

517

517

518

519

520

520

521

522

522

Frozen material shall not be placed in the embankment nor shall embankment be placed upon frozen material.

524

524

There will be no separate measurement of payment for compacted embankment, and all costs incidental to placing in layers, compacting, diskings, watering, mixing, sloping, and other necessary operations for construction of embankments will be included in the contract price for excavation, borrow, or other items.

526

527

533

533

536

536

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

540.1

The Engineer may specify payment for compacted "Embankment in Place". In this case, delete the preceeding paragraph and indicate that payment will be made under embankment and that no payment will be made for excavation, borrow, or other items.

541

543

544

546

546

547.2

2.7 FINISHING AND PROTECTION OF SUBGRADE. After the subgrade has been substantially completed the full width shall be conditioned by removing any soft or other unstable material which will not compact properly. The resulting areas and all other low areas, holes or depressions shall be brought to grade with suitable select material. Scarifying, blading, rolling and other methods shall be performed to provide a thoroughly compacted subgrade shaped to the lines and grades shown on the plans.

553

553

554

555

556

559

559

560

Grading of the subgrade shall be performed so that it will drain readily. The Contractor shall take all precautions necessary to protect the subgrade from damage. He/she shall limit hauling over the finished subgrade to that which is essential for construction purposes.

562

563

564

564

564

All ruts or rough places that develop in a completed subgrade shall be smoothed and recompacted.

566

566

No subbase, base, or surface course shall be placed on the subgrade until the subgrade has been approved by the Engineer.

570

570

2.8 HAUL. All hauling will be considered a necessary and incidental part of the work. Its cost shall be considered by the Contractor and included in the contract unit price for the pay of items of work involved. No payment will be made separately or directly for hauling on any part of the work.

573

574

575

576

576

2.9 TOLERANCES. In those areas upon which a subbase or base course is to be placed, the top of the subgrade shall be of such smoothness that, when tested with a 16-foot (5 m) straightedge applied parallel and at right angles to the centerline, it shall not show any deviation in excess of 1/2-inch (1.3 cm), or shall not be more than 0.05-foot (.015 m) from true grade as established by grade hubs or pins. Any deviation in excess of these amounts shall be corrected by loosening, adding, or removing materials; reshaping; and recompacting by sprinkling and rolling.

579

580

581

582

583

583

584

586

588

588

On runway safety areas, intermediate and other designated areas, the surface shall be of such smoothness that it will not vary more than 0.10 foot (0.03 m) from true grade as established by grade hubs. Any deviation in excess of this amount shall be

591

592

593

594

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

corrected by loosening, adding or removing materials, and
reshaping.

596

596

2.10 TOPSOIL. When topsoil is specified or required as shown on the plans or under Item T-905, it shall be salvaged from stripping or other grading operations. The topsoil shall meet the requirements of Item T-905. If, at the time of excavation or stripping, the topsoil cannot be placed in its proper and final section of finished construction, the material shall be stockpiled at approved locations. Stockpiles shall not be placed within [**] feet of runway pavement or [**] feet of taxiway pavement and shall not be placed on areas which subsequently will require any excavation or embankment. If, in the judgement of the Engineer, it is practical to place the salvaged topsoil at the time of excavation or stripping, the material shall be placed in its final position without stockpiling or further rehandling.

599

600

601

603

604

605

606

610

610

612

613

614

614

614

618.1

The Engineer shall specify the appropriate clearances in accordance with AC 150/5370-2, Appendix 1.

619

620

621.2

Upon completion of grading operations, stockpiled topsoil shall be handled and placed as directed, or as required in Item T-905.

627

628

No direct payment will be made for topsoil as such under Item P-152. The quantity removed and placed directly or stockpiled shall be paid for at the contract unit price per cubic yard (per cubic meter) for "Unclassified Excavation".

630

631

632

632

When stockpiling of topsoil and later rehandling of such material is directed by the Engineer, the material so rehandled shall be paid for at the contract unit price per cubic yard (per cubic meter) for "Topsoiling", as provided in Item T-905.

634

635

636

637

3. METHOD OF MEASUREMENT

639

3.1 The quantity of excavation to be paid for shall be the number of cubic yards (cubic meters) measured in its original position.

641

642

642

Measurement shall not include the quantity of material excavated without authorization beyond normal slope lines, or the quantity of material used for purposes other than those directed.

644

646

646

3.2 Borrow material shall be paid for on the basis of the number of cubic yards (cubic meters) measured in its original position at the borrow pit.

648

649

649

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

3.3 Stockpiled material shall be paid for on the basis of the number of cubic yards (cubic meters) measured in the stockpiled position as soon as the material has been stockpiled.

651

652

652

656.1

If the Engineer wishes to specify payment for the quantity of embankment in place in lieu of paying for excavation,

657

657

delete paragraph 3.1 and substitute the following: The

659

quantity of embankment to be paid for shall be the number of

659

cubic yards (cubic meters) measured in its final position.

660

661.2

3.4 For payment specified by the cubic yard (cubic meter), measurement for all [excavation] [embankment] shall be computed by the average end area method. The end area is that bound by the original ground line established by field cross sections and the final theoretical pay line established by [excavation] [embankment] cross sections shown on the plans, subject to verification by the Engineer. After completion of all [excavation] [embankment] operations and prior to the placing of base or subbase material, the final [excavation] [embankment] shall be verified by the Engineer by means of field cross sections taken randomly at intervals not exceeding 500 linear feet (150 meters).

666

669

670

671

672

675

676

679

682

683

684

684

Final field cross sections shall be employed if the following changes have been made:

686

686

(a) Plan width of embankments or excavations are changed by more than plus or minus 1.0 foot (0.3 meter); or

688

688

(b) Plan elevations of embankments or excavations are changed by more than plus or minus 0.5 foot (0.15 meter).

690

690

4. BASIS OF PAYMENT

692

4.1 For "Unclassified Excavation" payment shall be made at the contract unit price per cubic yard (cubic meter). This price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item.

695

696

697

700

4.2 For "Rock Excavation" payment shall be made at the contract unit price per cubic yard (cubic meter). This price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item.

703

704

706

708

4.3 For "Muck Excavation" payment shall be made at the contract unit price per cubic yard (cubic meter). This price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item.

711

712

714

716

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

4.4 For "Drainage Excavation" payment shall be made at the contract unit price per cubic yard (cubic meter). This price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item. 719
720
721
724

4.5 For "Borrow Excavation" payment shall be made at the contract unit price per cubic yard (cubic meter). This price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item. 727
728
729
732

4.6 For "Stockpiled Material" payment shall be made at the contract unit price per cubic yard (cubic meter). This price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item. 735
736
737
740

4.7 For "Embankment in Place" payment shall be made at the contract unit price per cubic yard (cubic meter). This price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item. 743
744
745
748

Payment will be made under: 750

Item P-152-4.1 Unclassified Excavation -- per cubic yard (cubic meter) 752
753

Item P-152-4.2 Rock Excavation -- per cubic yard (cubic meter) 755

Item P-152-4.3 Muck Excavation -- per cubic yard (cubic meter) 757

Item P-152-4.4 Drainage Excavation -- per cubic yard (cubic meter) 759
760

Item P-152-4.5 Borrow Excavation -- per cubic yard (cubic meter) 762
763

Item P-152-4.6 Stockpiled Material -- per cubic yard (cubic meter) 765
766

Item P-152-4.7 Embankment in Place -- per cubic yard (cubic meter) 768
769

***** 774.1

The Engineer shall include only those classifications shown 775

in the bid schedule. 775

***** 776.2

ITEM P-152 EXCAVATION AND EMBANKMENT

1.5

1.6

5. TESTING REQUIREMENTS

781

ASTM D698	Tests for Moisture-Density Relations of Soils	783
	and Soil-Aggregate Mixtures, Using 5.5-pound	784
	(2.5 kg) Rammer and 12-inch (304.8 mm) Drop	785

ASTM D1556	Test for Density of Soil In-Place by the Sand	787
	Cone Method	788

ASTM D1557	Tests for Moisture-Density Relations of Soils	790
	and Soil-Aggregate Mixtures, Using 10-pound	791
	(4.5 kg) Rammer and 18-inch (457 mm) Drop	792

ASTM D2167	Test for Density of Soil In-Place by the	794
	Rubber Balloon Method	795

+ + END OF Item P-152 + +

797.3