MOUNTAIN-PLAINS CONSORTIUM

RESEARCH BRIEF | MPC 24-540 (project 661) | August 2024

Improved Sustainability and Efficiency of Partial-Depth Concrete Bridge Deck Repair



the **ISSUE**

There have been significant advances in the development of rapid setting cementitious materials for partial-depth bridge deck repair. The rapid set times of these materials allow for traffic to be reopened onto the bridge deck in several hours versus days once the material has been placed. However, much time is still spent on removing damaged and deteriorated bridge deck and in preparing the concrete cutouts for placement of the rapid set material. This partial deck removal is a much more delicate process than full deck or pavement roadway removal because the soundness of the concrete surrounding and below the cutout must be maintained. Therefore, the patch preparation process is extremely labor intensive. With the recent development of autonomous machinery, this labor-intensive process could become more efficient. However, prior to developing autonomous machines to prepare the patches, foundational research on methods that reduce the preparation time and that can be easily automated needs to be conducted.

the **RESEARCH**

The study's overall objective is to examine different concrete removal methods to decrease traffic closure time due to the preparation process for partial depth replacement. This effort is intended to improve the efficiency of concrete removal methods as well as evaluate the life cycle sustainability of the techniques. To achieve this objective, the following specific research objectives are identified:

- Identify from the existing literature commonly used concrete patch removal methods used in partial depth bridge deck repair.
- Quantify the removal time for commonly used concrete patch removal methods.

(continued)



A University Transportation Center sponsored by the U.S. Department of Transportation serving the Mountain-Plains Region. Consortium members:



Lead Investigator(s)

Andrew D. Sorenson adsorensen@tamu.edu

Research Assistant(s)

Israi Abu Shanab, GRA PhD

Project Title

Environmentally Sustainable Accelerated Partial Bridge Deck Concrete Removal Methods Analysis

Sponsors | Partners

USDOT, Research and Innovative Technology Administration

the **RESEARCH** (continued)

- Identify additional techniques that decrease the removal time of partial deck patches and that may be automated.
- Determine the environmental sustainability of different concrete removal techniques relative to partial bridge deck removal.
- Determine an optimized removal method that accounts for both the time efficiency and environmental impact.

the **FINDINGS**

Researchers found that increasing the saw cutting lines decreases the jackhammering time for different concrete strengths and increases the concrete removal volume. The saw and patch method can be influenced by many factors, such as the operator's skills and health/energy level, saw blade sharpness, and jackhammer pull-off angle. Method IV, which has the largest number of saw cut lines, is the optimal concrete removal method among the other proposed methods and saves approximately 35% of the required concrete removal time. Also, it has the potential for future automation.

the **IMPACT**

The benefits of this project are reduced lane closure time and decreased environmental impact from partial depth concrete repair.

For more information on this project, download the Main report at https://www.ugpti.org/resources/reports/details.php?id=1183

For more information or additional copies, visit the Web site at www.mountain-plains.org, call (701) 231-7767 or write to Mountain-Plains Consortium, Upper Great Plains Transportation Institute, North Dakota State University, Dept. 2880, PO Box 6050, Fargo, ND 58108-6050.





